

Contract Document Revisions – Addendum-001

SUBJECT

09/06/2013

DATE

Recreation Services Building

PROJECT

640-424

VA PROJECT NO.

Drawing Revisions:

Sheet GI1.1.2	Mounting height for switches, outlets, thermostat, fire alarm and nurse call adjusted.
Sheet CD1.2.1	Updated demo note 15
Sheet CS1.5.1	Removed cross section reference for 18/CS1.8.1
Sheet CS1.8.1	Added concrete splash pad for 51/CS1.8.1
Sheet CS1.8.4	Changed footing in detail to coordinate with architectural plan.
Sheet LP1.1.0	General and Irrigation Notes Clarified
Sheet LP5.1.0	Detail 20: clarifications regarding steel dowel
Sheet LP5.1.2	Detail 22: clarifications regarding pins
Sheet LP5.1.3	Detail 22: clarifications regarding pins
Sheet LP7.2.0	Detail 14 clarified
Sheet SF2.1.0	Revised 1" slab depression extent. Clarify underpinning/shoring extent under (E) building 530. Modify continuous wall footing by (E) building 530 to avoid conflict with potential underpinning.
Sheet SF2.1.1	Clarify underpinning/shoring extent under (E) building 530 with keynote 2.04.
Sheet SF5.1.2	Detail 36 – Revised detail for waterproofing requirements.
Sheet SF7.2.3	Details 50 & 54 – Clarify guardrail post is to be stainless steel. Detail 47 – Revise architectural detail reference.
Sheet AE2.1.2	Removed slope lines at vegetated roofing.
Sheet AE3.1.1	Revised fire sprinkler riser location in kitchen.
Sheet AE4.1.1	Moved camera location at exterior door.
Sheet AE4.1.4	Detail 51: Added graphic representation of connection plates at truss mockup. Added note to call out AESS type. Added gray tone to AESS members. Detail 17: Added graphic to show structural steel below.
Sheet AE4.2.1	Details 51 & 54: Revised graphics to show plate connections and HSS bracing at trusses. Added keynote to truss referencing structural drawings for details.
Sheet AE4.2.2	Details 27 & 54: Revised graphics to show plate connections and HSS bracing at trusses. Added keynote to truss referencing structural drawings for details.
Sheet AE4.3.1	Graphic representation of vegetated roofing system in wall sections revised to match specifications.
Sheet AE4.3.2	Graphic representation of vegetated roofing system in wall section revised to match specifications. Graphic revised for underpinning condition at detail 36.

Sheet AE5.1.0	Clarified detail note.
Sheet AE5.1.1	Vegetated roofing system at rainscreen parapet revised to match specifications.
Sheet AE5.1.2	Detail 18 deleted.
Sheet AE5.1.3	Detail 14: Rainscreen Parapet Cap detail adjusted per structural recommendations. Note revised to match design intent regarding flashing at splice joints. Security camera details added (35 & 51)
Sheet AE5.3.1	Revised detail titles for clarity. Adjusted the underslab waterproofing lap section. Revised footing detail 54 to clarify waterproofing intent.
Sheet AE5.3.2	Removed reference to structural drawings in waterstop note. Revised waterproofing note at elevator pit detail. Revised column footing detail to show leveling nuts.
Sheet AE5.3.3	Detail titles changed for clarification, waterproofing types clarified. Dowels at stair 1 foundation detail shown for clarity.
Sheet AE5.4.1	Vegetated Roof sections updated to match specifications. Roof drain location revised. Detail notes revised to match specification language.
Sheet AE5.4.2	Roof Drains at Vegetated Roof Detail revised to match specifications.
Sheet AE5.4.3	removed detail 39, Isolated Stack Flashing, as it does not apply to this project. Revised waterproofing at roof penetration detail to match specifications.
Sheet AE6.1.1	Finish at intermediate landings revised.
Sheet AE6.1.4	Stair landing material revision.
Sheet AE6.1.7	Waterproofing note clarified.
Sheet AE6.2.1	Elevator section revised at pit level to match structural. Detail callout revised.
Sheet AE6.2.2	Lantern detail revised.
Sheet AE7.0.1	Wall thickness at restroom lavatories revised to match detail.
Sheet AE7.0.3	Sheet note 14 added (drawing and specification reference)
Sheet AE7.1.3	Sheet note 14 added (drawing and specification reference)
Sheet AE7.2.2	Dimension added at interior glazing type F, shifted alignment to exterior mullion.
Sheet AE7.3.1	Shifted floor drains to avoid beam, and added dimension.
Sheet AE8.0.2	Revised restroom lavatory elevations to show counter support brackets.
Sheet AE8.1.1	Fire riser and keynote removed from detail 15.
Sheet AE8.2.2	Television and outlet mounting in Exercise 240 clarified. Revised restroom lavatory elevations to show counter support brackets.
Sheet AE8.3.1	Intermediate landing materials at Stair 1 and Stair 2 revised.
Sheet AE9.2.2	Detail 54 title revised to match detail intent.
Sheet AE9.2.5	Detail 54 revised, extraneous details removed.
Sheet AE9.5.2	Revised countertop mounting detail to coordinate with plumbing design
Sheet AE9.5.3	Paint finish added to plywood at built-in casework (details 44 & 50)
Sheet AE9.7.1	Interior glazing type F revised, detail 48 added.

Sheet QH2.0.1	TELE310 removed from Storage B100A.
Sheet QH2.0.2	TELE310 shown (above) on floor plan. SCBA302 shown (above) on floor plan. Outline of gait track above added to floor plan.
Sheet QH2.1.1	Clarified graphics to match equipment report
Sheet QH2.2.1	Room 250: BOPL300(2) deleted to match equipment report. EXLA300 moved to accommodate clearances around equipment. Location of TELE318 in room 240 clarified.
Sheet MH2.1.0	Added transfer air duct for Vestibule B-105A
Sheet MH2.1.2	Removed gridlines outside of project area.
Sheet PP0.1.1	VRD (vegetated roof drain) and VOD (vegetated overflow drain) added to plumbing symbols legend
Sheet PL2.1.2	Revised vegetated roof drain and overflow drain tags
Sheet FX2.0.0	Revised location of riser from corner of HAC to corner of Storage room
Sheet FX2.1.0	Revised location of riser and floor control assembly from southwest corner of kitchen to northwest corner of kitchen.
Sheet FX6.0.0	Clarification added for drain coordination on detail 45.
Sheet ES0.1.0	Revised / Added miscellaneous Abbreviations Revised General Notes 17 and 23
Sheet EDS1.1.1	Added luminaire demolition Added (E) Manhole
Sheet ES1.1.0	Revised Keynote 1.01
Sheet ES1.1.1	Added empty HV conduits from (E) PMH-28 to (E) PMH-21 Revised routing of ATS signal conduits Added location of (E) Aquatics Main Switchboard Clarified miscellaneous Keynote Tags on plan Clarified ductbank references on Keynotes Added requirements for Aquatics Feeder to Keynote 1.08
Sheet ES1.1.2	Changed luminaire symbol Revised Keynote 1.13
Sheet EP2.1.0	Revised receptacles in Mech Room to GFCI type Removed normal power connection to CHWP controls Revised miscellaneous homerun designations Added mounting height to GFI outlet Revised circuiting to receptacles in Elev Machine Room
Sheet EP2.1.2	Added mounting height to GFI outlet Deleted extraneous enclosures from plan
Sheet EP4.1.1	Added Emergency power to CRP-1 controls Clarified VFD symbol
Sheet EP5.1.1	Added additional Tags to Feeder Schedule Revised feeder from transformer N to Main Switchboard N Revised feeder from transformer E to Emergency Main Breaker Added "Service Entrance Rated" notation to Emergency Main Breaker
Sheet EP6.1.0	Revised Ductbank details 52, 53, and 54 Added Ductbank detail 35

Sheet EP6.1.1	Revised grounding connection for Emergency System
Sheet EP7.1.2	Revised Panel Schedule NB1
Sheet FA0.1.0	Revised fire alarm system device schedule
Sheet FA3.1.2	Deleted wiring to roof and associated keynote on plan
Sheet FA3.1.3	Deleted manual pull station Revised keynote 3.01 to "Not Used"
Sheet FA5.1.1	Revised the fire alarm building riser diagram
Sheet TN2.1.1	Revised outlet at casework in room 131.
Specifications	<p>01 00 00 – Paragraph 1.6-I added for temporary lighting</p> <p>01 91 00 – Replaced entire section</p> <p>03 30 00 – Cement and water factors for concrete table revised.</p> <p>04 72 10 – Deleted IBC 2009 reference under related work</p> <p>Revised paragraph 1.3 quality assurance</p> <p>Added paragraph 1.4-F for LEED submittals</p> <p>Deleted quality assurance and manufacturing tolerances paragraphs</p> <p>Deleted segment wall reference</p> <p>05 40 00 Added backing plates to framing assemblies</p> <p>05 50 00 Added counter support brackets</p> <p>07 42 13.16 – clarified description by adding "exterior"</p> <p>07 55 63 – Revised items F-H, and J under 2.2 Auxiliary Materials. Added item K.</p> <p>Revised 2.6A Vegetated roof assembly by adding components. Deleted unreinforced membrane from paragraph 3.5. Revised 3.5F and added 3.5G & H. Deleted 3.6B, revised 3.6D</p> <p>07 60 00 – Added 2.2H. Added 2.6 for copings.</p> <p>08 44 13 – deleted reference to metal framed skylights. Revised 2.1A-2.</p> <p>09 06 00 – 2.11A section reference revised.</p> <p>22 14 00 – Added roof drain and overflow drain for vegetated roof areas</p> <p>23 07 11 – Edited paragraph for protective insulation to prevent personnel injury. Edited pipe insulation schedule.</p> <p>23 09 23 – Edited system description.</p> <p>32 05 20 – Deleted</p> <p>32 05 23 – added items B, C and D to description. Added references to related work section. Added paragraph for mock-up in submittals section. Revised manufacturer's certificates and data. Added Caltrans to applicable publications. Added pedestrian concrete pavements, stone veneer landscape walls, and Portland cement to products. Revised Subbase, forms, concrete curing materials and expansion joint fillers. Added 3.9 Concrete finishing</p>

pedestrian pavement. Revised liquid membrane curing. Added 3.20 construction waste management.

32 84 00 – Drip system operation indicator added. Butterfly valves deleted. Pressure reducing valve deleted. Emitter access boxes deleted. Strainers deleted. Flow meters added. Moisture sensors added. ET measurement device added. Rain measurement device added. Automatic control equipment revised. Control enclosure pad added. Remote control valves revised. Maintenance and warranties added. Construction Waste Management added.

32 90 00 – 3.6 L added. deleted reference to deer protection, clarified pruning and maintenance period.

33 30 00 – deleted vitrified clay piping. Deleted ductile iron pipe.

33 40 00 – Revised PVD piping.

33 51 00 – revised description. Removed reference to cast in place concrete. Deleted submittals 1.6F, H, I and J. Added general description under products. Revised polyethylene pipe, and fiberglass pipe. Deleted pipe sleeves, gas filter, gas pressure regulators, and meters. Added polyethylene encasement. Revised Part 3 execution.

Appendix C VA Palo Alto Expanded Room by Room Report

Submittal Name, Report Date, and Submittal Date revised.

TELE310 moved from B100A Storage, to B100 Recreation Room

CACO301 added to B100A Storage

CAMU300 deleted from B100A Storage

TABA301 & TABA302 group revised for clarification

DICH300 group revised for clarification

COMA309 name revised and group revised for clarification

TELE348 – number changed to match the number of cybex equipment to which these attach in the room.

EXBA301, TRBA300, & TRST300 moved from AV1 to Room 250 (where shown on equipment plans).

TRBA301 added to room 250.

EXPU301 in room 250 revised to be freestanding as opposed to wall mounted

EXWA300 group revised for clarification