









SUBMITTALS/DELIVERIES



CPM LEGEND

1. THE SAMPLE CPM NETWORKS SHOWN ON THIS DRAWING ARE FOR THE CONTRACTOR'S INFORMATION. THE SAMPLE NETWORKS INDICATE THE LEVEL OF DETAIL AND TECHNIQUE WHICH WILL BE REQUIRED ON THE CONTRACTOR'S NETWORK TO COMPLY WITH THE REQUIREMENTS OF THE 'NAS' SECTION OF THE SPECIFICATIONS. THE CPM LEGEND SHOWN ON THIS DRAWING MUST BE USED BY THE CONTRACTOR IN DEVELOPING AND GRAPHICALLY PORTRAYING HIS NETWORK.

2. THE CONTRACTOR SHOULD REFER TO SPECIFICATIONS SECTIONS:01001(PAYMENT CLAUSES) 01010(1.4D/PHASING) AND 01311(NAS) FOR FURTHER INFORMATION.

3. THE APPROVAL TIME OF LONG-LEAD PROCUREMENT AND JOINT REVIEW ITEMS SHALL REQUIRE MORE THAN THE MINIMUM DURATION OF TWENTY (20) WORK DAYS. THE APPROVAL DURATION FOR ITEMS LISTED UNDER THE SUBMITTALS/DELIVERIES ON DRAWING CPM-1 ARE CONTRACTUAL.

4. THE CONTRACT DURATION IS 630 CALENDAR DAYS.

NOTES

Fully Sprinklered

Revisions	Date

2WR
Watson Watson Rutland / Architects Inc.
166 Commerce Street
P.O. Box 4834
Montgomery, Alabama 36104
205)263-6401

STATE OF ALABAMA — WATSON — WATSON — RUTLAND — REGISTERED ARCHITECTS

Drawing Title	Sample CPM Network
Project Title	Relocate Regional Office to Department Owned Grounds
Date	27 JANUARY 92
Project No.	322-002
Approved—DIRECTOR, CPM STAFF	
Building Number	42
Checked	
Drawn	SAK
Location	VMAC Montgomery, Al.
DRAWING NO.	CPM-1
Dwg. 2 Of 134	

Office of Facilities — Department of Veterans Affairs

VA FORM 08-6231A, JAN 1990

G.P.O. 1991-0-282-421/40,001