

LINE OF CEILING/ TYPICAL

NOTE ALL CENTERLINE OF ALL TILE JOINTS _____
SHALL COINCIDE AS SHOWN HERE.

8x8 MATT FINISHED LIGHT GRAY TILE W/ 1/8" JOINTS
AND NON SANDED LIGHT GRAY GROUT. THIS TILE SHALL BE
THE SAME COLOR, BUT MATT FINISHED AS THE LIGHT
GRAY TILE BELOW ACCENT BAND.

4x8 MATT FINISHED LIGHT GRAY TILE W/ 1/8" JOINTS
AND NON SANDED LIGHT GRAY GROUT. THIS TILE SHALL BE
THE SAME COLOR, BUT MATT FINISHED AS THE LIGHT
GRAY TILE BELOW ACCENT BAND. TOP EDGE OF THIS TILE SHALL
BE A SABITARY RETURN TO WALL.


2x2 ACCENT TILE, AS SELECTED FROM MATT FINISHED PORCELAIN
TILES, ALL MANUFACTURERS AVAILABLE TILE RANGES.

4x4 MATT FINISH WHITE TILE BY SAME MANUFACTURER
AS 4x4 BLACK.

8x8 GLOSS FINISHED WALL TILE, LAID IN A CHECKER
BOARD PATTERN, COLORS TO BE WARM LIGHT GRAY
AND WARM DARK GRAY, SOLID FINISH. LAID W/ 1/8"
GROUT JOINTS/ TO MATCH JOINTS OF 4x4 BELOW, USING
LIGHT GRAY NON SANDED GROUT.

2 ROWS 4x4" GLOSS FINISH BLACK TILE, WITH BOTTOM
ROW TO BE SANITARY BASE AND SANITARY OUTSIDE
CORNER AS OCCURS, WITH BLACK NON SANDED GROUT

FLOOR TILE TO BE 8x8 TEXTURED SLIP RESISTANT FLOOR
TILE WITH GRAY AND WHITE SPECS (COLOR) WITH A
BACKGROUND COLOR OF BLACK, WITH 1/4" JOINTS AND BLACK
SANDED GROUT.



Wassweiler
ARCHITECT
334 221 9736

VA REGIONAL OFFICE
345 PERRY HILL ROAD
MONTGOMERY, ALABAMA

TILE DETAILS

PREFABRICATE METAL
STORAGE BUILDING

1 Jun 2003
322V83034

CENTRAL ALABAMA VETERANS
HEALTH CARE SYSTEM/ WEST CAMPUS

A-1.03
Rev. 10/01 02

