LUMINAIRE SCHEDULE

MARK	LAMPS	VOLTAGE	DESCRIPTION	MANUFACTURER
A	2-54W T5HO	277	LOW PROFILE INDUSTRIAL FIXTURE WITH HIGH-OUTPUT T5 LAMP. MOUNTING: AIRCRAFT CABLE. MOUNT IN COMMON PLANE 12'-0" AFF.	WILLIAMS "84" SERIES OR APPROVED EQUAL
AB	2-54W T5HO	277	SAME AS "A" FIXTURE EXCEPT WITH BATTERY PACK. "AB" FIXTURES ARE NIGHT LIGHTS.	WILLIAMS "84" SERIES OR APPROVED EQUAL
B	2-32W T8	277	4' STRIP FIXTURE WITH WIREGUARD	WILLIAMS SERIES 76 COLUMBIA K4 SERIES OR APPROVED EQUAL
C	2-32W T8	277	2' x 4' RECESSED TROFFER WITH A12 ACRYLIC PRISMATIC LENS	WILLIAMS EP SERIES COLUMBIA 5PS SERIES OR APPROVED EQUAL
CB	2-32W T8	277	SAME AS "C" FIXTURE EXCEPT WITH BATTERY PACK	WILLIAMS EP SERIES COLUMBIA 5PS SERIES OR APPROVED EQUAL
D	1-100W METAL HALIDE MEDIUM BASE	277	WALL-PAK, CORROSION RESISTANT DIE-CAST ALUMINUM HOUSING, ELECTROSTATICALLY APPLIED BRONZE FINISH, SPECULAR ANODIZED ALUMINUM REFLECTOR, PRISMATIC BOROSILICATE GLASS LENS, WITH PHOTOCELL. MOUNT AT 12'-0".	LITHONIA TWH SERIES OR APPROVED EQUAL
F	2-26W QUAD TUBE	277	FLUORESCENT DOWN LIGHT OPEN REFLECTOR BAFFLE, SPECULAR CLEAR ALZAK	INDY 708R OR APPROVED EQUAL
G	2-13W COMPACT FLUORESCENT	277	POLYCARBONATE WALL LANTERN, WHITE ACRYLIC DIFFUSER, BATTERY PACK, UL LISTED FOR WET LOCATIONS. NOTE 5. MOUNT AT 8'-0".	PROGRESS P7192 OR APPROVED EQUAL
X	LED	277	WALL-MOUNTED EXIT LIGHT W/BATTERY	EXCALIBUR LED LITECELL SERIES OR APPROVED EQUAL

FIXTURE SCHEDULE NOTES

1. FIXTURE DESCRIPTION AND PART NUMBER ARE SUPPLEMENTARY. IF ANY DISCREPANCY EXISTS, IT SHALL BE CALLED TO THE ENGINEER'S ATTENTION FOR CLARIFICATION. CONTRACTOR MUST PROVIDE FOR WORST-CASE SITUATION.
2. FIXTURES TO BE FURNISHED COMPLETE WITH ALL LAMPS AND MOUNTING HARDWARE.
3. SEE ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT LOCATION OF FIXTURES.
4. FIXTURE TRIMS ARE TO BE COORDINATED WITH TYPE CEILING IN WHICH THEY MOUNT. PROVIDE MOUNTING HARDWARE AS REQUIRED, SEE ARCHITECTURAL FINISH SCHEDULE.
5. BALLAST SHALL BE ABLE TO POWER BOTH LAMPS. SHALL ALSO BE REQUIRED TO POWER ONE LAMP IN THE EVENT THAT THE OTHER FAILS.

ALABAMA LICENSED NO. 23103 PROFESSIONAL ENGINEER ERIC GARNER, SR.

1/23/03

P:\2002-027.des\EL\027e0202.dwg, (0.5|1), 01/23/03 at 13:27:35 by burtnett

Revisions | Date

VA FORM 08-6231A, MAR 1984

wassweiler ARCHITECTS 334 221 9736

VA REGIONAL OFFICE
345 PERRY HILL ROAD
MONTGOMERY, ALABAMA

Approved:
Approved:
Approved:
Approved:

Drawing Title: LUMINAIRE SCHEDULE AND FIXTURE NOTES

Approved:
Approved:

Project Title: PREFABRICATE METAL STORAGE BUILDING

Building Number | Checked | Drawn: MGB

Location: CENTRAL ALABAMA VETERANS HEALTH CARE SYSTEM/WEST CAMPUS

Date: 1 Jan 2003

Project No. 322VB3034

Drawing No. E-2.2

Dwg. - 01 -