



WALL MOUNTED
ELECTRIC WATER HEATER DETAIL
NOT TO SCALE

LEGEND

- COLD WATER PIPING
- HOT WATER PIPING
- WASTE PIPING
- VENT PIPING
- 3" F.D.-B FLOOR DRAIN - TYPE (SEE SPEC.)
- F.C.O. FLOOR CLEANOUT
- W.C.O. WALL CLEANOUT
- GATE VALVE
- B.F. BELOW FLOOR
- WH WALL HYDRANT
- BACKFLOW PREVENTOR

FIXTURE SCHEDULE

MARK	FIXTURE	CW	HW	W	REMARKS
P-1	TOILET, FLOOR MOUNTED, SIPHON JET	1"	-	4"	HANDICAPPED
P-2	URINAL, WALL HUNG	3/4"	-	2"	HANDICAPPED
P-3	LAVATORY, VITREOUS CHINA,	1/2"	1/2"	1-1/4"	HANDICAPPED
P-4	MOP BASIN	1/2"	1/2"	3"	
P-5	WATER COOLER, CRS. WALL MOUNTED	1/2"	-	1-1/4"	HANDICAPPED

WATER HEATER SCHEDULE

MARK	FIXTURE	KW	VOLTS	PH	GALLONS
WH-1	ELECTRIC WALL MOUNTED WATER HEATER	1.65	208	3	10

Wassweiler
ARCHITECT

VA REGIONAL OFFICE
345 PERRY HILL ROAD
MONTGOMERY, ALABAMA

FLOOR PLAN

PREFABRICATE METAL
STORAGE BUILDING

1 Jan 2003
322VB3034

