


- 072000 - SEALANTS
1. SEALANT SHALL BE ONE OF THE FOLLOWING:
- ASTM D320, POLYURETHANE OR POLYSULFIDE, TYPE M, CLASS MOVEMENT 25, GRADE NS, SHORE A HARDNESS 25-40
  - ASTM D3020, SILICONE NEUTRAL CURE, TYPE S, CLASS MOVEMENT RANGE OF +100% TO -50%, GRADE NS, SHORE A HARDNESS 15-20MINIMUM ELONGATION 1200%
- INTERIOR CAULKING SHALL BE ASTM D384, ACRYLIC LATEX
- SEALANT BACKER SHALL BE TYPE C, CLOSED CELL MATERIAL WITH SURFACE SKIN
- PRIMER SHALL BE AS RECOMMENDED BY THE SEALANT MANUFACTURER.
- THE INSTALLER SHALL BE AN EXPERIENCED INSTALLER IN THE APPLICATION OF JOINT SEALANTS AND SHALL COMPLY WITH THE MANUFACTURER'S PRINTED INSTRUCTIONS.

[illegible]

Drawing Title	
EAST ELEVATION AND MECHANICAL ROOM PLAN	
Approved Project Director	
	Name

Office of  
Construction and  
Facilities  
Management

 Department of  
Veterans Affairs