

Iowa City VA Healthcare System  
400 Car Parking Garage

Description of Deductive Alternates

**Deduct Alternate 3**

Item 12 Division 32 - Exterior Improvements

Delete all shade trees, evergreen trees, ornamental trees deciduous shrubs, evergreen shrubs and perennials.

Item 13 Division 26 - Electrical

Delete all F-11 illuminated bollards (quantity 10), and all associated conduit

- a. Delete two, type F11 luminaires located on the south side of the new parking structure, and DELETE circuit '4301-16' and label breaker as spare.
- b. Delete eight, type F11 luminaires located on the north side of the existing hospital entrance. Circuit '4301-14' is to only be used for the F10 flagpole lighting.

Item 14 Division 12 - Furnishings

Substitute 21 precast bollards with flexible delineator posts.

Item 15 Division 05 - Metals

Substitute chain link fencing, for all painted steel fencing.

Item 16 Division 10 - Specialties

Delete all vehicular directional signage installed within the parking structure.