




1. REFRIGERANT PIPING DOWN TO SPLIT SYSTEM AIR HANDLING UNIT. SEE DRAWING MP104 FOR CONTINUATION. INSTALL REFRIGERANT PIPING PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
2. REFRIGERANT PIPING DOWN TO MEZZANINE LEVEL (SEE DRAWING MP104 FOR CONTINUATION). INSTALL REFRIGERANT PIPING PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.
3. 6" OUTSIDE AIR DUCT UP FROM MEZZANINE TO GOOSENECK. SEE DETAIL. (SEE MP104 FOR CONTINUATION)

THE MECHANICAL CONTRACTOR SHALL TAKE THE LEAD IN PREPARATION OF COORDINATION DRAWINGS. SUCH DRAWINGS SHALL BE ARRANGED AND DESIGNED THROUGHOUT AND FROM COORDINATION WITH ALL OTHER MAJOR AND MINOR SUBCONTRACTORS AND THE GENERAL CONTRACTOR. PROVIDE PLAN VIEW, SECTIONS AND ELEVATIONS AS REQUIRED TO FULLY COORDINATE ALL NEW WORK WITH EXISTING CONDITIONS. DRAW TO SCALE (AT LEAST 1/8" = 1'-0") AND INDICATE ALL DIMENSIONS, MATERIALS, AND LIMITS. PROVIDE THE FOLLOWING RATINGS: ALL DUCTWORK: ALL AIR DISTRIBUTION, MECHANICAL EQUIPMENT, MECHANICAL PIPING, FIRE PROTECTION PIPING, ALL PLUMBING PIPING, CABLE TRAYS (WITH ELEVATIONS NOTED); LIGHTING FIXTURES (WHEN CLIPPING MOUNTED), LIGHTING GRID AND CEILING HEIGHT; MAJOR BEAMS AND JOISTS (WITH ELEVATIONS MARKED); FIRE ALARM DEVICES AND SPEAKERS (WHERE CEILING MOUNTED); ELECTRICAL CONDUITS EQUIPPED WITH 2-INCH DIAMETER, ELECTRICAL BUSWAY AND REQUIRED CLEARANCES; EQUIPMENT WITH 2-INCH DIAMETER, ELECTRICAL BUSWAY AND REQUIRED CLEARANCES. INDICATE LOCATION OR ADDRESS TO ABOVE CEILING PIPING, DUCTWORK OF OTHER EQUIPMENT. SECTIONS SHALL BE CUT THROUGH AREAS SHOWING MATERIALS AND SYSTEMS OF ALL CONTRACTS. IF THERE ARE ANY OUTSTANDING ISSUES THAT CANNOT BE RESOLVED, CONSULT WITH THE ARCHITECT AND/OR ENGINEER (THROUGHOUT THE VA COTR) FOR GUIDANCE AND MAKE CORRECTIONS IN ACCORDANCE WITH DIRECTIONS GIVEN. IT IS IMPORTANT TO NOTE THAT FABRICATION CANNOT BEGIN UNTIL COORDINATION DRAWINGS HAVE BEEN REVIEWED BY ALL MAJOR MATERIAL, EQUIPMENT, SYSTEM OR PRODUCT SUPPLIER. INSTALLATION MONITORED PRIOR TO APPROVAL. BE TAKEN AT THE CONTRACTORS OWN RISK AND MAY HAVE TO BE MODIFIED, MOVED, AND/OR RECONFIGURED AT THE CONTRACTORS COST.



Department of Veterans Affairs
William Jennings Bryan Dorn
VA Medical Center
6439 Garners Ferry Road
Columbia, SC 29209



Drawing Title
MECHANICAL ROOF PLAN
★ BUILDING IS FULLY SPRINKLERED ★

Date APRIL 10, 2012
Project Number 544-11-101
DRAWING No. MP105

