


GENERAL NOTES	
A. SEE SHEET PL001 FOR PLUMBING SYMBOLS AND PIPE LEGEND.	


WALL TYPES LEGEND

— ♦ — ♦ — (2) HOUR FIRE BARRIER

 CMU, SEE ARCHITECTURAL PLANS FOR SIZES

COORDINATION DRAWINGS

THE MECHANICAL CONTRACTOR SHALL TAKE THE LEAD IN PREPARATION OF COORDINATION DRAWINGS. SUCH DRAWINGS SHALL BE ARRANGED AND DESIGNED THROUGHOUT AND COORDINATED WITH ALL OTHER TRADES AND AVOID OVERLAP AND THE GENERAL CONTRACTOR SHALL PROVIDE PLANS, SECTIONS AND ELEVATIONS AS REQUIRED TO FULLY COORDINATE ALL NEW WORK WITH EXISTING CONDITIONS. DRAW TO SCALE (AT LEAST NOT LESS THAN 1/8" = 1'-0"). DRAWINGS SHALL SHOW, BUT NOT BE LIMITED TO, THE FOLLOWING: ALL DUCTWORK, AIR FLOW DISTRIBUTION, MECHANICAL EQUIPMENT; MECHANICAL PIPING; FIRE PROTECTION PIPING; ALL PLUMBING PIPING; CABLE TRAYS (WITH ELEVATIONS NOTED); LIGHTING FIXTURES (WHEN CEILING MOUNTED); CEILING GRID SYSTEMS; HANGERS; HANGING TRAYS; ALL ELECTRICAL, TELEPHONE, AND FIRE ALARM DEVICES AND SPEAKERS (WHEN CEILING MOUNTED); ELECTRICAL CONDUITS, LARGER THAN 2-INCH DIAMETER; ELECTRICAL BUNDLES AND REQUIRED CLEARANCES; EQUIPMENT PROVIDED BY OTHERS THAT PROVIDE INTO CEILING CAVITIES OR IMPIDE THE ACCESS OR ACCESS TO ABOVE CEILING PIPING, DUCTWORK OF OTHER EQUIPMENT. SECTIONS SHALL BE CUT THROUGH AREAS SHOWING MATERIALS AND SYSTEMS OF ALL CONTRACTS. IF THERE ARE ANY OUTSTANDING ISSUES THAT CANNOT BE RESOLVED, CONSULT WITH THE ARCHITECT AND/OR ENGINEER (THROUGH THE VA CTO) FOR CLARIFICATION AND MAKE CORRECTIONS AS ACCORDS WITH THESE INSTRUCTIONS AND NOTIFICATIONS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACCURACY OF ALL INFORMATION. IMPORTANT TO NOTE THAT FABRICATION CANNOT BEGIN UNTIL COORDINATION DRAWINGS HAVE BEEN APPROVED. ANY MATERIAL, EQUIPMENT, SYSTEMS, ETC., PROCUREMENT OR INSTALLATION COMMENCED WITHOUT THE APPROVAL OF THE ARCHITECT/ENGINEER OWN RISK AND MAY HAVE TO BE MODIFIED, MOVED AND/OR RECONFIGURED AT THE CONTRACTORS COST.

[illegible]

Department of Veterans Affairs
William Jennings Bryan Dorn
VA Medical Center
6439 Garners Ferry Road
Columbia, SC 29209

Architect/Engineer Address

**Harrell,
Saltrick &
Hopper**

Design & Management Solutions for the Built Environment

8016 TOWER POINT DRIVE
CHARLOTTE, NC 28227

WWW.HSNPC.COM


COPYRIGHT © 2011 HARRELL, SALTRICK & HOPPER, PC
HSN PROJECT # 11015

P 704.814.1320
F 704.321.0833

Recommended Approvals:	
1. MEDICAL DIRECTOR	6. OPERATIONS SERVICE LINE MANAGER
2. ASSOCIATE DIRECTOR	7. INFECTION CONTROL MANAGER
3. CHIEF OF STAFF	8. SAFETY MANAGER
4. ASSOC. DIRECTOR	9. GENERAL ENGINEER
5. SERVICE LINE MGRS.	10. COTR

Drawing Title
BASEMENT PLUMBING PLAN
*BUILDING IS FULLY SPRINKLERED *

Project Title		
REPLACE BOILER PLANT/ COGEN/CHP		
Drawn LDR	Building Number 21	AutoCAD File Name
Checked	Reviewed	Const. Contract No.

Date APRIL 10, 2012	
Project Number 544-11-101	
DRAWING No. PL101	