


100% CONSTRUCTION DOCUMENTS

Date APRIL 30, 2012	
Project Number 544-11-101	
DRAWING No. EL103	

THE MECHANICAL DRAWINGS SHALL HAVE THE LEAD IN PREPARATION OF COORDINATION DRAWINGS. SUCH DRAWINGS SHALL BE ARRANGED AND DESIGNED THROUGHOUT AND THROUGH COORDINATION WITH ALL OTHER MAJOR AND MINOR SUBCONTRACTORS AND THE GENERAL CONTRACTOR. PROVIDE PLAN VIEWS, SECTIONS AND ELEVATIONS AS REQUIRED TO FULLY COORDINATE ALL NEW WORK WITH EXISTING CONDITIONS. DRAW TO SCALE (AT NOT LESS THAN 3/8" = 1'-0"). DRAWINGS SHALL SHOW, BUT NOT BE LIMITED TO: ALL RAILINGS; ALL OUTWORK; ALL AIR DISTRIBUTION; MECHANICAL EQUIPMENT; MECHANICAL PIPES; FIRE PROTECTION PIPING; ALL PLUMBING PIPES, CABLE TRAYS (WITH ELEVATIONS NOTED); LIGHTING FIXTURES (WHEN CEILING MOUNTED); CEILING GRID AND CEILING HUNGING; MAJOR BEAMS AND JOISTS (WITH ELEVATIONS MARKED); FIRE ALARMS DEVICES AND SPEAKERS (WHEN CEILING MOUNTED); ELECTRICAL CONDUITS LARGER THAN 2-INCH DIAMETER, CEILING LIGHTS AND REQUIRED CLEARANCES; EQUIPMENT PROVIDED BY OTHERS THAT PROTRUDE INTO CEILING CAVITIES OR OVER THE CEILING LOCATION AREA; CEILING LIGHTS AND REQUIRED CLEARANCES. ALL SECTIONS SHALL BE CUT THROUGH AREAS SHOWING MATERIALS AND SYSTEMS OF ALL CONTRACTS. IF THERE ARE ANY OUTSTANDING ISSUES THAT CANNOT BE RESOLVED, CONSULT WITH THE ARCHITECT AND/OR ENGINEER (THROUGH THE VA COTR) FOR GUIDANCE AND MAKE CORRECTIONS IN ACCORDANCE WITH DIRECTIONS GIVEN. IF IT IS NECESSARY TO MAKE CHANGES TO THE DRAWINGS, THE CHANGES MUST BE APPROVED HAVE BEEN APPROVED. ANY MATERIAL, EQUIPMENT, SYSTEM, ETC., PROCUREMENT OR INSTALLATION COMMENCED PRIOR TO APPROVAL IS TAKEN AT THE CONTRACTORS OWN RISK AND MAY HAVE TO BE MODIFIED, MOVED AND/OR RECONFIGURED AT THE CONTRACTORS COST.

