

SECTION 07 24 00
EXTERIOR INSULATION AND FINISH SYSTEMS

PART 1 - GENERAL

1.1 DESCRIPTION

Exterior Finish Systems specified in this section consist of Exterior Insulation and Finish System (EIFS).

1.2 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Samples:
 - Two 300 mm (one-foot) square samples of the EIFS finishes over cement board identical to the proposed installation in thickness, color, texture and workmanship.
- C. Test Reports and Manufacturer's Literature
 - 1. Manufacturer's literature and instructions for installation of the system. Include manufacturer's recommended details for corner treatment, sills, soffits, dentils, quoins, lintels, openings and other special applications.
 - 2. Summary of test results by the Exterior Finish System manufacturer to substantiate compliance with the specified performance requirements. Furnish complete test reports as required.
 - 3. Statement by Exterior Finish System manufacturer that all components of the system proposed for use on this project are approved by that manufacturer.
 - 4. Statement by the Installer of the Exterior Finish System that they are experienced with the installation, having done at least three (3) projects using this system and can furnish names and locations of these projects if required.

1.4 DELIVERY AND STORAGE

- A. Deliver materials in unopened packages with manufacturer's labels intact, legible and grade seals unbroken.
- B. Store and handle in strict compliance with manufacturer's instructions. Protect from damage.
- C. Remove from premises any damaged or deteriorated material.

1.5 ENVIRONMENTAL CONDITIONS

Unless a higher temperature is required by the system manufacturer, the ambient air temperature shall be 7 degrees Celsius (45 degrees F) or greater and rising at the time of installation of the system and shall

A. Description: The PB system consists of Type I molded rigid polystyrene insulation adhesively adhered to the waterproofed sheathing and finished with a glass-fiber-mesh reinforced based-coat and a textured finish coat.

B. Performance Requirements:

TEST	TEST METHOD	REQUIREMENT
Flame Spread	ASTM E84	Flame spread of 25 or less. Smoke developed rating 450 or less.
Full Scale Wall Fire Test	ASTM E108	No significant surface flaming or propagation of vertical or lateral flames
Impact Resistance	EIMA 101.86 (Hemispherical Head Test)	Standard Impact Resistance 2.83 to 5.54J (25-49 inch-lbs)
Structural Performance (Test panels 1200 mm x 1200 mm (4 feet by 4 feet) typical of project application)	ASTM E330	No permanent deformation, delamination or deterioration for positive and negative pressures as required.
Water Penetration	ASTM E331	No Water penetration
Abrasion Resistance	ASTM D968	500 liters of sand-slight smoothing - no loss of film integrity
Accelerated Weathering	ASTM G90	2000 hours. No deterioration
Salt Spray Resistance	ASTM B117	Withstand 300 hours. No deleterious effects.
Water Vapor	ASTM E96	Not more than 18 grains an hour per square foot.
Absorption-Freeze-Thaw	ASTM C67 50 Cycles: 20 hrs. at - 9 deg C ; 4-hr. thaw in water	After 50 cycles - Total weight gain of not more than 6.2 grams. No checking splitting, or cracking.

C. Adhesive: Manufacturers standard product including primer as required compatible with sheathing.

D. Insulation:

1. Thermal Resistance: Thermal resistance (R-value), as indicated, measured by ASTM C177.

2. Insulating Material: ASTM C578, as recommended by EIFS manufacturer and treated to be compatible with EIFS components. Age insulation a minimum of 6 weeks prior to installation.
 3. Provide Type I Molded Expanded Polystyrene (MEPS) insulation board for Type PB systems, in sizes as required except no larger than 600 mm X 1200 mm (24 X 48 inches) boards, and not more than 100 mm (4 inches) in thickness.
- E. Create a means of drainage between the insulation board and waterproofed sheathing.
- F. Waterproof Sheathing -
1. Where existing material to be covered is masonry or CMU, all material to be covered with self sealing asphaltic waterproofing.
 2. All existing materials of any other substrate shall be covered with cement board and taped per manufacturer's recommendations.
- G. All penetrations and terminations shall be flashed.
- H. Mechanical Anchors: As recommended by the EIFS manufacturer.
- I. Accessories: Conform to the recommendations of the EIFS manufacturer, including trim, edging, anchors, expansion joints, and other items required for proper installation of the EIFS. All metal items and fasteners to be corrosion resistant.
- J. Reinforcing Fabric: Balanced, open weave, glass fiber fabric made from twisted multi-end strands specifically treated for compatibility with the other materials of the system. Minimum weight 4.3 oz/sq. yd.
- K. Base Coat: For PB system, manufacturer's standard product. Minimum thickness of 1-1/2 times reinforcing fabric thickness but not less than 2.4 mm (3/32 inches) wet thickness.
- L. Finish Coat: For PB system, manufacturer's standard product. Minimum thickness 1.6 mm (1/16 inch), complying with Performance Requirements in paragraph B.
- M. Sealant: ASTM C 920; material having a minimum joint movement of 50% with 100% recovery. Type, grade and use shall be as recommended by the sealant manufacturer. When required, primer, bond breaker and backer rods shall be non-staining as recommended by the sealant manufacturer. Do not use absorptive materials as backer rods.

PART 3 EXECUTION

3.1 INSPECTION

Examine substrate, opening supports and conditions under which this work is to be performed. Notify Resident Engineer in writing of

conditions detrimental to the proper completion of this work. Do not proceed with work until unsatisfactory conditions have been corrected.

3.2 CONTROL JOINTS

- A. Exterior Insulation and Finish System. Install at 15 meters (50 feet) maximum in both directions and at building expansion joints, floor lines and where EIFS intersects other materials per manufacturer's recommendations.

3.3 SEALANTS:

- A. Apply according to manufacturer's recommendations and the following:
- B. Exterior Insulation and Finish System: Apply sealant per EIFS manufacturer's recommendation. Do not seal locations intended for water drainage.

3.4 ACCESSORIES:

Install according to manufacturer's recommendation.

3.5 FINISH:

A. EXTERIOR INSULATION AND FINISH SYSTEM:

1. Insulation Board: Place horizontally from level base line. Stagger vertical joints and interlock at corners. Butt joints tightly. Provide flush surfaces at joints. Offset insulation board joints from joints in sheathing by at least 200 mm (8 inches). Do not align joints with corners of doors, windows and other openings. Do not leave insulation board exposed longer than recommended by insulation manufacturer.
2. Mechanical Fasteners: Fasten with manufacturer's standard anchors, spaced as recommended by manufacturer, but not more than 600 mm (2 feet) horizontally and vertically.
3. Sanding: Sand entire surface of insulation before application of base coat to improve bonding of basecoat, level high joints and remove dirt and weathering damage. Do not pre-fill low areas with basecoat.
4. Base Coat and Reinforcing Fabric: Trowel apply to the insulation a uniform thickness of base coat as recommended by the system manufacturer but not less than 1-1/2 times the reinforcing fabric thickness with a minimum of 2.4 mm (3/32 inch). Install reinforcing fabric in accordance with manufacturer's instructions. Provide diagonal reinforcement at opening corners, backwrapping, and any other reinforcement recommended by EIFS manufacturer. The fabric shall not be visible beneath the surface of the basecoat after

installation. Cure the basecoat for a minimum of 24 hours before application of the finish coat.

5. Finish: Inspect basecoat for damage or defects and repair prior to application of finish coat. Trowel apply finish coat according to manufacturer's recommendations but a minimum of 1.6 mm (1/16 inch). Texture finish as required. Provide finish surfaces that are plumb and plane with no greater deviation than 1:500 (1/4 inch in 10 feet).

3.6 CLEAN UP:

Upon completion, remove all scaffolding, equipment, materials and debris from site. Remove all temporary protection installed to facilitate installation of system.

- - - - E N D - - -