


- DRAWING KEYNOTES:**
- 1 REMOVE EXISTING PLUMBING FIXTURES IN THIS ROOM AND CAP ALL EXISTING PIPING SERVING DEMOLISHED FIXTURES BEHIND NEW FINISHED SURFACES.
 - 2 REMOVE EXISTING URINAL IN THIS LOCATION AND REWORK PIPING INSIDE CHASE TO RECEIVE RELOCATED WATER CLOSET ASSEMBLY.
 - 3 EXISTING WATER CLOSET AND FLUSH VALVE ASSEMBLY TO BE RELOCATED AS SHOWN.
 - 4 REMOVE EXISTING FLOOR DRAIN GRATE AND REPLACE WITH SOLID GASKETED COVER.
 - 5 CONTRACTOR TO REROUTE EXISTING PIPING ABOVE CEILING IN THIS ROOM TO BE OUTSIDE THE FOOTPRINT OF THE NEW ELECTRICAL ROOM.
 - 6 EXTEND EXISTING A/S MAIN TO SERVE NEW BRASS PENDANT TYPE SPRINKLERS IN THESE ROOMS. NEW A/S AREA TO BE PROTECTED BASED ON ORDINARY HAZARD GROUP 1 OCCUPANCY, 130 SQUARE FOOT PER SPRINKLER HEAD MAXIMUM SPACING.

BUILDING 107 - GROUND FLOOR

TVHS, YORK CAMPUS



BUILDING 107 - GROUND FLOOR

TVHS, YORK CAMPUS

Revisions	Date

Tennessee Valley Healthcare System

MAZZETTI NASH LIPSEY BURCH
3322 West End Ave., Suite 600
Nashville, TN 37203-6566
TEL: 615.525.4600
FAX: 615.525.3600
www.mazzetti.com

GOBBELL HAYS PARTNERS, INC.
ARCHITECTURE • ENGINEERING
ENVIRONMENT • HEALTH • SAFETY
217 Fifth Avenue North
Nashville, TN 37219
ph: 615-254-8500
fax: 615-256-3430
www.gbi1.com

Project Title : UPGRADE ELECTRICAL DISTRIBUTION PHASE 3		Date : OCTOBER 31, 2012	
Drawing Title : PLUMBING DEMOLITION PLAN BUILDING 107 GROUND FLOOR		Project No. : 626A4-11-202	
Approved By : _____		Location : ALVIN C. YORK CAMPUS MURFREESBORO, TN	
Building Number : 107	Checked By : -	Drawn By : GLD	

Date : OCTOBER 31, 2012	Project No. : 626A4-11-202	Drawing No. : 107-PD.100	Dwg. : G4	Of : 97
-------------------------	----------------------------	--------------------------	-----------	---------

Department of Veterans Affairs