

**Pre-bid Site Visit:**

Prior to submitting a quotation, offerors are encouraged to contact XXXXXX at the Fort Sam Houston National Cemetery, 210-820-3891.

**SCOPE OF WORK**

The Contractor shall provide all necessary expertise, supervision, labor, equipment, and supplies to deliver Tif 419 Bermuda for cemetery staff installation, at the Fort Sam Houston National Cemetery property located at 1520 Harry Wurzbach Road, San Antonio, TX 78209.

Delivery to be accomplished within the hours of 8:00 a.m. to 10:00 a.m. Monday thru Friday.

**A. Furnishing and delivery of grass sod:**

**A.1** - Grass sod shall be ordered and delivered approximately 3 orders per month estimated at 11,250 square feet per order. The amount of grass sod to be delivered may vary depending on the interment rate. The grass sod shall be delivered within two (2) business days of order.

**A.2** - Grass sod shall be ordered and delivered (no installation) at approximately 8,333 square feet per month. This sod will be installed by cemetery staff. The amount of grass sod to be delivered may vary according to cemetery need. The grass sod shall be delivered within three (3) business days of order.

**A.3** - Grass sod shall be certified 419 Bermuda, delivered freshly cut, weed, disease, and insect free, and of healthy appearance with uniform color, leaf texture, and shoot density. Grass sod shall be relatively free of thatch, less than 0.5 inch (uncompressed). Grass sod shall be machine cut at a uniform soil thickness of 0.60 inch, plus or minus .25 inch, at the time of cutting. Measurement for thickness shall exclude top growth and any thatch. Irregular sized pads, broken pads, and torn or uneven ends will not be acceptable. Standard sized sections of grass sod shall be strong enough that it can be picked up and handled without damage. Grass sod shall not be harvested or transplanted when its moisture content (excessively dry or wet) may adversely affect its survival. Grass sod shall be harvested and delivered within a 24 hour period, unless a suitable preservation method is approved by the COR prior to delivery.

**B. Contractor Equipment, Personnel, and Contractor Responsibilities**

**B.1** - Contractor shall not damage any property within the cemetery grounds. Any damage incurred by contractor shall be repaired or replaced at contractor expense with no additional

charge to the government. This damage includes, but not is not limited to, rutting of grounds caused by contractor equipment, headstone and marker damage, and any other damage to cemetery property and grounds caused by contractor.

**B.2** - Contractor shall clean up and/or pick up any trash, debris, dirt, mud, tire marks or any other related items upon completion of work in that area on any given work day.

**End of Scope of Work**