



PLUMBING FIXTURE SCHEDULE										
MARK	DESCRIPTION	WASTE PIPE	VENT PIPE	COLD WATER	HOT WATER	WASTE FIXTURE UNITS	WATER FIXTURE UNITS	WRIST BLADE HANDLES	ELECTRIC SENSOR	REMARKS
		IN	IN	IN	IN					
P-103	WATER CLOSET (ADA)	4	2	1.25	-	6	10.0	NO	YES	KOHLER "KINGSTON" MODEL K-4325 (OR APPROVED EQUAL), 1.6 GPF, 16 1/2" HIGH ELONGATED WATER CLOSET; SLOAN "ROYAL" MODEL III ES-S EXPOSED SENSOR OPERATED 1.6 GPF FLUSH VALVE, OPTIMA EL-1500-L SELF ADAPTIVE INFRARED SENSOR WITH INDICATOR LIGHT, COURTESY FLUSH OVER-RIDE BUTTON AND MODEL EL-154 TRANSFORMER; CHURCH MODEL 5400SS OPEN FRONT SEAT-LESS COVER WITH SS CHECK HINGES
P-104	WATER CLOSET WITH LAVATORY IN CABINET	4	2	1.25	-	6	10.0	NO	NO	WHITEHALL SWINGETTE MODEL 4050-QN20031877, PROVIDE FACTORY INSTALLED PUSH BUTTON OPERATED FLUSH VALVE WITH VACUUM BREAKER AND CHECKSTOP AND INFECTIOUS CONTROL FLUSH (IFC) AND SECURED STAINLESS STEEL PANEL FOR ACCESS TO VALVES AND PIPING, HINGED SEAT WITH COVER, CYLINDER LOCK WITH KEY TO LOCK SWING CABINET CLOSED TO STATIONARY CABINET, SOLID SURFACE TOP WITH INTEGRAL BOWL (CORIAN) WITH GOOSENECK FAUCET WITH WRIST BLADE FAUCET AND FOOT PEDAL VALVE CONTROLS, POLYETHYLENE AND WOOD GRAIN PANELS, SWING UP GRAB BAR, AND LOUVERS ON THE STAINLESS PANEL ABOVE TOILET WITH 6" X 4" DUCT CONNECTION (NOT TO INTERFERE WITH FLUSH VALVE); FIXTURE DIMENSIONS FROM FACE OF FINISHED WALL TO FRONT OF UNIT SHALL NOT EXCEED 26" (CLOSED POSITION) AND 31" (SWING OUT FULLY OPENED).
P-104A	BED PAN WASHER	-	-	0.5	-	-	1.0	NO	NO	CHICAGO FAUCETS MODEL 804-EPABCP WALL MOUNTED SINGLE HANDLE BED PAN WASHER IN A CABINET-SEE ARCHITECTURAL DRAWINGS FOR CABINET.
P-418A	WALL HUNG SINK (ADA)	2	1.5	0.5	0.5	1	1.0	NO	NO	KOHLER "KINGSTON" MODEL K-2007-R (OR APPROVED EQUAL) 21" X 18" LAVATORY WITH 1 HOLE FOR FAUCET; CHICAGO FAUCETS MODEL GN1AE3JKABCP 3 1/2" RIGID/SWING GOOSENECK SPOUT, CHICAGO FAUCETS MODEL 834-EPABCP HOT AND COLD WATER PEDAL BOX WITH EXTENDED PEDALS AND MODEL 122-NF THERMOSTATIC MIXING VALVE; MCGUIRE PRODUCTS MODEL 155A GRID STRAINER, MODEL PW2125 PREWRAPPED 17 GA. P-TRAP AND SUPPLY COVERS, MODEL 216SLK STOPS; J.R. SMITH 0710 "LABOR SAVER" FLOOR MOUNTED CARRIER.
P-418B	WALL HUNG SINK (ADA)	2	1.5	0.5	0.5	1	1.0	NO	NO	KOHLER "KINGSTON" MODEL K-2007-R (OR APPROVED EQUAL) 21" X 18" LAVATORY WITH 2 HOLES FOR FAUCET AND EMERGENCY EYEWASH (P-708); CHICAGO FAUCETS MODEL GN1AE3JKABCP 3 1/2" RIGID/SWING GOOSENECK SPOUT, CHICAGO FAUCETS MODEL 834-EPABCP HOT AND COLD WATER PEDAL BOX WITH EXTENDED PEDALS AND MODEL 122-NF THERMOSTATIC MIXING VALVE; MCGUIRE PRODUCTS MODEL 155A GRID STRAINER, MODEL PW2125 PREWRAPPED 17 GA. P-TRAP AND SUPPLY COVERS, MODEL 216SLK STOPS; J.R. SMITH 0710 "LABOR SAVER" FLOOR MOUNTED CARRIER.
P-418C	WALL HUNG LAVATORY (ADA)	2	1.5	0.5	0.5	1	1.0	NO	NO	KOHLER "CHESAPEAKE" MODEL K-1722-R (OR APPROVED EQUAL) 19" X 17" LAVATORY WITH 1 HOLE FOR FAUCET; CHICAGO FAUCETS MODEL GN1AE3JKABCP 3 1/2" RIGID/SWING GOOSENECK SPOUT, CHICAGO FAUCETS MODEL 834-EPABCP HOT AND COLD WATER PEDAL BOX WITH EXTENDED PEDALS AND MODEL 122-NF THERMOSTATIC MIXING VALVE; MCGUIRE PRODUCTS MODEL 155A GRID STRAINER, MODEL PW2125 PREWRAPPED 17 GA. P-TRAP AND SUPPLY COVERS, MODEL 216SLK STOPS; J.R. SMITH 0710 "LABOR SAVER" FLOOR MOUNTED CARRIER.
P-418D	WALL HUNG LAVATORY (ADA)	2	1.5	0.5	0.5	1	1.0	YES	NO	KOHLER "CHESAPEAKE" MODEL K-1722-R (OR APPROVED EQUAL) 19" X 17" LAVATORY WITH 2 HOLES FOR FAUCET; CHICAGO FAUCETS MODEL 895-317ABCP DECK MOUNTED WITH 4" METAL WRISTBLADE HANDLES AND MODEL 122-NF THERMOSTATIC MIXING VALVE; MCGUIRE PRODUCTS MODEL 155A GRID STRAINER, MODEL PW2125 PREWRAPPED 17 GA. P-TRAP AND SUPPLY COVERS, MODEL 216SLK STOPS; J.R. SMITH 0710 "LABOR SAVER" FLOOR MOUNTED CARRIER.
P-505	CLINICAL SERVICE SINK	4	2	1	1/2	6	10.0	-	-	ZURN Z5410 WALL MOUNT CLINICAL SERVICE SINK. ZURN Z80842AV-BWN EXPOSED FLUSH VALVE WITH BEDPAN WASHER AND SINK FAUCET. ZURN Z85500-WM DOUBLE FOOT PEDAL VALVE.
P-528	BREAK ROOM SINK	2	1.5	0.5	0.5	3	2.0	YES	NO	JUST MFG. CO (OR APPROVED EQUAL) MODEL DL-2037-A-GR 20" X 37" X 7-1/2" DEEP DOUBLE COMPARTMENT SINK WITH MODEL J-35-GS-STP BASKET STRAINER AND MODEL JT-200 17 GA P-TRAP AND 216S STOPS. CHICAGO FAUCETS MODEL 1100-317VPAABCP WITH 4" WRISTBLADE HANDLES. IN SINK ERATOR MODEL HOT1 INSTANT HOT WATER DISPENSER, 40 CUPS OF 190 DEGREES F WATER PER/HR, 115V, 500 WATTS, 4.3 AMP HEATING ELEMENT WITH GROUNDED THREE (3) PRONG PLUG.
P-528A	NOURISHMENT ROOM SINK	2	1.5	0.5	0.5	2	2.0	YES	NO	JUST MFG. CO (OR APPROVED EQUAL) MODEL SL-1921-A-GR 19" X 21" X 7-1/2" DEEP SINGLE COMPARTMENT SINK WITH MODEL J-35-GS-STP BASKET STRAINER AND MODEL JT-200 17 GA P-TRAP AND 216S STOPS. CHICAGO FAUCETS MODEL 1100-317VPAABCP WITH 4" WRISTBLADE HANDLES. IN SINK ERATOR MODEL HOT1 INSTANT HOT WATER DISPENSER, 40 CUPS OF 190 DEGREES F WATER PER/HR, 115V, 500 WATTS, 4.3 AMP HEATING ELEMENT WITH GROUNDED THREE (3) PRONG PLUG.
P-528B	MEDICATION ROOM SINK	2	1.5	0.5	0.5	2	2.0	YES	NO	JUST MFG. CO (OR APPROVED EQUAL) MODEL SL-1921-A-GR 19" X 21" X 7-1/2" DEEP SINGLE COMPARTMENT SINK WITH MODEL J-35-GS-STP BASKET STRAINER AND MODEL JT-200 17 GA P-TRAP AND 216S STOPS. CHICAGO FAUCETS MODEL 1100-317VPAABCP WITH 4" WRISTBLADE HANDLES.
P-701	SHOWER (ADA)	2	1.5	0.5	0.5	2	2.0	NO	NO	SYMMONS (OR APPROVED EQUAL) TEMPTROL II SHOWER SYSTEM MODEL BP-56-500-830-V, PRESSURE BALANCING MIXING VALVE WITH ADJUSTABLE STOP SCREW TO LIMIT HANDLE TURN, CLEAR-FLO SHOWER HEAD WITH ARM AND FLANGE, LEVER DIVERTER WITH INTEGRAL VOLUME CONTROL, WALL/HAND SHOWER WITH 5' FLEXIBLE METAL HOSE, IN-LINE VACUUM BREAKER, WALL CONNECTION AND FLANGE, PROVIDE WALL HOOK ON HAND SPRAY UNIT IN PLACE OF 30" SLIDE BAR. SHOWER FLOOR- FIAT "GIBRALTAR" MODEL RM 36" X 36" PRECAST TERRAZZO.
P-702	SHOWER (NOT USED)	2	1.5	0.5	0.5	2	2.0	NO	NO	SYMMONS (OR APPROVED EQUAL) TEMPTROL II SHOWER SYSTEM MODEL BP-56-500-830-V, PRESSURE BALANCING MIXING VALVE WITH ADJUSTABLE STOP SCREW TO LIMIT HANDLE TURN, CLEAR-FLO SHOWER HEAD WITH ARM AND FLANGE.
P-708	EMERGENCY EYE-FACE WASH	-	-	0.5	0.5	-	-	-	-	ACORN MS0850-RH-TMVB DECK MOUNTED SWING DOWN EYEWASH WITH ABS PLASTIC EYEWASH SPRAY HEADS. WATER FLOW IS ACTIVATED/DEACTIVATED AUTOMATICALLY WHEN EYEWASH SWINGS DOWN/UP OVER THE SINK. LENGTH OF YOKE TO BE 9-1/2". THERMOSTATIC MIXING VALVE IS ASSE LISTED PER THE ASSE 1071 STANDARD. THE TEPID OUTPUT WATER COMPLIES WITH ANSI Z358.1 STANDARD.
P-805	TRAP PRIMER	-	-	0.5	-	-	-	-	-	PRECISION PLUMBING PRODUCTS 1" OR APPROVED EQUAL MODEL PR-500 AUTOMATIC FLOOR DRAIN TRAP PRIMER.
P-809	DIALYSIS BOX	2	1.5	0.5	-	2.0	1.0	NO	NO	METCRAFT MODEL A660 DIALYSIS BOX, FULLY RECESSED TYPE 316 STAINLESS STEEL, POLYPROPYLENE BALL VALVE.
P-901	FLOOR DRAIN	2	1.5	-	-	-	-	-	-	J.R. SMITH MODEL 2005-F37 (OR APPROVED EQUAL) FLOOR DRAIN WITH 7" DIAMETER ROUND TOP ANTI-FLOOD RIM, POLISHED NICKEL BRONZE STRAINER

- NOTES:
1. PROVIDE WATER HAMMER ARRESTOR TO EACH WATER CLOSET FIXTURE UNIT
 2. FOR ADA COMPLIANT WATER CLOSETS, SEAT MUST BE 17" HIGH MINIMUM AND 19" HIGH MAXIMUM, REFER TO ARCHITECTURAL DRAWINGS.
 3. ALL ADA LAVATORY WITH PIPING AND FITTING TO BE PROVIDED WITH ADA COMPLIANT FITTINGS AND INSTITUTIONAL ADA INSULATOR KIT.

CONSTRUCTION DOCUMENTS

<div>ADDENDUM #3/REVISION #1</div> <div>13 DEC 2013</div>	CONSULTANTS:		ARCHITECT/ENGINEERS:	<div>Drawing Title</div> <div>PLUMBING SCHEDULES</div>	<div>Project Title</div> <div>Design Services to Remodel Building 100, 4E MICU CCU</div>	<div>Project Number</div> <div>663-C21943</div>	Office of Construction and Facilities Management
	<div>SÄZAN GROUP</div> <div>600 Stewart St., Ste 1400 Seattle, Washington 98101</div> <div>Tel 206.267.1700 Fax 206.267.1701 SAZAN #338-1210</div>		<div>MANDEVILLE · BERGE · BOX</div> <div>ARCHITECTS ENGINEERS PLANNERS</div> <div>500 UNION ST. SEATTLE, WA 98101</div>	<div>Approved: Project Director</div>	<div>Building Number</div> <div>100</div>	<div>Building Number</div> <div>100</div>	
					<div>Location</div> <div>PUGET SOUND HEALTH CARE SYSTEM, SEATTLE 1660 SOUTH COLUMBIAN WAY, SEATTLE, WA 98108</div>	<div>Drawing Number</div> <div>100-PL601</div>	
<div>Revisions:</div>	<div>Date</div>			<div>Date</div> <div>30 OCT 2013</div>	<div>Checked</div> <div>SS</div>	<div>Drawn</div> <div>NUA</div>	<div>Dwg. 58 of 84</div>