

**> You are here:** [Home](#) > [Products](#) > [Surge Protection and Power Conditioning](#) > [SurgeArrest Performance](#)



**APC Power-Saving Performance SurgeArrest, 11 Outlets with Phone and Video Protection, 120V**  
Part Number: P11GTV



**Technical Specifications**

Product Overview

Documentation

Ratings and Reviews

**Output**

Number of Outlets	11
Receptacle Style	NEMA 5-15R

**Input**

Nominal Input Voltage	120V
Input Frequency	50/60 Hz +/- 5 Hz (manual switch)
Input Connections	NEMA 5-15P
Cord Length	1.83 meters
Input Breaker Capacity	15.0 A



**Surge Protection and Filtering**

Surge energy rating	3400 Joules
EMI/RFI Noise rejection (100 kHz to 10 MHz)	70 dB
NM Surge Response Time (ns)	1 ns
Data Line Protection	Analog phone line for phone/fax/modem/DSL (RJ-11 connector), Coaxial cable for CATV/SATV/modem/Audio-Video (coax connector)
Let Through Voltage Rating	< 40

**Physical**

Net Weight	1.11 KG
Maximum Height	40.00 mm
Maximum Width	119.00 mm
Maximum Depth	363.00 mm

Shipping Weight	1.31 KG
Shipping Height	58.00 mm
Shipping Width	252.00 mm
Shipping Depth	428.00 mm
Master Carton Units	6.00
Master Carton Dimensions (Length 399 x 291 x 464 mm x Width x Height)	
Master Carton Weight	9.25 KG
SCC Codes	1073130426923 3
Color	Black
Units per Pallet	192.00
<b>Environmental</b>	
Operating Environment	0 - 40 °C
Operating Relative Humidity	0 - 95%
Operating Elevation	0-4500 meters
Storage Temperature	-15 - 45 °C
Storage Relative Humidity	0 - 95%
Storage Elevation	0-15000 meters
<b>Conformance</b>	
Regulatory Approvals	ETL, UL 1363, UL 1449
Standard Warranty	Lifetime
UL 1449 TVSS Rating	<400V
<b>Sustainable Offer Status</b>	
RoHS	Compliant
REACH	REACH: Contains No SVHCs