


CARL VINSON V.A. MEDICAL CENTER  
DUBLIN, GEORGIA  
STEAM AND CONDENSATE  
PIPING SYSTEM STUDY  
PROJECT No. 557-10-109



LOCATION MAP  
NO SCALE

INDEX OF DRAWINGS

DWG. NO.	DRAWING TITLE	SHEET NO.	DWG. NO.	DRAWING TITLE	SHEET NO.
I-1.01	COVER SHEET, MAPS AND DRAWING INDEX	1	11-G-001	BASEMENT PLAN AND ENLARGED PLAN	55
I-1.02	MECHANICAL LEGEND, GENERAL NOTES AND SCHEDULE	2	11-G-002	PROCESS FLOW DIAGRAM AND DETAILS	56
I-1.03	MECHANICAL DETAILS	3	11-G-101	FIRST FLOOR PLAN AND DETAILS	57
I-1.04	STEAM FIRE DOMESTIC WATER HEATER DEMOLITION AND NEW WORK DETAILS	4	11-G-201	SECOND FLOOR PLAN AND DETAILS	58
ASB-001	GENERAL NOTES - ASBESTOS ABATEMENT PLAN	5	12-G-001	DETAILS	59
01-G-001	BASEMENT/CRAWL SPACE PLAN AND MECHANICAL ROOM ENLARGED	6	12-G-002	DETAILS	60
01-G-002	PROCESS FLOW DIAGRAM AND DETAILS	7	12-G-003	DETAILS	61
01-G-101	FIRST FLOOR PLAN	8	12-G-004	DETAILS	62
01-G-201	SECOND FLOOR PLAN	9	12-G-005	DETAILS	63
01-G-301	ATTIC FLOOR PLAN	10	12-G-006	DETAILS	64
02-G-001	BASEMENT FLOOR PLAN	11	12-G-007	DETAILS	65
02-G-002	BUILDING 2 ENLARGED PLANS	12	13-G-001	BASEMENT PLAN AND DETAILS	66
02-G-003	PROCESS FLOW DIAGRAM AND DETAILS	13	13-G-101	FIRST FLOOR PLAN	67
02-G-101	FIRST FLOOR PLAN AND ENLARGED PLANS	14	13-G-201	SECOND FLOOR PLAN	68
02-G-102	PROCESS FLOW DIAGRAM AND DETAILS	15	13-G-301	ATTIC FLOOR PLAN AND DETAILS	69
02-G-201	SECOND FLOOR PLAN	16	14-G-001	BASEMENT FLOOR PLAN AND DETAILS	70
02-G-301	ATTIC FLOOR PLAN AND DETAILS	17	15-G-001	BASEMENT FLOOR PLAN	71
02-G-401	BASEMENT FLOOR PLAN	18	15-G-002	DETAILS	72
02-G-402	PROCESS FLOW DIAGRAM, DETAILS AND CORRIDOR PLANS	19	15-G-003	DETAILS	73
03-G-001	BASEMENT FLOOR PLAN AND DETAILS	20	15-G-101	FIRST FLOOR PLAN	74
03-G-101	FIRST FLOOR PLAN AND DETAILS	21	16-G-001	BASEMENT FLOOR PLAN	75
03-G-201	SECOND FLOOR PLAN	22	16-G-002	DETAILS	76
03-G-301	ATTIC FLOOR PLAN AND DETAILS	23	16-G-003	DETAILS	77
03-G-401	BASEMENT FLOOR PLAN AND DETAIL	24	16-G-004	DETAILS	78
03-G-402	DETAILS	25	19-G-001	JUNCTION 17/19 - BASEMENT FLOOR PLAN	79
04-G-001	BASEMENT FLOOR PLAN	26	19-G-002	DETAILS	80
04-G-002	CRAWL SPACE AND CORRIDOR ENLARGED PLANS	27	19-G-301	BUILDING 17/19 JUNCTION - ATTIC PLAN	81
04-G-003	PROCESS FLOW DIAGRAM AND DETAILS	28	26-G-001	BASEMENT FLOOR PLAN	82
04-G-101	FIRST FLOOR PLAN	29	26-G-002	PROCESS FLOW DIAGRAM AND DETAILS	83
04-G-201	SECOND FLOOR PLAN AND PROCESS FLOW DIAGRAM AND DETAILS	30	26-G-003	DEMOLITION AND NEW WORK ISOMETRIC PIPING PLANS BUILDING 26 AND 27	84
04-G-301	ATTIC FLOOR PLAN AND PROCESS FLOW DIAGRAM AND DETAILS	31	27-G-001	BUILDING 27 ENLARGED FLOOR PLAN	85
05-G-001	NORTH AND SOUTH CRAWL SPACE PLANS	32	27-E-001	LEGEND, PANEL SCHEDULE, AND SWITCHBOARD - ELECTRICAL	86
05-G-002	SECTIONS AND DETAILS	33	27-E-002	FLOOR PLAN, POWER RISER DIAGRAM AND NOTES - ELECTRICAL	87
05-G-101	FIRST FLOOR PLAN	34			
05-G-102	DETAILS	35			
05-G-201	ROOF PLAN	36			
05-G-202	DETAILS	37			
06-G-001	CRAWL SPACE	38			
06-G-002	DETAIL	39			
06-G-003	DETAILS	40			
06-G-101	FIRST FLOOR PLAN AND DETAILS	41			
06-G-201	SECOND FLOOR PLAN AND DETAILS	42			
06-G-301	ATTIC FLOOR PLAN, DETAILS AND SECTIONS	43			
09-G-001	CRAWL SPACE PLAN AND DETAILS	44			
09-G-101	FIRST FLOOR PLAN AND DETAILS	45			
09-G-201	SECOND FLOOR PLAN AND DETAILS	46			
09-G-301	ATTIC FLOOR PLAN	47			
09-G-302	DETAILS	48			
09-G-401	BLDG 9-11/13-15, BLDG 13-15/17-19 CRAWL CORRIDOR SPACE PLAN	49			
10-G-001	BASEMENT PLAN	50			
10-G-002	DETAILS	51			
10-G-003	DETAILS	52			
10-G-004	DETAILS	53			
10-G-401	BLDGS 14-16 TO 10-12 CRAWL SPACE CORRIDOR PLAN	54			

GENERAL NOTES/PHASING AND SCOPE OF WORK

- A. THE OVERALL SCOPE OF THIS PROJECT IS TO PROVIDE THE GOVERNMENT WITH A RENOVATED AND ACCURATELY DOCUMENTED STEAM AND STEAM CONDENSATE SYSTEM. SOME SHEETS IN THIS DRAWING SET DO NOT SHOW CONSTRUCTION WORK REQUIRED AND ARE CLEARLY MARKED TO REFLECT THAT. THEY ARE INCLUDED IN THE SET TO PROVIDE A COMPLETE RECORD OF THE ENTIRE SYSTEM BOTH FOR THE BENEFIT OF THE CONTRACTOR AND ULTIMATELY TO BE PART OF THE UPDATED EXISTING CONDITIONS SET THAT THE CONTRACTOR AND THE ENGINEER ARE RESPONSIBLE FOR PROVIDING TO THE GOVERNMENT.
- B. THE LOCATIONS OF THE STEAM AND CONDENSATE SYSTEM EQUIPMENT, COMPONENTS AND PIPING SHOWN ON THE PLAN VIEWS OF THESE DOCUMENTS ARE APPROXIMATE. FIELD VERIFICATION IS REQUIRED PRIOR TO WORK IMPLEMENTATION. PRE-BID FIELD FAMILIARIZATION IS ENCOURAGED FOR CONTRACTOR'S NOT FAMILIAR WITH THIS SITE SO THAT THEY MAY OBTAIN AN ACCURATE PICTURE OF WORKING CONDITIONS, AVAILABLE ACCESS ROUTES, RIGGING OPTIONS ETC.
- C. THE WORK OF THIS PROJECT SHALL BE COMPLETED IN A WORKING HOSPITAL AND SHALL; THEREFORE, BE SEQUENTIAL PHASED TO MINIMIZE / ELIMINATE THE LIKELY HOOD OF UNPLANNED STEAM SYSTEM SHUTDOWNS DUE TO THE WORK OF THIS PROJECT. THE CONTRACTOR IS DIRECTED TO CAREFULLY READ ALL SECTIONS OF THE SPECIFICATIONS TO GAIN AN UNDERSTANDING OF PHASING AND SCHEDULED SHUTDOWN NOTIFICATION REQUIREMENTS WHICH WILL HAVE AN IMPACT ON THE DURATION OF THIS PROJECT.
- D. AS INDICATED IN THE DRAWINGS AND SPECIFICATIONS THE SCOPE OF THIS PROJECT IS TO COMPLETED THE REQUIRED STEAM AND CONDENSATE SYSTEM REPAIRS, MODIFICATIONS AND UPGRADES SHOWN. THE EXACT WORK SEQUENCE SHALL DEPEND ON THE TIME OF YEAR THAT THE WORK BEGIN. HOWEVER, IN GENERAL THE WORK SHALL PROCESS AS FOLLOWS:
- INSTALL INDICATED PIPING MODIFICATIONS AND AUTOMATIC CONTROLS TO SUPPLY PLANT STEAM SUPPLIED VIA PROCESS STEAM PIPING TO HEATING STEAM PIPING IN INDICATED BUILDINGS: 2B, 3B, 6A & B, 7B, 9A & B, 11B & C, 12B, 14A & B, 15A, AND 16A, B, C IN SUMMER OR WITH COTR APPROVAL IN CAREFULLY PLANNED SHUTDOWN.
  - DEMOLISH AND REMOVE FROM THE HOSPITAL SITE ALL INDICATED HEATING STEAM SYSTEM SUPPLY AND CONDENSATE PIPING. THIS SCOPE IS CLOSELY RELATED TO ITEM 1 ABOVE AS THE LISTED BUILDINGS WILL CONTINUE TO BE STEAM HEATED AFTER THE COMPLETION OF THIS PROJECT. THE CONTRACTOR SHALL REMOVE AND SELL FOR SALVAGE OR OTHERWISE PROPERLY DISPOSE OF ALL PIPING AND MATERIALS REMOVED. MATERIALS SHALL NOT BE REUSED IN THIS PROJECT THIS WORK SHALL NOT BEGIN UNTIL THE WORK OF ITEM 1 IS COMPLETED AND FULLY TESTED. SPECIAL EMPHASIS HAS TO BE PLACED ON COMPLETING THIS WORK IN BUILDING 2 PRIOR TO BEGINNING THE WORK IN ITEM 4 BELOW.
  - REMOVE INDICATED EXISTING CROSS OVER CONNECTIONS BETWEEN PROCESS AND STEAM HEATING SYSTEMS.
  - REPLACE AS INDICATED PROCESS CONDENSATE RETURN PIPING IN BUILDING 2. THIS WORK SHOULD BE COMPLETED DURING WARM WEATHER AND/OR WITH PRE-PLANNING TO PRE-INSTALL NEW PIPING IN PLACE OF REMOVED STEAM HEATING MAINS IN PARALLEL PRIOR TO REMOVAL OF EXISTING CONDENSATE PIPE.
  - REPLACE AS INDICATED EXPOSED CONDENSATE PIPES BETWEEN BUILDING 2 AND THE BOILER PLANT.
  - PROVIDE STEAM POWERED STEAM CONDENSATE PUMPS FOR INDICATED STEAM FIRED DOMESTIC WATER HEATERS. THIS WORK WILL BE ACCOMPLISHED AT NIGHT TO REDUCE DOMESTIC HOT WATER DOWN TIME.
  - REPAIR AS INDICATED OR REPLACE AS INDICATED EXISTING STEAM POWERED CONDENSATE PUMPS. THIS WORK SHALL BE COMPLETED AT NIGHT TO REDUCE DISRUPTIONS TO HOSPITAL.
  - INSTALL EXTERNAL FLANGED CONNECTIONS AND VALVES TO MAKE PROVISIONS FOR PROVIDING THE STEAM HEADER LINE WITH STEAM FROM A TRAILER MOUNTED RENTAL BOILER.
  - REPLACE AND/OR RELOCATE INDICATED PRESSURE REDUCING VALVES AND PRESSURE RELIEF VALVES AND VENT PIPING.