

VA263-14-B-0002

Question

One of the contractors bidding this project wants me to put a 3000A and 100A breaker on the secondary side of transformer 11-1. This is not indicated clearly on the plans or by addendum. Is this correct, and if so, what are the specifications?

Answer

The intent was to have the transfer switches be service rated, and the over current protection at the transfer switches. This apparently did not get changed in the specs.

263623 Automatic Transfer Switches – 2.1 A. 2. should read “Automatic transfer switches are to be 4-pole draw-out construction, electrically operated, mechanically held open contact type, service rated with integral utility circuit breaker.