



GENERAL DEMOLITION NOTES

1. DRAWINGS SHOULD BE TAKEN AS A COMPLETE DOCUMENT. CONTRACTOR TO CONFIRM ALL ITEMS REQUIRED TO BE DEMOLISHED AND EXTENT OF DEMOLITION BASED UPON THE EXTERNAL INTENT OF THE ENTIRE DOCUMENT.
2. CONTRACTOR TO PROTECT ITEMS TO REMAIN. COORDINATE THE STORAGE OF ITEMS TO BE REUSED WITH OWNER.

SPECIFIC DEMOLITION NOTES

1. DEMOLISH ALL EXISTING ACOUSTIC CEILING TILES AND GRID. PROTECT GYPSUM BOARD CEILINGS AND PATIENT LIFTS (WHEN APPLICABLE).
2. EXISTING PATIENT LIFT TO REMAIN.
3. EXISTING PATIENT LIFT RAIL & SUPPORT SYSTEM TO BE RELOCATED TO ACCOMMODATE NEW HEADWALL INSTALLATION. REINSTALL AND MODIFY PER MANUFACTURER'S REQUIREMENTS.
4. EXISTING CURTAIN TRACK TO BE REUSED.
5. DEMOLISH EXISTING SUPPLY AIR DIFFUSERS.
6. EXISTING LIGHT FIXTURE TO BE REUSED.
7. NOT USED.
8. DEMOLISH EXISTING EXHAUST DIFFUSER.

DEMOLITION LEGEND

- ITEMS TO BE REMOVED
- SPECIFIC NOTE
- NOTE THAT APPLIES TO ENTIRE ROOM

ARCHITECTS/ENGINEERS/CONSULTANTS:		HEALTHCARE CONSULTANT:	
ARCHITECT: SPUR DESIGN LLC 7700 North Hudson Ave., Suite 9 Oklahoma City, Oklahoma 73116		JUNK ARCHITECTS 902 Broadway, 8th Floor Kansas City, Missouri 64105	
MEP ENGINEER: Lee & Browne Consulting Engineers, Inc. 1207 S. Sheridan Road Tulsa, Oklahoma 74112			
PARTIAL THIRD AND FOURTH FLOOR CEILING DEMOLITION PLANS		ICU Headwall Relocation Jack C. Montgomery VA Medical Center	
Project Number 6223-10-107		Building Number 53	
Drawing Number AD504		Date 5/23/12	
Checked SAC		Drawn LLA	
Sheet 7 OF 38			