BUILDING 12 - BASEMENT FLOOR
FIRE DAMPER SCHEDULE

New Symbol	Existing Label	Site	Building	Level	Room #	Location	Type	Access Panel	Operating	Required	Measurement (size)	Picture #	Comments
		HS/FM	541/542/123/446	B01/123/446a		ACW/FL/W	Fusible / Motorized	Y / N	Y / N	Y / N	"x" x "	1,2,3,4,	
B13	FD102	HS	12	B	AB02	W	F	Y	Y	Y	8 x 16	8658	
B15		HS	12	B	AB21	W	M	Y	Y	Y	8 x 10	8660	Outside AB21 in corridor
B16		HS	12	B	AB21	W	M	Y	Y	Y	8 x 10	8661	Outside AB21 in corridor
B17		HS	12	B	DB19	W	F	Y	Y	Y	12 x 8	8662	Elevator Equipment
B21		HS	12	B	AB08B	W	U	N	U	Y	20"		can't confirm
B22		HS	12	B	AB08B	FL	U	N	U	Y	32"		can't confirm
B23		HS	12	B	AB08B	FL	U	N	U	Y	48 x 48		can't confirm
B24		HS	12	B	AB08B	FL	U	N	U	Y	38"		can't confirm
B25		HS	12	B	AB08B	FL	U	N	U	Y	62 x 48		can't confirm
B26		HS	12	B	AB08B	W	U	N	U	Y	60 x 24		can't confirm

PLAN NOTES: (XX)

A. BUSINESS OCCUPANCY AT ELEVATOR & EXIT CORRIDOR – 30 MINUTE SMOKE RATED WALLS REQUIRED (NOT 2 HOUR FIRE RATED WALLS)

B. 2 HOUR FIRE RATED WALL REQUIRED AROUND VERTICAL SHAFT

C. 2 HOUR FIRE RATED WALL REQUIRED AROUND MECHANICAL ROOM BECAUSE OF VERTICAL PENETRATIONS

SYMBOLS LIST

- 2 HOUR FIREWALL
- 1 HOUR FIREWALL
- 2 HOUR FIRE/SMOKEWALL
- 1 HOUR FIRE/SMOKEWALL
- 30 MINUTE SMOKE BARRIER
- SMOKE RESISTIVE HAZARDOUS AREA
- HORIZONTAL EXIT
- EXIT
- EXIT PASSAGEWAY
- SUITE DESIGNATIONS
- AREA OPEN TO CORRIDOR – WITH SMOKE DETECTION
- AREA OPEN TO CORRIDOR – NO SMOKE DETECTION REQUIRED
- EXISTING FIRE DAMPER
- REQUIRED FIRE DAMPER (FUTURE)

1 BUILDING 12 – BASEMENT FLOOR PLAN – REQUIRED FIRE DAMPERS
3/32" = 1'-0"

NORTH

Revisions	Date

CONSULTANTS:

ARCHITECT/ENGINEERS:

SCHEMMER
ARCHITECTS | ENGINEERS | PLANNERS
TPA PROJECT NO: 60264.000

Drawing Title: BUILDING 12 - BASEMENT FLOOR PLAN - REQUIRED FIRE DAMPERS

Approved: Project Director

Project Title: Department of Veterans Affairs Medical Center Fire Damper Survey

Location: Hot Springs, South Dakota

Date: 3/29/2012 | Checked: RJR | Drawn: BDC

Project Number: 568-11-211

Building Number: 12

Drawing Number: Dwg. of

Office of Construction and Facilities Management

VA FORM 08-6231