

SCOPE OF WORK

EXCAVATE SECTION 1II-A JEFFERSON BARRACKS NATIONAL CEMETERY, ST. LOUIS, MO 63125

- A. The Contractor: Shall provide all labor, tools, materials, and equipment necessary to excavate to a minimum depth of 9'-0", backfill, and restore turf in burial section 1II-A to prepare the section for standard burial operations.
- B. The Work: The Work shall include, but shall not be limited to the following (not necessarily in the order indicated):
 - 1. Stripping, stockpiling, and replacement of suitable topsoil materials.
 - 2. Excavation and removal from the site of unsuitable materials and rock and disposal at an approved fill site;
 - 3. Excavation, stockpiling, and replacement of suitable backfill material.
 - 4. Provide additional suitable clean material to backfill the excavation.
 - 5. Compact and grade the backfilled materials.
 - 6. Replace stripped topsoil, compact and grade.
 - 7. Install new turf sod over disturbed areas.
 - 8. Provide temporary irrigation to establish the new turf.
- C. Time of Completion: The project shall be completed within 60 calendar days after contract award.
- D. Contractor Quality Control: The Job Site Superintendent will: a) review and approve submittals, b) inspect the quality of work performed, and c) certify the completed work, payrolls, and other purposes prior to submission of invoices to NCA for payment .
- E. Availability/Constraints of Site: See attachment "*Jefferson Barracks National Cemetery - Additional Information and Requirements.*"
- F. Environmental Controls: Temporary erosion control measures may be required.
- G. Submittals After Award: None
- H. Pre-bid Site Inspection: A pre-bid site inspection can be arranged if desired. Contact the Cemetery Director at (314) 845-8320 to make site visit arrangements.
- I. POC: The Contracting Officer's Representative (COR) for this project is Terry Smart; Jefferson Barracks National Cemetery.
- J. Project completion: The project site shall be protected and/or restored to a condition equal to that existing prior to the commencement of work.

END OF SCOPE OF WORK