



- CORE DRILL 2" DIA VERTICAL PENETRATION FROM SECOND FLOOR TO ATTIC.
- PROVIDE & INSTALL 2" CONDUIT VERTICAL RISER FROM BASEMENT TO ATTIC WITH BREAKOUTS ON FLOOR 1 & FLOOR 2.
- CONTRACTOR TO VERIFY LOCATION WITH C.O.R.

- CORE DRILL 1" DIA VERTICAL PENETRATION FROM FLOOR 2 TO ATTIC.
- PROVIDE & INSTALL 1" CONDUIT VERTICAL RISER FROM FLOOR 1 TO ATTIC WITH BREAKOUT ON FLOOR 2.
- CONTRACTOR TO VERIFY LOCATION WITH C.O.R.

Revisions		Date	
SCALE: 1/8" = 1'-0"		Approved:	
		PROGRAM MANAGER, PROJECTS	
		SAFETY INDUSTRIAL HYGIENE	
		HEALTH SYSTEMS SPECIALIST	
		MAINTENANCE SUPERVISOR	
		MAINTENANCE FOREMAN	
Drawing Title		Project Title	
BUILDING 17		CONSTRUCT RACEWAYS	
SECOND FLOOR			
Approved: Senior Engineer		Building Number	
		17	
Approved: Senior Director		Checked	
		BONEAL	
		Drawn	
		BONEAL	
		Drawing No.	
		520-14-132	
		Date	
		11/20/2013	
		Page 1 of 1	
		17-2	
		Office of Facilities	
		Department of Veterans Affairs	