GENERAL & MISC.EQUIP.

SYSTEM	GRAPHIC	INTERCOM STATION	ANALOG INDICATION: TEMPERATURE	REL.HUMIDITY	PRESSURE	C.F.M.	K.W.	G.P.M.	K.W.H.	# / HR.	ALARM: STATUS	HIGH/LOW	HIGH	LOW	CRITICAL	MAINTENANCE	CONTROL: STATUS	ON—OFF	ON—OFF—AUTO	OPEN—CLOSE	ADJUSTMENT	VIA LOCAL HOA	RUN TIME TOTAL	PROGRAM START STOP	MAINTENANCE PROGRAM	REMARKS
GENERAL & MISC.																										
EACH SER. BAY A,B,C,D																										ALSO LOCATION FURTHER LISTED
BSMT. THRU P.H. LEVELS		X																								IN THESE I/O SCHEDULES.
OUTDOOR DB			X																							
OUTDOOR WB			X																							
OUTDOOR DEW POINT			X																							
OUTDOOR				X																						
LAB COLD ROOMS			X									X		X												
AUTOPSY COLD ROOM			X									X		X												
CANTEEN REFRIG. & FREEZER			X									X		X												
DIETITIC REFRIG. & FREEZER			X									X		X												
HEPA FILTER CONTROL	X				X							X			X									X		PROVIDE FOR EACH LOCATION.
RADIOISOTOPE HOOD	X				X							X			X									X		PROVIDE FOR EACH LOCATION.

SYSTEM	GRAPHIC	INTERCOM STATION	ANALOG INDICATION: TEMPERATURE	REL.HUMIDITY	PRESSURE	C.F.M.	K.W.	G.P.M.	K.W.H.	# / HR.	ALARM: STATUS	HIGH/LOW	HIGH	LOW	CRITICAL	MAINTENANCE	CONTROL: STATUS	ON—OFF	ON—OFF—AUTO	OPEN—CLOSE	ADJUSTMENT	VIA LOCAL HOA	RUN TIME TOTAL	PROGRAM START STOP	MAINTENANCE PROGRAM	REMARKS
DENTAL COMP AIR																										
(SERVICE BAY - D)																										
COMPRESSOR	X									X	X			X	X					X		X		X		
DENTAL ORAL EVAC SYSTEM																										
(SERVICE BAY - D)	X									X	X			X	X					X		X		X		
NITROGEN SYSTEM																										ALSO RESERVE SWITCH OVER
(SERVICE BAY - C)				X						X	X			X												ALARM - MAINTENANCE.
NITROUS OXIDE (BSMT LOADING	X			X						X	X			X												ALSO RESERVE SWITCH OVER
DOCK GAS STORAGE ROOM)																										ALARM - MAINTENANCE.
BULK OXYGEN SUPPLY	X			X						X	X			X												LEVEL ALARM. ALSO RESERVE
(BSMT AREA C)																										SWITCH OVER ALARM - MAINTENANCE
INTER-VENT FANS	X									X				X	X							X		X		SEE DWGS. FOR NO. AND
																										LOCATIONS
SERV. BAY VENT FANS	X									X				X	X											SEE DWGS. FOR NO. AND
																										LOCATIONS
ATRIUM SMOKE FANS	X									X				X			X					X		X		SEE DWGS. FOR NO. AND
																										LOCATIONS

EQUIP.GROUPED BY FLOORS

SYSTEM	GRAPHIC	INTERCOM STATION	ANALOG INDICATION: TEMPERATURE	REL.HUMIDITY	PRESSURE	C.F.M.	K.W.	G.P.M.	K.W.H.	# / HR.	ALARM: STATUS	HIGH/LOW	HIGH	LOW	CRITICAL	MAINTENANCE	CONTROL: STATUS	ON—OFF	ON—OFF—AUTO	OPEN—CLOSE	ADJUSTMENT	VIA LOCAL HOA	RUN TIME TOTAL	PROGRAM START STOP	MAINTENANCE PROGRAM	REMARKS
PARKING LEVEL P3																										
DEWATERING SUMP																										
PUMPS P-50 THRU P-55												X		X		X					X		X		X	HIGH WATER ALARM
SUMP PUMP P-56												X		X		X					X		X		X	HIGH WATER ALARM
GARAGE EXHAUST FANS																										
VAF39, VAF40	X										X				X	X		X					X		X	
SPACE TEMPERATURE			X																							LOCATE AT COL. 8F
PARKING LEVEL P2																										
GARAGE EXHAUST FANS																										
VAF41, VAF42	X										X				X	X		X					X		X	
ELEV. M.R. VENT FAN PEF67	X										X				X	X		X					X		X	
ELEV. M.R. AC34	X										X				X	X		X					X		X	
SEWAGE EJECTOR P57												X		X		X					X		X		X	
SPACE TEMPERATURE			X																							LOCATE AT COL. 8F
DISTRICT STEAM FLOW										X																
PARKING LEVEL P1																										
GAS BOOSTER PUMP											X				X	X					X		X		X	
GARAGE EXHAUST FANS																										
VAF43, VAF44	X										X				X	X		X					X		X	
ELEVATOR M.R. VENT FAN																										
PEF68	X										X				X	X		X					X		X	
BASEMENT LEVEL																										
EMERG GEN. FUEL OIL PUMPS	X	X																								
P65, P66		X									X			X		X		X					X		X	
DOMESTIC BOOSTER WATER																										
PUMPS P58, P59, P60											X				X						X					FOR EACH PUMP
BOOSTER WATER SYSTEM				X								X	X	X												PRESSURE FOR SYSTEM
																										INCOMING & DISCHARGE
PNEUMATIC TRASH/LINEN																										
EXHAUSTERS 1 & 2															X	X		X					X			
ELECT. SWITCHGEAR ROOM																										
VENT 1CF32, 1CF66															X	X		X					X		X	
SPACE TEMPERATURE		X																								
FLAM STORAGE	X																									
RM EX CF124											X				X	X		X					X		X	

SYSTEM	GRAPHIC	INTERCOM STATION	ANALOG INDICATION: TEMPERATURE	REL.HUMIDITY	PRESSURE	C.F.M.	K.W.	G.P.M.	K.W.H.	# / HR.	ALARM: STATUS	HIGH/LOW	HIGH	LOW	CRITICAL	MAINTENANCE	CONTROL: STATUS	ON—OFF	ON—OFF—AUTO	OPEN—CLOSE	ADJUSTMENT	VIA LOCAL HOA	RUN TIME TOTAL	PROGRAM START STOP	MAINTENANCE PROGRAM	REMARKS
BASEMENT LEVEL CONT.																										
CONDENSATE PUMPS P33, P34															X	X					X		X		X	
SUBSTATION VENT - 1CF45,																										INTERCOM IN EACH SUBSTATION
1CF46, 1CF47, 1CF48	X	X									X				X	X		X					X		X	ROOM A,B,C,D
EMER. GEN FUEL OIL TANK													X	X	X											FUEL LEVEL
FIRE PUMP P62		X													X						X		X		X	INTERCOM IN FIRE PUMP ROOM
FIRE JOCKEY P63											X				X			X			X		X		X	
DRY SPRINKLER SYSTEM																										
AIR COMPRESSOR											X				X	X		X								
BSMT LOADING DOCK																										
EXH 1CF139	X										X				X	X		X			X		X		X	
BSMT TRASH ROOM																										
EXH 1CF140	X										X				X	X		X			X		X		X	
SPACE TEMPERATURE		X																								LOCATE AT COL. 8F
DISTRICT STEAM FLOW									X																	
FIRE PUMP ROOM																										
VENT PEF126	X										X				X	X		X					X		X	
STORAGE RM 1PD100																										
VENT CF116	X										X				X	X		X					X		X	
TELE RM 1PA106	X		X																							SPACE TEMP.
AC																										
COND UNIT 1											X				X	X		X				X			X	
A/C UNIT 1			X								X				X	X		X	X			X			X	SELECT 1 OR 2 SYSTEM
SMOKE DETECTOR														X												
COND UNIT 2											X				X	X						X			X	
A/C UNIT 1			X								X				X	X		X	X			X			X	SELECT 1 OR 2 SYSTEM
SMOKE DETECTOR														X												

8-0-1-1356

Revisions	Date
"AS BUILT"	6-17-94

RECORD COPY
CORRECTED ON BASIS OF DATA
FURNISHED BY THE RESIDENT ENGINEER

Key Plan

Seal

RTKL/CS&D/HENRY ADAMS (J.V.)
ARCHITECTS AND ENGINEERS
400 E. PRATT STREET
BALTIMORE, MD 21202

Drawing Title: E.C.C. INPUT / OUTPUT BINS SCHEDULES HVAC

Approved Project Director: John F. Miller

Project Title: 324-BED REPLACEMENT HOSPITAL-PHASE II

Building Number: 1

Location: VAMC-BALTIMORE, MD

Checked | Drawn

Date: 9/1/88

Project No. 511-001D

DRAWING NO. 1-H96

Dwg./2301/123

Veterans Administration

VA FORM 08-6231A, MAR 1984

☆ U.S. GOVERNMENT PRINTING OFFICE: 1984-440-467

V0022A0