1 1st Floor Finish Plan - Area B
1/8" = 1'-0"

INTERIOR FINISH REMARKS:

A. SEE ENLARGED FINISH PLAN FOR FLOOR MATERIAL PATTERN.
B. SEE ELEVATIONS FOR PANEL TYPES, CONFIGURATION AND LAYOUTS.
C. ALL HORIZONTAL COUNTERTOPS AND BACKSPLASHES TO BE SSM-4. ALL VERTICAL UPPER & LOWER CABINETS TO BE LAM-4. SEE ELVATIONS, DETAILS & SECTIONS.
D. ALL HORIZONTAL COUNTERTOPS AND BACKSPLASH TO BE SSM-1. ALL VERTICAL UPPER & LOWER CABINETS TO BE LAM-4.
E. 1/2 HEIGHT WALL AT SERVING COUNTER TO BE SSM-1. COUNTERS TO BE SSM-1.
F. NA
G. PT-21 TO BE INSTALLED 2'-0" TO EITHER SIDES OF JANITOR'S SINK AND 4'-0" A.F.F.
H. ALL VERTICAL SURFACES TO BE LAM-4. ALL HORIZONTAL SURFACES TO BE LAM-7.
I. ALL VERTICAL SURFACES TO BE LAM-4. ALL HORIZONTAL SUFACES TO BE LAM-9.
J. ALL VERTICAL SURFACES TO BE LAM-4. ALL HORIZONTAL SUFACES TO BE LAM-9.
K. SEE REFLECTED CEILING PLAN FOR FINISHES & MATERIAL SPECIFICATIONS.
L. SEE ELEVATIONS FOR LOCATIONS OF WALL FINISHES, CHAIR RAILS AND CROWN MOLDING.
M. SEE ELEVATIONS AND ENLARGEMENT DETAILS FOR TILE DESIGN AND SPECIFICATION.
N. INSTALL TILE ON 45 DEGREE ANGLE.
O. ALL HORIZONTAL COUNTERTOPS AND BACKSPLASHES TO BE SSM-2. ALL VERTICAL SURFACES TO BE LAM-4.
P. EXISTING FLOORING AND CEILING GRID AND TILES TO REMAIN. PATCH WALLS AND BASE TO MATCH EXISTING.
Q. ALL HORIZONTAL COUNTERTOPS TO BE LAM-10. ALL VERTICAL UPPER AND LOWER CABINETS TO BE LAM-4.
R. VENDOR SUPPLIED CABINETRY BY ADEC. FINISHES TO BE WILSONART, 10745-60 FONTHILL PEAR FOR VERTICAL CABINETRY. HORIZONTAL COUNTERS TO BE SOLID SURFACE GIBRALTER, BEIGE TEMPEST 1530TM. METAL BASE TO BE SLATE 86.0970.00. CHAIR SEAMLESS UPHOLESTERY TO BE TAWNY 61.3600.32.
S. FLOOR TO HAVE 6" COVE BASE.
T. INSTALL VWC-18.36" A.F.F. TO 7'-0" A.F.F. WITH ALUMINUM TRIM SURROUND AND MARKER BOARD TRAY, SEE PLAN FOR LOCATION.
U. MILLWORK BY FURNITURE VENDOR SEE DRAWINGS.

GENERAL INTERIOR FINISH NOTES:

1. ALL GROMMETS TO BE 2" DIAMETER, COLOR TBD AND TO BE APPROVED BY THE INTERIOR DESIGNER.
2. REFER TO FINISH ROOM TAG FOR WALL PAINT COLORS. ALL PAINT TO BE EGGSHELL FINISH, UNLESS OTHERWISE NOTED.
3. TRANSITIONS BETWEEN DISSIMILAR FLOOR FINISHES TO OCCUR AT CENTERLINE OF DOOR UNLESS NOTED OTHERWISE.
   INSTALL TRANSITION STRIPS PER DETAILS ON IF701. INTERIOR DESIGNER TO APPROVE COLOR OF TRANSITION STRIP.
4. ALL HORIZONTAL COUNTERTOPS AND BACKSPLASHES TO BE LAM-1 U.N.O. ALL VERTICAL SURFACE OF UPPER AND
   LOWER CABINETS TO BE LAM-4 U.N.O.
5. ALL WINDOW SILLS TO BE SSM-5.
6. ALL FIRE EXTINGUISHER CABINETS, ELECTRICAL PANELS, SUPPLIES AND METAL GRILLS TO BE FACTORY PAINTED ENAMEL PAINT. PAINT TO MATCH ADJOINING WALL AND CEILING FINISH FOR SPECIALITY CEILINGS.
7. NOT USED
8. TOILET PARTITIONS TO BE HDPE, SOLID PLASTIC - AMPCO, KHAKI 947-122.
9. ALL DOORS TO BE STAINED TO MATCH LAM-4.
10. ALL GROUT TO BE SEALED A MINIMUM OF 2 TIMES.
11. ALL GROUT JOINTS TO BE 1/4" MINIMUM U.N.O.
12. ALL WINDOWS TO RECEIVE ROLLER SHADES RS-1 U.N.O., SEE DOOR AND WINDOW SCHEDULE.
13. JANITOR'S CLOSET WILL HAVE TILE, PT-21 TO BE INSTALLED UP TO 48" A.F.F. AND 2'-0" TO EITHER SIDE OF SINK.
14. ALL CONTINUOUS CAULK AT BACKSPLASH TO BE CLEAR.
15. ALL CORNERGUARD TO BE CG-1 U.N.O. BOTTOM EDGE OF CG-1 TO START AT TOP OF BASE.
16. ALL WALL GUARDS TO BE WG-1 U.N.O. WITH MATCHING TOP CAP.
17. ALL BASE TO BE RB-1 U.N.O.
18. ALL SUBFLOORS TO BE LEVELED PRIOR TO FLOORING INSTALLATION - TYP.
19. STAIR RUNNER AND RISER TO BE PAINTED P-2 WITH ENAMEL FINISH U.N.O. TREADS TO BE TR-1 AND LANDING TO BE RF-1. HANDRAIL AND POST IN STAIR 101 TO BE PAINTED P-2.
20. COORDINATE WITH ARCHITECTURAL DRAWINGS FOR ALL NON-FINISH DETAILS.
21. INSIDE OF OPEN CABINETS TO MATCH ADJACENT CABINET FINISH.
22. ALL ELEMENTS THAT APPEAR TO ALIGN, MUST ALIGN.
23. FLOOR TILES SHOULD BE INSTALLED IN PATTERN SHOWN U.N.O.
24. CHALK LINES FOR FLOORING TO BE VERIFIED BE INTERIOR DESIGNER BEFORE INSTALLATION OF MATERIALS.
25. ALL RESIDENT ROOM ENTRY DOORS TYPE D3 & D11 TO RECEIVE DFG-1 48" HIGH AND DP-1 24" HIGH ON THE BOTH SIDES OF THE DOOR.

FLOORING LEGEND

PT-1 · LVT-9 · SV-2 Border · SV-1 · LN-1

FINISH LEGEND:

ACT-1 Wall Base Floor — CEILING FINISH; MOLDINGS AND TRIMS; REMARKS; WALL FINISH; BASE FINISH; FLOOR FINISH
CPT — VCT — LOCATION OF TRANSITION OF MATERIALS

MOLDINGS AND TRIMS
1 - CRM-1
2 - CRM-2
3 - CRM-3
4 - CR-1
5 - CR-2
10 - MP-1
11 - MP-2
12 - MP-3

CG1 CORNER GUARDS
EG1 END GUARDS
WG WALL GUARD
HR HAND RAIL

KEY PLAN



Department of Veterans Affairs

Architect of Record

rpadesign
5960 Fairview Road
Suite 500
Charlotte, NC 28210
704
887.3500
887.3507 fax

Consultants

MECHANICAL/ELECTRICAL/PLUMBING FIRE PROTECTION:
AME Consulting Engineers, PC
421 Penman Street, Suite 200
Charlotte, NC 28203
704.295.4263 PHONE
704.295.7543 FAX

STRUCTURAL:
ZAPATA, Inc.
6302 Fairview Rd., Ste. 600
Charlotte, NC 28210
704.378.4923 PHONE
704.358.8342 FAX

CIVIL:
COLEJENEST & STONE, P.A.
200 South Tryon Street, Suite 1400
Charlotte, North Carolina 28202
704.376.1555 PHONE
704.376.7851 FAX

Project
VAMC Salisbury
Building 42 Additions & Renovation - Phase III

City, State
Salisbury, NC

VA Project Number
659-335

Issued For
Construction

Item	Date	Description
1	01/31/14	Amendment A00003
2	02/21/14	Amendment A00004

Drawn By SLS/SP/BR/FF/ES/AB
Checked By FF

Seal / Signature

FRANKLIN EUGENE FREEMAN REGISTERED ARCHITECT 9311 NORTH CAROLINA CHARLOTTE, N.C. 2/21/14

RPA DESIGN, PC REGISTERED ARCHITECTURAL CORPORATION NORTH CAROLINA CERT. NO. 50913 CHARLOTTE, N.C.

Sheet Title
Interior Finish Plan - First Floor Area B

Date December 21, 2012

Sheet Number
IF101B

This document is the property of RPA Design and RPA Design retains all rights therein, including copyrights.
It may only be used in a manner consistent with RPA Design's rights while RPA Design is providing services for the specific project identified or referred to herein or extensions thereto.
It may not be used for any other purpose except with the express written agreement of, and compensation to, RPA Design.

C:\Users\elizabeth.sumner\Documents\09-0005-03_VAMC-Salisbury-Phase-III_Main_C14_elizabeth.sumner.rvt
2/21/2014 5:12:48 PM