



- SPRINKLER ZONE DESCRIPTION AND SPRINKLER NOTES**
- THE INDICATED RISERS SHALL SUPPLY ALL SPRINKLERS IN DESIGNATED FIRE PROTECTION ZONES. SPRINKLERS SHALL BE ZONED TO COVER ROOM NUMBERS THAT CORRESPOND TO ZONE LETTER.
  - SEE ALSO INDIVIDUAL PLUMBING FLOOR PLANS.
  - SEE ALSO RISER DRAWING 1-P64.
  - EACH SERVICE BAY PENTHOUSE (A, B, C, D) AT 7TH FLOOR LEVEL SHALL HAVE SPRINKLERS SUPPLIED THROUGH A FLOW SWITCH IN EACH PENTHOUSE ON RESPECTIVE RISER.
  - CENTER PENTHOUSE AT 7TH AND 8TH FLOORS SHALL HAVE SPRINKLERS SUPPLIED THROUGH A FLOW SWITCH ON 7TH AND 8TH FLOOR FROM RISER.
  - PROVIDE INDICATED DRY SPRINKLERS FROM DRY VALVES FROM RISER.
  - SEE PARKING LEVEL FLOOR PLANS FOR DRY SPRINKLER SYSTEM IN GARAGE.
  - THE FLOOR PLANS ON THIS DRAWING INDICATE GENERAL ARRANGEMENT OF SHOWN AND/OR FIRE WALLS THAT FORM ZONES. SEE ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS.
  - RISERS SHALL ALSO SUPPLY SPRINKLERS BELOW THE WEST ATRIUM SKYLIGHT AND IN THE OPEN SERVICE WALKWAY AROUND THE WEST ATRIUM AT THE SEVENTH FLOOR.
  - RISER SHALL ALSO SUPPLY SPRINKLERS BELOW THE EAST ATRIUM SKYLIGHT AND IN THE OPEN SERVICE WALKWAY AROUND THE EAST ATRIUM AT THE SEVENTH FLOOR.
  - THE 9TH FLOOR ELEVATOR MACHINE FOR ELEVATORS P-1, 2, 3 SHALL HAVE A FLOW SWITCH AND SUPERVISED VALVE FROM RISER.
  - ALL OTHER ELEVATOR AND TRANSPORT LIFT SYSTEMS SHALL HAVE SPRINKLER SUPPLIED AS PART OF THE INDICATED ZONE WITH A SUPERVISED VALVE LOCATED OUTSIDE OF THE MACHINE ROOM.

AS BUILT

Revisions

6/17/94

Date

1

2

3

4

5

6

7

8

9

RTKL/CS&D/HENRY ADAMS (J.V.)  
ARCHITECTS AND ENGINEERS  
400 E. PRATT STREET  
BALTIMORE, MD 21202

Project Title

324-BED  
REPLACEMENT  
HOSPITAL - PHASE II

Project No.

511-001D

Drawing No.

I-P65

Location

VAMC-BALTIMORE, MD

Approved Project Director

*[Signature]*

Checked

Drawn

Project Title

324-BED  
REPLACEMENT  
HOSPITAL - PHASE II

Project No.

511-001D

Drawing No.

I-P65

Location

VAMC-BALTIMORE, MD

Date

9/1/88

Project No.

511-001D

Drawing No.

I-P65

Location

VAMC-BALTIMORE, MD

RECORD DRAWING

CORRECTED ON BASIS OF DATA

FURNISHED BY THE RESIDENT ENGINEER

North

C

D

A

B

Key Plan

1

2

3

4

5

6

7

8

9

Scale

one-eighth inch = one foot

one-quarter inch = one foot

three-eighths inch = one foot

one-half inch = one foot

three-quarters inch = one foot

one inch = one foot

one and one-half inch = one foot

three inches = one foot

8-0-1-1220

H.A. JOB NO. V0022A0