

AMENDMENT NO. A00001

SOLICITATION: VA261-14-B-0259

PROJECT: 640-13-1-102P

BIDDER QUESTIONS AND CLARIFICATIONS

QUESTION: I am unable to locate the specification for installation of bird deterrent devices.

ANSWER: That information is not contained in specifications, only on drawings. However, see attached bird wire cut sheet. This is NOT a brand name requirement and is intended to be descriptive, but not restrictive, and is to indicate the quality and characteristics of products that will be satisfactory.

QUESTION: Please provide the lead based paint report.

ANSWER: For lead abatement see demolition note (1) on drawing 100-GD-10-1.0 which states "Contractor shall abate lead paint before cutting steel rail to prevent dispersion of lead on Government property. Please refer to lead abatement specification, contractor may remove guardrail with existing paint and abate / dispose off site in conformance to applicable state and county requirements. See attached lead based paint report.

QUESTION: Identify which parts of the guardrail are to be stainless steel and also which parts are to be painted.

ANSWER: See guardrail details and elevations on drawing 100-A-30-3.0. All components to be epoxy painted except for stainless steel mesh screen and "U" edging per screen manufacturer.

QUESTION: Will there be a material laydown area that the contractor can utilize during the project? If so, please identify the location.

ANSWER: There will be adequate operations and storage area for contractor use. Laydown area will be in the vicinity but not in the immediate project area. Exact location is not known at this time.