DOOR AND FRAME SCHEDULE

	MARK	DOOR SIZE WD	DOOR SIZE HGT	DOOR MATL	DOOR GLAZING	ELEV	FRAME MATL	FRAME DETAIL HEAD	FRAME DETAIL JAMB	FRAME DETAIL SILL	FIRE RATING LABEL	HARDWARE SET NO	NOTES
THIS GROUP NOT IN SCOPE EXCEPT 7 DOORS SHOWN IN SCOPE	I2-100	3'-8"	7'-0"	WD		A	EX.	--	--	--	45 MIN.	43	WIREGLASS
	I2-101	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	I2-102	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	I2-103	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	I2-104	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	1	--
	I2-104A	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	45	--
	I2-105	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	I2-105A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	I2-106	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	I2-107	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	I2-107A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	I2-108	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	I2-109	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	I2-109A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	I2-109A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	I2-110	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	I2-111	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	I2-112	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	I2-112A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	I2-112A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	I2-113	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	I2-114	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	47	--
	I2-114A	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	9	--
	I2-114B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	10	UNDERCUT ¾" ABOVE FINISH FLOOR
	I2-115	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	I2-116	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	I2-117	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
THIS GROUP NOT IN SCOPE EXCEPT 13 DOORS SHOWN IN SCOPE	H2-100	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	H2-100A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	H2-101	3'-8"	7'-0"	EX		B	EX.	--	--	--	45 MIN.	43	--
	H2-102	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	H2-102A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	H2-102A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	H2-103	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	H2-104	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	H2-105	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	H2-105A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	H2-106	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	H2-107	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	H2-107A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	H2-108	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	--	--
	H2-108A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	H2-108A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	H2-109	3'-10"	7'-0"	WD		A	EX.	--	--	--	--	23	LAMINATED GLASS
	H2-110	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	H2-111	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	47	--
	H2-112A	3'-10"	7'-0"	WD		A	EX.	--	--	--	--	9	POLYCARBONATE GLASS
	H2-112B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	10	UNDERCUT ¾" ABOVE FINISH FLOOR
	H2-113	3'-8"	7'-0"	WD		A	EX.	--	--	--	--	43	WIREGLASS
	H2-114	3'-0"	7'-0"	WD		A	EX.	--	--	--	45 MIN.	23	LAMINATED GLASS
	H2-116	6'-0"PR	7'-0"	WD		D	EX.	--	--	--	--	28	--
	H2-117	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	J2-100	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	25	REINSTALL PEEP
	J2-100A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	7	--
	J2-101	3'-0"	7'-0"	WD		A	EX.	--	--	--	--	25	LAMINATED GLASS
	J2-101A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	J2-101B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	J2-102	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	J2-103	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	J2-104	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	J2-105	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	REINSTALL PEEP
	J2-106	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	REINSTALL PEEP
	J2-107	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	J2-108	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	J2-109	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	J2-110	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	J2-111	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	J2-112	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	13	--
THIS GROUP NOT IN SCOPE EXCEPT 12 DOORS SHOWN IN SCOPE	G2-100	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	G2-101	3'-8"	7'-0"	WD		A	EX.	--	--	--	45 MIN.	43	WIREGLASS
	G2-102	5'-4"PR	7'-0"	WD		D	EX.	--	--	--	--	28	--
	G2-104	3'-0"	7'-0"	WD		A	EX.	--	--	--	45 MIN.	23	LAMINATED GLASS
	G2-105	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	47	--
	G2-105A	3'-10"	7'-0"	WD		A	EX.	--	--	--	--	9	POLYCARBONATE GLASS
	G2-105B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	10	UNDERCUT ¾" ABOVE FINISH FLOOR
	G2-106	3'-0"	7'-0"	WD		A	EX.	--	--	--	--	25	LAMINATED GLASS
	G2-107	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	G2-107A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	G2-107A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	G2-108	3'-10"	7'-0"	WD		A	EX.	--	--	--	--	23	LAMINATED GLASS
	G2-109	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	G2-110	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	G2-110A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	G2-111	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	G2-112	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	G2-112A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	G2-113	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	G2-113A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	G2-113A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	G2-114	3'-0"	7'-0"	WD		B	EX.	--	--	--	45 MIN.	43	--
	G2-115	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	G2-116	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	G2-116A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	A2-102	3'-8"	7'-0"	WD		A	EX.	--	--	--	--	23	LAMINATED GLASS
	A2-102-A	3'-0"	7'-0"	WD		A	EX.	--	--	--	--	23	LAMINATED GLASS
	A2-103	3'-8"	7'-0"	WD		A	EX.	--	--	--	--	23	LAMINATED GLASS
	A2-103A	6'-0"PR	7'-0"	WD		D	EX.	--	--	--	--	28	--
	A2-104	3'-0"	7'-0"	WD		B	EX.	--	--	--	45 MIN.	43	--
	A2-105	6'-0"PR	7'-0"	WD		C	EX.	--	--	--	--	86	LAMINATED GLASS
	A2-105-A	3'-0"	7'-0"	WD		A	EX.	--	--	--	--	84	LAMINATED GLASS
	A2-105A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	F2-100	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	F2-100A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	F2-101	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	F2-102	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	F2-103	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	F2-104	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	F2-105	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	F2-106	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	F2-107	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	F2-108	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	F2-109	3'-0"	7'-0"	WD		A	EX.	--	--	--	--	--	LAMINATED GLASS
	F2-109A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	F2-109B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	B2-100	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	157	--
	B2-101	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	B2-102	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	B2-103	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	B2-104	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	B2-105	3'-0"	7'-0"	WD		A	EX.	--	--	--	--	23	LAMINATED GLASS
	B2-105A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	B2-105B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--
	B2-106	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	B2-107	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	REINSTALL PEEP
	B2-107A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	--

DOOR AND FRAME SCHEDULE

	MARK	DOOR SIZE WD	DOOR SIZE HGT	DOOR MATL	DOOR GLAZING	ELEV	FRAME MATL	FRAME DETAIL HEAD	FRAME DETAIL JAMB	FRAME DETAIL SILL	FIRE RATING LABEL	HARDWARE SET NO	NOTES
THIS GROUP NOT IN SCOPE EXCEPT 8 DOORS SHOWN IN SCOPE	E2-100	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	E2-100A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	E2-101	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	E2-102	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	E2-102A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	E2-102A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	E2-103	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	E2-103A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	E2-104	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	E2-105	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	E2-105A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	E2-106	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	E2-107	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	1	--
	E2-107A	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	1	--
	E2-108	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	E2-108A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	E2-108A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	E2-109	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	E2-110	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	E2-111	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	E2-112	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	47	--
	E2-112A	3'-10"	7'-0"	WD		A	EX.	--	--	--	--	9	POLYCARBONATE GLASS
	E2-112B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	10	UNDERCUT ¾" ABOVE FINISH FLOOR
	E2-113	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	E2-114	3'-8"	7'-0"	WD		A	EX.	--	--	--	45 MIN.	43	WIREGLASS
	E2-115	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	E2-116	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	E2-117	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
THIS GROUP NOT IN SCOPE EXCEPT 16 DOORS SHOWN IN SCOPE	C2-100	3'-8"	7'-0"	WD		A	EX.	--	--	--	45 MIN.	43	WIREGLASS
	C2-101	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	17	--
	C2-102	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	C2-103	3'-8"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	C2-104	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	1	--
	C2-104A	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	1	--
	C2-105	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	C2-105A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-106	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	C2-107	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	C2-107A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-107A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-108	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	C2-109	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	C2-109A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-109A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-110	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	C2-111	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	C2-112	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	C2-112A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-112A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-113	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	C2-114	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	47	--
	C2-114A	3'-10"	7'-0"	WD		A	EX.	--	--	--	--	9	POLYCARBONATE GLASS
	C2-114B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	10	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-115	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	C2-116	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	C2-117	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
	C2-119	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	23	--
THIS GROUP NOT IN SCOPE EXCEPT 16 DOORS SHOWN IN SCOPE	D2-100	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	D2-101	3'-8"	7'-0"	WD		A	EX.	--	--	--	45 MIN.	43	WIREGLASS
	D2-102	6'-0"PR	7'-0"	WD		D	EX.	--	--	--	--	28	--
	D2-105	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	47	--
	D2-105A	3'-10"	7'-0"	WD		A	EX.	--	--	--	--	9	POLYCARBONATE GLASS
	D2-105B	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	10	UNDERCUT ¾" ABOVE FINISH FLOOR
	D2-107	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	D2-107A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	D2-107A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	D2-108	3'-10"	7'-0"	WD		A	EX.	--	--	--	--	23	LAMINATED GLASS
	D2-109	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	D2-110	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	D2-110A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	D2-111	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	13	--
	D2-112	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	3	--
	D2-112A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	D2-113	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	D2-113A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	D2-113A-A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	D2-114	3'-4"	7'-0"	WD		B	EX.	--	--	--	--	43	--
	D2-115	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	D2-116	3'-8"	7'-0"	WD		B	EX.	--	--	--	45 MIN.	43	--
	D2-116-A	3'-8"	7'-0"	WD		B	EX.	--	--	--	45 MIN.	43	--
	D2-117	3'-10"	7'-0"	WD		B	EX.	--	--	--	--	7A	--
	D2-117A	3'-0"	7'-0"	WD		B	EX.	--	--	--	--	18	UNDERCUT ¾" ABOVE FINISH FLOOR
	C2-2	7'-9"PR.	7'-0"	ACR		C	EX.	--	--	--	45 MIN.	5	WIRE / POLYCARBONATE
	C2-2-A	7'-9"PR.	7'-0"	ACR		C	EX.	--	--	--	--	5	WIRE / POLYCARBONATE
	C2-4	7'-9"PR.	7'-0"	ACR		C	EX.	--	--	--	45 MIN.	5	WIRE / POLYCARBONATE
	C2-9	7'-9"PR.	7'-0"	ACR		C	EX.	--	--	--	45 MIN.	5	WIRE / POLYCARBONATE
	C2-7	7'-9"PR.	7'-0"	ACR		C	EX.	--	--	--	45 MIN.	5	WIRE / POLYCARBONATE
	C2-8	7'-9"PR.	7'-0"	ACR		C	EX.	--	--	--	45 MIN.	5	WIRE / POLYCARBONATE

SCHEDULE KEY



NOTE: DOOR NUMBERS ARE ROOM NUMBERS. WHERE MORE THAN ONE DOOR OCCURS AT A ROOM A SUFFIX IS ADDED AND KEYED ON THE DRAWING.

NOTES

1. VERIFY DOOR SIZES AND FIT TO EXISTING FRAMES
2. MATCH EXISTING FIRE RATINGS ON ALL DOORS.

Revisions | Date

BIRCHFIELD PENUEL & ASSOCIATES, ARCHITECTS
2805 CRESCENT AVENUE · SUITE 200 · BIRMINGHAM, ALABAMA 35209

STATE OF ALABAMA — CHARLES E. PENUEL NO. 2395, WILLIAM C. BIRCHFIELD NO. 2341, BIRMINGHAM, ALABAMA — REGISTERED ARCHITECT

Door Replacement Building 137
Department of Veterans Affairs
MEDICAL CENTER
TUSCALOOSA, ALABAMA

Drawing Title: DOOR SCHEDULE, SECOND FLOOR

Approved: Chief Engineer

Project Title: DOOR REPLACEMENT BUILDING 137

Date: 01-19-2009
VA Project No. 679-08-115
BPA FILE No. 10508A81_2_3_4
VA Contract No.

Building Numbers: 137 | Checked: WCB | Drawn: FF

Location: VA MEDICAL CENTER TUSCALOOSA, ALABAMA

DRAWING NO. 137-A8.2
Dwg. 7 Of 9

Veterans Administration