

FINISH SCHEDULE (EXPAND MICU)				
ROOM #	ROOM NAME	FLOORING	BASE	WALLS ACCENT FOR WALLS
1F110	SHELL	CONC	N/A	N/A
1F111	ISOLATION ICU	VCT PATT	RB	P6
1F112	SHOWER	CTH	N/A	CT1
1F113	ANTE	VCT FIELD	RB	P5
1F114	ICU	VCT PATT	RB	P1
1F115	ICU	VCT PATT	RB	P1
1F116	ICU	VCT PATT	RB	P1
1F117	ICU	VCT PATT	RB	P1
1F118	ICU	VCT PATT	RB	P1
1F119	SOILED UTILITY	SVF	SVF	P6
1F120	CLEAN UTILITY	VCT FIELD	RB	P1
1F121	NURSE STATION	VCT PATT	RB	P1
1F121	HALL	VCT FIELD	N/A	P1
1F123	MED	VCT FIELD	RB	P1
1F124	NOURISHMENT	VCT FIELD	RB	P1
C1-94	CORRIDOR	VCT FIELD	RB	P1
PROVIDE FLOOR TILE PATTERN TO MATCH THAT IN MICU EAST				
P1	Sherwin-Wms. SW6148 Wool Skin			
P2	Sherwin-Wms. SW6226 Languid blue			
P3	Sherwin-Wms. SW7036 accessible beige semigloss latex			
P4	Sherwin-Wms. SW7036 accessible beige epoxy paint			
P5	Sherwin-Wms. SW6148 Wool skin epoxy paint			
P6	Sherwin-Wms. SW6226 Languid blue epoxy paint			
RB	Flexco Wallflowers wall base WF020 Neutral			
VCT Field	Mannington Essentials 133 Almondine			
CT1	Mannington Essentials 143 Fax			
CT2	American Clean Porte Leone 13 x 13 porcelain tile Noce PL93 laid on the diagonal			
with custom building products epoxy grout color 145 light smoke				
CT2	4" Wainscoat in American Clean Porte Leone 13 x 13 porcelain tile Noce PL93 laid horizontal with grout as above			
Border at top of wainscoat in American Clean Universal Brickwork PL80 3" x 12 1/2"				
Bullnose above border S43E9 in American Clean Porte Leone Noce PL93 3" x 13"				
EXCEPT in showers. Showers walls to be American Clean PL93 laid on horizontal to ceiling				

PATIENT OVERHEAD LIFT SYSTEM

CONTRACTOR SHALL PROVIDE AND INSTALL A PATIENT LIFT SYSTEM FOR EACH PATIENT ROOM. PROVIDE COMPLETE DESIGN AND INSTALL SERVICES, AND PROVIDE EQUIVALENT SYSTEM INSTALLED IN MICU EAST. SYSTEM SHALL EQUAL TO THAT PROVIDED BY BARRIER FREE DESIGN INC. LAYOUT OF TRACKS AND RAILING SHALL MIRROR THAT IN MICU EAST. PROVIDE X-Y COVERAGE OF BED AREA AND IF TOILETS CANNOT BE COVERED WITH THE X-Y COVERAGE, THEN AN ADDITIONAL RAIL AND GATE SYSTEM MUST BE PROVIDED. FULLY COORDINATE WITH VA AND PROVIDE INSTALLATION PLANS AND DETAILS.

EQUIPMENT SCHEDULE

ITEM NO	DESCRIPTION	FURNISHED/INSTALLED
1	VERTICAL HEADWALL UNIT	CONTRACTOR/CONTRACTOR
2	BEDSIDE LAVATORY/TOILET/DIALYSIS CARE UNIT	CONTRACTOR/CONTRACTOR
3	FLAT SCREEN TV - W (WALL HUNG) C- (CEIL HUNG)	CONTRACTOR/CONTRACTOR
4	OVERBED LIGHT	CONTRACTOR/CONTRACTOR
5	VERNA CARE BED PAN FLUSHER	OWNER/CONTRACTOR
6	WALL LAVATORY W/FOOT PEDAL CONTROL	CONTRACTOR/CONTRACTOR
7	MEDICAL WASTE HAMPER	OWNER/OWNER
8	CLEAN LINEN CART (LARGE)	OWNER/OWNER
9	CLEAN LINEN CART (SMALL)	OWNER/OWNER
10	REFRIGERATOR (FULL SIZE)	OWNER/OWNER
11	REFRIGERATOR (UNDER COUNTER)	OWNER/OWNER
12	MICROWAVE	OWNER/OWNER
13	XXXXXXXXXXXX	XXXXXXXXXXXX
14	COFFEE POT	OWNER/OWNER
15	OMNI CELL SUPPLY UNIT	OWNER/OWNER
16	BLANKET WARMER	OWNER/OWNER
17	ICE MACHINE	OWNER/OWNER
18	BLOOD GAS MACHINE	OWNER/OWNER
19	PORTABLE SUPPLY CARTS	OWNER/OWNER
20	CRASH CART	OWNER/OWNER
21	LINEN CART (MEDIUM)	OWNER/OWNER
22	PORTABLE MEDICINE CARTS	OWNER/OWNER
23	RECYCLE SHRED BIN	OWNER/OWNER
24	ISOLATION CARTS	OWNER/OWNER

FIRST FLOOR KEY NOTES

- 1 PROVIDE NURSE'S STATION CASEWORK, CHAIRS AND COUNTERS TO MATCH EXISTING IN MICU EAST.
- 2 PROVIDE CASEWORK IN MEDICATION ROOM, SOILED UTILITY AND NOURISHMENT KITCHEN TO MATCH EXISTING IN MICU EAST.
- 3 CONSTRUCT PIPE CHASES WITH 2" METAL STUDS.
- 4 COUNTERTOP WITH KNEE SPACE BELOW, TOP OF COUNTERTOP TO BE 36" A.F.F. CONSTRUCT WITH ONE LAYER OF 3/4" MEDIUM DENSITY FIBER BOARD & 1" x 2" NOSING, VENEER TOP & EDGE WITH PLASTIC LAMINATE. PLASTIC LAMINATE WILSONART SELECT CHERRY.
- 5 EXISTING HANDRAIL REMAINS
- 6 EXISTING LADDER TO ROOF HATCH ABOVE.
- 7 INSTALL VERTICAL SUPPORT SUSPENDED TO CEIL DECK FOR TV MOUNT. CONSTRUCT SIMILAR TO EXISTING IN EXIST MICU EAST.
- 8 PVC HANDRAIL & BRACKET. MATCH EXISTING HANDRAIL IN MICU EAST.

GENERAL NOTES

- A. FLATSCREEN TV'S SHALL BE MANUFACTURED BY LG COMMERCIAL HOSPITAL GRADE LCD WIDESCREEN, 32-10040 16: 120W MAX. HDTV WITH HD-PPV CAPABILITY. FURNISH MOUNTING BRACKETS AND PIVOT ARM TO MATCH EXISTING INSTALLATION. REF: WWW.LGCOMMERCIAL.COM. NOTE: SETUP SHALL INCLUDE NURSE CALL SYSTEM INTERFACE WITH PATIENT CONTROL UNIT.
- B. BEDSIDE LAVATORY/DIALYSIS CARE UNIT SHALL BE MANUFACTURED BY WILLOUGHBY INDUSTRIES-HEALTHCARE PRODUCTS, MODEL #2101, MOD 47 FLOOR MOUNT WITH INTEGRAL CABINET DUAL VALVE DIALYSIS BOX AND INSTALL WALL MOUNTED GRAB BAR AND CURTAIN TRACK AND CURTAIN.
- C. PROVIDE 1" HORIZONTAL MINIBLINDS ON ALL WINDOWS AT THE ALCOVE WORK STATIONS. MATCH THOSE INSTALLED IN MICU EAST. FURNISH LEVELOR BLINDS, COLOR 201 IVORY.
- D. INSTALL WINDOW SHADE SYSTEM, ON EXTERIOR WINDOWS. SHADES SHALL BE EQUAL TO AND MATCH SAME AS IN MICU EAST. FURNISH MECHSHADES, WITH FASCIA. SHADES SHALL BE THERMOVEL 3000 SERIES SATIN AND DIAMOND REVERSIBLE WEAVE FABRIC, 3010 ALABASTER WITH COLONIAL WHITE MECHSHADE FASCIA. (AVAILABLE FROM ARK SHADES, BLINDS AND SHUTTERS, (601.812.4032))

SYMBOL LEGEND

MED 1F-153 ROOM NAME
1F-153 ROOM NUMBER

NEW DOOR AND FRAME
REFERENCE DOOR SCHEDULE
EXIST DOOR AND FRAME

ACCESSORY NOTE
NOTE REFERENCE

DOOR MARK

DETAIL DRAWING REFERENCE
DRAWING IDENTIFICATION SHEET NUMBER
DETAIL LOCATION

SECTION DRAWING REFERENCE
DRAWING IDENTIFICATION SHEET NUMBER

INTERIOR ELEVATION MARK
DRAWING IDENTIFICATION SHEET NUMBER

ELEVATION MARK
DRAWING IDENTIFICATION SHEET NUMBER

FURNITURE ELEVATION MARK
DRAWING IDENTIFICATION SHEET NUMBER

KEY NOTE
NOTE REFERENCE

EQUIPMENT SYMBOL
NOTE REFERENCE

NEW MODULAR FURNITURE
MILLWORK

NORTH
SCALE: 1/8" = 1'-0"

DRAWING TITLE

1ST FLOOR
REFERENCE PLAN

PROJECT TITLE

JLM MEMORIAL VETERANS
HOSPITAL- EXPAND MICU

DATE

NOV 2013

PROJECT NUMBER

BUILDING NUMBER

1

CHECKED

JM

DRAWN

RS

DRAWING NO.

A2.1R

Dwg 4 of 10

LOCATION

CAVHS LITTLE ROCK, AR

APPROVED: MEDICAL CENTER DIRECTOR

APPROVED: CHIEF OF STAFF

APPROVED: WOMEN VET. PROG. COORD.

APPROVED: SERVICE CHIEF

APPROVED:

APPROVED: DEPUTY MEDICAL CENTER DIRECTOR

APPROVED: FACILITY PLANNER

APPROVED: SERVICE CHIEF

APPROVED: SERVICE CHIEF

APPROVED:

APPROVED: ASSOCIATE DIRECTOR

APPROVED: CHIEF ENGINEER

APPROVED: SERVICE CHIEF

APPROVED: SERVICE CHIEF

APPROVED: