

**SPECIFICATIONS
TABLE OF CONTENTS**

DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

01 01 15 LIST OF DRAWING SHEETS

DIVISION 01 – GENERAL REQUIREMENTS

01 01 00 GENERAL REQUIREMENTS

01 00 11 MEDICAL CENTER REQUIREMENTS

01 12 16 WORK SCHEDULE

01 33 23 SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES

01 33 24 ELECTRONIC SUBMITTAL PROCEDURES

01 58 16 TEMPORARY INTERIOR SIGNAGE

01 74 19 CONSTRUCTION WASTE MANAGEMENT

DIVISION 02 – EXISTING CONDITIONS

02 41 00 DEMOLITION

[02 82 13 19 ASBESTOS FLOOR TILE AND MASTIC ABATEMENT](#)

DIVISION 03 – CONCRETE

03 30 53 CASTE IN PLACE CONCRETE (SHORT FORM)

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

07 84 00 FIRESTOPPING

07 92 00 JOINT SEALANTS

07 21 13 THERMAL INSULATION

DIVISION 08 – OPENINGS

08 11 13 HOLLOW METAL DOORS AND FRAMES

08 14 00 INTERIOR WOOD DOORS

08 71 00 DOOR HARDWARE

DIVISION 09 – FINISHES

09 06 00 SCHEDULE OF FINISHES

09 29 00 GYPSUM BOARD

09 51 00 ACOUSTICAL CEILINGS

09 65 13 RESILIENT BASE AND ACCESSORIES

09 65 16 RESILIENT SHEET FLOORING

09 68 00 CARPETING

09 69 00 ACCESS FLOOR SYSTEM

09 91 00 PAINTING

DIVISION 10 - SPECIALTIES

10 26 00 WALL PROTECTION

DIVISION 12 - FURNISHINGS

12 32 01 WOOD OAK LABORATORY CASEWORK

DIVISION 21 – FIRE SUPPRESSION

21 05 11 COMMON WORK RESULTS FOR FIRE SUPPRESSION

21 13 13 WET-PIPE SPRINKLET SYSTEMS

DIVISION 22 – PLUMBING

22 05 11 COMMON WORK RESULTS FOR PLUMBING

22 05 23 GENERAL-DUTY VALVES FOR PLUMBING

22 07 11 PLUMBING INSULATION

22 11 00 FACILITY WATER DISTRIBUTION

22 13 00 FACILITY SANITARY AND VENT PIPING

22 40 00 PLUMBING FIXTURES

[22 63 00 GAS SYSTEMS FOR LABORATORY AND HEALTHCARE FACILITIES](#)

DIVISION 23 – HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

23 05 11 COMMON WORK RESULTS FOR HVAC

[23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC](#)

23 21 13 HYDRONIC PIPING

23 31 00 HVAC DUCTS AND CASINGS

23 37 00 AIR OUTLETS AND INLETS

23 82 00 CONVECTION HEATING AND COOLING UNITS

DIVISION 26 – ELECTRICAL

26 05 11 REQUIREMENTS FOR ELECTRICAL INSTALLATIONS

26 05 19 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

26 05 26 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

26 05 33 RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS

26 09 23 LIGHTING CONTROLS

26 24 16 PANELBOARDS

26 27 26 WIRING DEVICES

26 51 00 INTERIOR LIGHTING

DIVISION 27 – COMMUNICATIONS

27 05 11 REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS

27 05 26 GROUNDING AND BONDING FOR COMMUNICATIONS SYSTEMS

27 05 33	RACEWAYS AND BOXES FOR COMMUNICATIONS SYSTEMS
27 15 00	COMMUNICATIONS HORIZONTAL CABLING

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

28 13 00	PHYSICALL ACCESS CONTROL SYSTEM
28 31 00	FIRE DETECTION AND ALARM

---End Table of Contents---

SECTION 22 63 00
GAS SYSTEMS FOR LABORATORY AND HEALTHCARE FACILITIES

PART 1 - GENERAL

1.1 DESCRIPTION

- A. Central Laboratory and Healthcare Gas Systems: Consisting of oxygen, nitrous oxide, nitrogen, and compressed air services; complete, ready for operation, including all necessary piping, fittings, valves, cabinets, station outlets, rough-ins, ceiling services, gages, alarms including low voltage wiring, nitrogen control panels, cylinder manifolds, air compressors, electric motors and starters, air dryers, filters, pressure regulators, dew point, carbon monoxide monitors and all necessary parts, accessories, connections and equipment.
- B. Laboratory and healthcare gas system alarm wiring from equipment to alarm panels.

1.2 RELATED WORK

- A. Sealing around pipe penetrations to maintain the integrity of time rated construction: [Section 07 84 00, FIRESTOPPING.](#)
- B. Sealing around pipe penetrations through the floor to prevent moisture migration: [Section 07 92 00, JOINT SEALANTS.](#)
- C. General requirements and items common to more than one section of [Division 22. Section 22 05 11, COMMON WORK RESULTS FOR PLUMBING.](#)
- D. Conduit: [Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS.](#)
- E. Electrical wiring and accessories: [Section 26 27 26, WIRING DEVICES.](#)

1.3 QUALITY ASSURANCE

- A. Materials and Installation: In accordance with NFPA 99, (2012) and as specified.
- B. Equipment Installer: Show technical qualifications and previous experience in installing laboratory and healthcare equipment on three similar projects. Submit names and addresses of referenced projects. Installers shall meet the qualifications of ANSI/ASSE Standard 6010.
- C. Equipment Supplier: Show evidence of equivalent product installed at three installations similar to this project that has been in satisfactory and efficient operation for three years. Submit names and addresses where the product is installed.
- D. Laboratory and healthcare System Testing Organization: The testing shall be conducted by a party technically competent and experienced in the field of laboratory and healthcare pipeline testing. Testing and systems verification shall be performed by personnel meeting the qualifications of ANSI/ASSE Standard 6030. Such testing shall be performed by a party other than the installing contractor.
- E. Provide names of three projects where testing of medical or laboratory gases systems has been performed by the testing agency. Include the name of the project, names of such persons at that project who supervised the work for the project owner, or who accepted the report for the project owner, and a

written statement that the projects listed required work of similar scope to that set forth in this specification.

- F. Submit the testing agency's detailed procedure which will be followed in the testing of this project. Include details of the testing sequence, procedures for cross connection tests, outlet function tests, alarm tests, purity tests, etc., as required by this specification. For purity test procedures, include data on test methods, types of equipment to be used, calibration sources and method references.
- G. Certification: Provide documentation prior to submitting request for final inspection to include all test results, the names of individuals performing work for the testing agency on this project, detailed procedures followed for all tests, and a certification that all results of tests were within limits allowed by this specification.
- H. "Hot taps" are not permitted for operating medical oxygen systems. Methods for connection and extension of active and pressurized medical gas systems without subsequent medical gas testing and verification are not allowed.

1.4 SUBMITTALS

- A. Submit as one package in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
 - 1. Piping.
- C. Certification: The completed systems have been installed, tested, purged, analyzed and verified in accordance with the requirements of this specification.

1.6 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the test by the basic designation only.
- B. American Society for Testing and Materials (ASTM):
 - B819-(R2006)Seamless Copper Tube for Medical Gas Systems
- C. American Society of Mechanical Engineers (ASME):
 - A13.1-07Scheme for Identification of Piping Systems
 - B16.22-01(R2005)Wrought Copper and Bronze Solder-Joint Pressure Fittings
 - B40.100 (2005)Pressure Gauges and Gauge Attachments Boiler and Pressure Vessel Code -
Section VIII-07Pressure Vessels, Division I
Section IX-07Welding and Brazing Qualifications
- D. American Welding Society (AWS):
 - AWS A5.8-04Brazing Filler Metal

AWS B2.2-91.....Standard for Brazing Procedure and Performance Qualification
(Modified per NFPA 99)

E. Compressed Gas Association (CGA):

C-9-04Standard Color Marking of Compressed Gas Cylinders

G-4.1 (2009).....Cleaning Equipment for Oxygen Service

G-10.1(2008)Nitrogen, Commodity

P-9-01Inert Gases Argon, Nitrogen and Helium

V-1-05Standard for Compressed Gas Cylinder Valve Outlet and Inlet
Connections

F. National Electrical Manufacturers Association (NEMA):

ICS-6-93(R2006).....Industrial Controls and Systems Enclosures

G. National Fire Protection Association (NFPA):

99-05Health Care Facilities

H. United States Pharmacopoeia XXI/National Formulary XVI (USP/NF)

I. Manufacturing Standardization Society (MSS):

MSS-SP-72-99Ball Valves With Flanged or Butt Welding For General Purpose

MSS-SP-110-96Ball Valve Threaded, Socket Welding, Solder Joint, Grooved and Flared
Ends

MSS-SP-73-03Brazing Joints for Copper and Copper Alloy Solder Pressure Fittings

PART 2 - PRODUCTS

2.1 PIPING AND FITTINGS

- A. Copper Tubing: Type "K", ASTM B819, seamless copper tube, hard drawn temper, with wrought copper fittings conforming to ASME B16.22 or brazing fittings complying with MSS SP-73. Size designated reflecting nominal inside diameter. All tubing and fittings shall be labeled "ACR/OXY", "OXY", "OXY/MED", "ACR/MED", or "MED".
- B. Brazing Alloy: AWS A5.8, Classification BCuP, greater than 537 °C (1000 °F) melting temperature. Flux is strictly prohibited for copper-to-copper connections.
- C. Screw Joints: Polytetrafluoroethylene (teflon) tape.
- D. Underground Protective Pipe: Polyvinyl Chloride (PVC), ASTM D1785, Schedule 80.
- E. Memory metal couplings: Temperature and pressure rating shall not be less than that of a brazed joint.
- F. Apply piping identification labels at the time of installation in accordance with current NFPA. Apply supplementary color identification in accordance with CGA Pamphlet C-9.
- G. Special Fittings: The following special fittings shall be permitted to be used in lieu of brazed joints:
1. Memory-metal couplings having temperature and pressure ratings joints not less than that of a brazed joint.

2. Listed or approved metallic gas tube fittings that, when made up, provide a permanent joint having the mechanical, thermal, and sealing integrity of a brazed joint.
3. Dielectric fittings where required by the manufacturer of special medical equipment to electrically isolate the equipment from the piping distribution system.
4. Axially swaged, elastic strain preload fittings providing metal to metal seal having pressure and temperature ratings not less than that of a brazed joint and when complete are permanent and non-separable.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. In accordance with current NFPA.
- B. Install cast escutcheon with set screw at each wall, floor and ceiling penetration in exposed finished locations and within cabinets and millwork.
- C. Keep open ends of tube capped or plugged at all times or otherwise sealed until final assembly.
- D. Cut piping square and accurately with a tube cutter (sawing not permitted) to measurements determined at place of installation. Ream tube to remove burrs, being careful not to expand tube, and so no chips of copper remain in the tube. Work into place without springing or forcing. Bottom tube in socket so there are no gaps between tube and fitting. Exercise care in handling equipment and tools used in cutting or reaming of tube to prevent oil or grease being introduced into tubing. Where contamination has occurred, material is no longer suitable for oxygen service.
- E. Spacing of hangers: Current NFPA.
- F. Rigidly support valves and other equipment to prevent strain on tube or joints.
- G. While being brazed, joints shall be continuously purged with *oil* free nitrogen. The flow of purged gas shall be maintained until joint is cool to touch.
- H. Do not bend tubing. Use fittings.
- I. Support ceiling column assembly from heavy sub-mounting castings furnished with the unit as part of roughing-in. Anchor with 15 mm (1/2-inch) diameter bolts attached to angle iron frame supported from structural ceiling, unless otherwise indicated.
- J. Provide two 25 mm (1 inch) minimum conduits from ceiling column assembly to adjacent corridor, one for mass spectrometer tubing and wiring and one for monitor wiring, for connection to signal cabling network.
- K. Install pressure switches, transmitter and gauges to be easily accessed, and provide access panel where installed above plaster ceiling. Install pressure switch and sensors with orifice nipple between the pipe line and switches/sensors.
- L. Apply pipe labeling during installation process and not after installation is completed. Size of legend letters shall be in accordance with ANSI A13.1.

- M. Pipe compressor intake to a source of clean ambient air as indicated in current NFPA.
- N. After initial leakage testing is completed, allow piping to remain pressurized with testing gas until testing agency performs final tests.
- O. Penetrations:
 - 1. Fire Stopping: Where pipes pass through fire partitions, fire walls, smoked partitions, or floors, install a fire stop that provides an effective barrier against the spread of fire, smoke and gases as specified in Section 07 84 00, FIRESTOPPING, with intumescent materials only. Completely fill and seal clearances between raceways and openings with the fire stopping material.
 - 2. Waterproofing: At floor penetrations, completely seal clearances around the pipe and make watertight with sealant as specified in Section 07 92 00, JOINT SEALANTS.
- P. Provide 40mm (1 1/2 inch) diameter line pressure gage downstream of zone valve in cabinets.
- Q. Provide zone valves in cabinets where indicated and outside each Operating Room and a minimum one zone valve assembly for each 18 outlet set.

3.2 TESTS

- A. Initial Tests: Blow down, and high and low pressure leakage tests as required by current NFPA with documentation.

--- E N D ---