



3616 Masonic Drive, Alexandria, LA 71301  
318.445.3151 adg@adgllc.net

## **ADDENDUM 1**

March 10, 2014

**PROJECT: SITE SECURITY - PHASE I**

**OWNER: VETERAN AFFAIRS MEDICAL CENTER  
ALEXANDRIA, LA**

**ISSUED BY: Alliance Design Group**

This Addendum is issued for the purpose of modifying and /or clarifying the specifications and drawings and is to be construed as being as much a part of the original Contract Documents as though originally contained therein.

### **DRAWINGS**

#### **SHEET A101:**

1. Provide a note under new cameras that indicate that new exterior cameras that are pole mounted shall be mounted to the nearest existing light pole. No new poles are required.

#### **SHEET A103:**

1. To clarify, the door and sidelites being relocated on the second floor of building 1 is wide enough to span the full width of the corridor. No new wall will be required.

#### **SHEET A111:**

1. Provide a general door schedule note that states: "Existing holes in frames shall be covered with aluminum plates ,to match the frame finish, riveted to the existing frame. Screw hole can be plugged with plug rivets."
2. Revise general door schedule note 4 to read: "Install **wireless** door contact at the head of the frame at all doors listed in the door schedule. **Door contact wireless receiver shall be connected to the door access controller**"

### **GENERAL NOTES:**

- All wiring is to be routed within conduit per section 26 05 33. All conduit is to be concealed within floors, walls, ceilings per section 26 05 33. Where ceiling or wall surfaces are non-accessible, the surface shall be patched and finish to match existing. Where existing hardware is removed and a hole is not covered by new hardware, the hole shall be patched and finished to match existing.

**ALLIANCE DESIGN GROUP**  
3616 MASONIC DRIVE  
ALEXANDRIA, LOUISIANA 71301  
(318) 487-2037