



FINISH LEGEND				
FINISH NAME	MFR	MODEL	COLOR	REMARKS
PORCELAIN CERAMIC TILE				
C1	FLOOR GRES	GLOBE 1.0	GOLD MATTE	12x24x3/8 BEIGE TILE
C2	FLOOR GRES	GLOBE 1.0	GOLD BUSH-HAMMERED	4x24x3/8 BEIGE TILE
C3	FLOOR GRES	GLOBE 1.0	GOLD POLISHED	2x12x3/8 BEIGE TILE
MARBLE				
M1	N/A	HONED	EMPERADOR LIGHT	12x24x3/8 TAUPE TILE
M2	N/A	HONED	EMPERADOR LIGHT	SEE PLANX3/8 TAUPE TILE
M3	N/A	N/A	ROJO ALICANTE	7x24x3/8 TERRACOTTA TILE
M4	N/A	N/A	ROJO ALICANTE	4x12x3/8 TERRACOTTA TILE
M5	N/A	N/A	ROJO ALICANTE	2x12x3/8 TERRACOTTA TILE
M6	N/A	N/A	VERDE MARE	5x12x3/8 GREEN TILE
M7	N/A	POLISHED	EMPERADOR LIGHT	SEE PLANX3/8 TAUPE TILE
RESILIENT BASE				
RB-1	JOHNSONITE	1/8" COVED TOE	190 "GREEGE"	GREEN,VINYL 96" ROLLS MIN

GENERAL NEW WORK PLAN NOTES:

1. GRIND AND FLASH PATCH CONCRETE SUB-FLOOR TO PROVIDE A SMOOTH LEVEL SURFACE TO RECEIVE FLOOR FINISH.
2. BOND 3/8" THICK TILE WITH 1/8" FULL BED THIN SET BOND COAT FOR TOTAL FLOOR FINISH SYSTEM THICKNESS OF 1/2".
3. PROVIDE 1/4" WIDE PERIMETER JOINT WHERE TILE ABUTS EXISTING SURFACES EQ TO TCA E-711-11 WITH BOND BREAKER TAPE AND UTHANE SEALANT. COLOR TO MATCH GROUT.

KEYED NEW WORK PLAN NOTES:

- ① PROVIDE 1/4" WIDE CONTROL JOINT KEY TO ICA EU 717F-11 WITH BOND BREAKER TAPE AND UTHANE SEALANT COLOR TO MATCH GROUT.
- ② TERMINATE TILE AT CENTERLINE OF DOOR IN CLOSED POSITION AND PROVIDE SCHLUTER RENO-U EU 125 STAINLESS STEEL TRANSITION STRIP. BUTT TRANSITION STRIP TO EXISTING RESILIENT TILE. PROVIDE STRAIGHT, FLUSH SQUARE EDGE AT RESILIENT TILE TO BUTT TRANSITION STRIP.
- ③ TERMINATE TILE AT EDGE OF ELEVATOR DOOR THRESHOLD WITH SCHLUTER RENO-U EU 125 STAINLESS STEEL TRANSITION STRIP. BUTT TRANSITION STRIP TO EDGE OF EXISTING METAL THRESHOLD.
- ④ TEMPORARILY REMOVE METAL EXPANSION JOINT COVER. TERMINATE TILE AT EDGE OF CONCRETE SLAB AT EXPANSION JOINT AND RESTORE EXPANSION JOINT COVER.
- ⑤ ORIGIN POINT OF FIELD TILES. ALIGN FIELD COURSE JOINT WITH STAR TIPS.
- ⑥ PROVIDE RESILIENT BASE RB-1 AT WALL SURFACES WITHOUT EXISTING MARBLE BASE, EXTENT SHOWN BY DASHED HALFTONE LINE.

FINAL CONSTRUCTION DOCUMENTS
BUILDING ONE IS FULLY SPRINKLERED

		CONSULTANTS:				ARCHITECT/ENGINEERS:		Drawing Title PORCELAIN CERAMIC TILE FLOOR PATTERN		Project Title Replace Main Lobby Finishes Building One First Floor		Project Number 650-12-008		Office of Construction and Facilities Management	
						Providence VAMC FMS Engineering 623 Atwells Avenue Eagle Square Unccass Building Providence, RI 02909-2472 (Tel) 401-459-4760x6419 (Fax) 401-421-0594 e-mail: Lois.Brady@VA.gov		Approved Project Director		Location Providence VAMC		Drawing Number A-1 Dwg. 1 of 1			
Revisions:		Date						Date September 5, 2013		Checked RHP		Drawn RHP			