

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	MANUFACTURER & MODEL#	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
					OWNER			CONTR	OWNER	CONTR	WATTS		VOLTAGE	CW	HW	DRAIN		
Surgery Support & Public Spaces (A & D Wings)																		
B8062	Family Waiting & Nourishment																	
B8060	112	N	1	Refrigerator - Undercounter	Follett		24w x 25.5d x 31.5h	X		X		UCT		115V				ADA
	127	N	1	Coffee Maker	Bunn or similar			X		X		CT			X		X	
		N	7	Cafe Chair				X		X		F						
		N	3	Table - Café				X		X		F						
		N	4	Settee				X		X		F						
		N	9	Lounge Chair				X		X		F						
		N	1	Table				X		X		F						
		N	2	Side Chair				X		X		F						
B8058	Greeter																	
			1	Computer Workstation				X		X		D						
			1	Task Chair				X		X		F						
A8001	Imaging Alcove																	
			1	Computer Workstation				X		X		D						Owner to confirm equipment specifications
			1	Digitizer				X		X		D						Owner to confirm equipment specifications
			1	Portable X-Ray				X		X		F						Owner to confirm equipment specifications
			1	Computer Workstation				X		X		D						
			1	Task Chair				X		X		F						
A8002	Consult																	
		N	1	Computer				X		X		W						
		N	2	Lounge Chair				X		X		F						
		N	1	Settee				X		X		F						
		N	1	Table				X		X		F						
		N	6	Side Chair				X		X		F						
A8003	ICU Equipment Storage																	
		R	1	Stretcher				X		X		F						currently in SICU corridor
		R	1	Stretcher				X		X		F						currently in SICU corridor
		R	1	Oxygen Tank Cart - Full Tanks			18w x 27d x 40h	X		X		F						
		R	1	EZ Way Patient standing lift				X		X		F						currently in SICU corridor
		R	1	Wheelchair				X		X		F						currently in SICU corridor
		R	1	Wheelchair				X		X		F						currently in SICU corridor

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	MANUFACTURER & MODEL#	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
								OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
A8011	Conference																	
		N	1	LCD Monitor - 50"				X		X		W						
		N	2	Workstation, Computer				X		X		D						
		N	2	Task Chair				X		X		F						
		N	14	Stacking Chair				X		X		F						
		N	12	Conference Chair				X		X		F						
		N	4	Conference Table				X		X		F						
		N	1	Smartboard	SMART			X		X		W						
		N	1	Projector, Multimedia/Data				X		X		C						
		N	1	Projection Screen				X		X		C						
		N	1	Video Teleconferencing System				X		X							Video conferencing unit consisting of a camera, microphone, video/audio compression components and a component cart.	
A8015	Housekeeping																	
		N	1	Janitor Cart				X		X		F						
		N	1	Mop Bucket				X		X		F						
		N	1	Shelf w/ mop holders	Bobrick		36" L		X		X	W						
		N	1	Chemical Dispenser (wall mtd)				X		X		W						
	121	N	1	Shelving Unit	Metro		48w x 24d x 72h	X		X		F						
A8017	OR Vendor Office																	
		N	2	Computer Workstation				X		X		D						
		N	2	Task Chair				X		X								
		N	2	Folding Guest Chair				X		X								wall hung w/ hook
		N	2	Wall Hook					X		X	W						
	121	N	3	Shelving Unit	Metro		48w x 18d x 72h	X		X		F						
A8019	Staff Toilets - Men's																	
		N	2	Soiled Linen Hamper				X		X		F						
A8021	Vestibule																	
		N	1	Personal Protection Supply Cart				X		X		F						Owner to confirm equipment specifications
	161	N	2	Scrub Valet - Dispenser				X		X		F						Owner to confirm equipment specifications
A8027	Staff Lockers - Men's																	
	162	N	1	Scrub Valet - Return				X		X		F						Owner to confirm equipment specifications

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL) MANUFACTURER & MODEL#	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
							OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
A8026	Vestibule																
		N	1	Personal Protection Supply Cart			X		X		F					Owner to confirm equipment specifications	
	161	N	2	Scrub Valet - Dispenser			X		X		F					Owner to confirm equipment specifications	
A8030	Staff Lockers - Women's																
	162	N	1	Scrub Valet - Return			X		X		F					Owner to confirm equipment specifications	
A8036	Staff Toilets - Women's																
		N	2	Soiled Linen Hamper			X		X		F						
A8029	Sterile Supply/Cart Assembly																
			6	Case Cart		42w x 29d x ?h	X		X		F						
	120	N	13	Shelving Unit (solid shelves)	Metro	48w x 24d x 72h	X		X		F						
	120	N	6	Shelving Unit (solid shelves)	Metro	48w x 18d x 72h	X		X		F						
	107	N	10	Top Track Shelving Units	Metro	48w x 24d x 72h	X		X		F					solid shelves	
			2	Task Chair - High			X		X		F						
			2	Task Chair - High			X		X		F						
			1	Pedestal File			X		X		F						
			1	Printer			X		X		D						
	164		1	PPE cabinet - SSTL			X		X		F						Owner to confirm equipment specifications
118	N	1	Pass Thru Window Assembly	Steris	36w x 36h x 5d	X			X	W							
A8042	Anesthesia Training																
		N	10	Stackable Chair			X		X		F						
		N	1	Task Chair - High			X		X		F						
		R	2	Stretcher			X		X		F						
		R	2	Mannequin			X		X		F						
A8046	OR Equipment Storage																
	120	N	3	Shelving Unit (solid shelves)	Metro	48w x 24d x 72h	X		X		F						
A8052	Anesthesia Storage																
	121	N	4	Shelving Unit	Metro	48w x 24d x 72h	X		X		F						
A8041	Housekeeping																
		N	1	Janitor Cart			X		X		F						
		N	1	Mop Bucket			X		X		F						
		N	1	Shelf w/ mop holders	Bobrick	36" L		X		X	W						
		N	1	Chemical Dispenser (wall mtd)			X		X		W						
	121	N	1	Shelving Unit	Metro	48w x 24d x 72h	X		X		F						

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL) MANUFACTURER & MODEL#	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
							OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
ED8209	Cart Washer																
	101	N	1	Cart Washer-Disinfector	Steelco LC20	see cut sheets	X			X	F		480 V				CS750S Steam or Equal. Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B **Project No.** 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
					OWNER		CONTR	OWNER	CONTR	WATTS		VOLTAGE	CW	HW	DRAIN		
Intensive Care Unit 1 (B Wing West)																	
B8032	ICU Patient Room																
B8034			1	Patient Bed			X		X		F						Owner to confirm equipment specifications
B8038		N	1	Prefabricated Headwall Unit	Compass or equal			X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
B8044		N	1	Prefabricated Footwall Unit	Compass or equal			X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
			1	Physiological Monitor	Philips		X		X		W						mtd on headwall w/ arm
			1	Sphygmomanometer			X		X		W						mtd on headwall
			1	Thermometer			X		X		W						mtd on headwall
			1	Pulse Oximeter			X		X		W						mtd on headwall
		N	1	Sharps			X		X		W						
		N	1	Glove Dispenser			X		X		W						
		N	1	System Clock			X		X		W						mtd on footwall. Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
		N	1	Soiled Linen Hamper			X		X		F						
		N	1	Television - 42"			X		X		W						
		N	1	Wall Bracket for TV			X		X		W						
		N	1	Markerboard			X		X		W						Marker Board is also noted as Patient Information on drawings. Corian shelf below board is Contractor Furnished and Installed
		N	1	Flashlight - Rechargeable			X		X		W						
		N	1	Overbed Table			X		X		F						
		N	1	Patient Recliner			X		X		F						
		N	1	Sleeper Settee or Recliner (family)			X		X		F						
		N	1	Guest Chair (folding)			X		X		W						mtd on wall bracket
	N	1	Wall Bracket for guest chair			X		X		W							
	N	1	Task Chair - High (no casters)			X		X		F							
	N	1	Charting Computer			X		X									
	N	1	Mobile computer cart			X		X		F						for charting computer	
119		R	1	Patient Lift	Arjo Maxi Sky 600		X		X		C						Owner to confirm equipment specifications. Owner installation includes tracks and associated structural supports.

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
					OWNER		CONTR	OWNER	CONTR	WATTS		VOLTAGE	CW	HW	DRAIN		
																MANUFACTURER & MODEL#	
B8040	ICU Bariatric Patient Room																
			1	Patient Bed			X		X		F						Owner to confirm equipment specifications
		N	1	Prefabricated Headwall Unit	Compass or equal			X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
		N	1	Prefabricated Footwall Unit	Compass or equal			X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
			1	Physiological Monitor	Philips		X		X		W						mtd on headwall w/ arm
			1	Sphygmomanometer			X		X		W						mtd on headwall
			1	Thermometer			X		X		W						mtd on headwall
			1	Pulse Oximeter			X		X		W						mtd on headwall
		N	1	Sharps			X		X		W						
		N	1	Glove Dispenser			X		X		W						
		N	1	System Clock			X		X		W						mtd on footwall. Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
		N	1	Soiled Linen Hamper			X		X		F						
		N	1	Television - 42"			X		X		W						
		N	1	Wall Bracket for TV			X		X		W						
		N	1	Markerboard			X		X		W						Marker Board is also noted as Patient Information on drawings. Corian shelf below board is Contractor Furnished and Installed
		N	1	Flashlight - Rechargeable			X		X		W						
		N	1	Overbed Table			X		X		F						
		N	1	Patient Recliner			X		X		F						
		N	1	Sleeper Settee or Recliner (family)			X		X		F						
		N	1	Guest Chair (folding)			X		X		W						mtd on wall bracket
		N	1	Wall Bracket for guest chair			X		X		W						
		N	1	Task Chair - High (no casters)			X		X		F						
		N	1	Charting Computer			X		X								
		N	1	Mobile computer cart			X		X		F						for charting computer
119		N	1	Patient Lift	Arjo Maxi Sky 1000		X		X		C						Owner to confirm equipment specifications. Owner installation includes tracks and associated structural supports.

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B **Project No.** 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
					OWNER		CONTR	OWNER	CONTR	WATTS		VOLTAGE	CW	HW	DRAIN		
																MANUFACTURER & MODEL#	
B8026	ICU Patient Room - Negative Isolation																
B8028			1	Patient Bed			X		X		F						Owner to confirm equipment specifications
B8046		N	1	Prefabricated Headwall Unit	Compass or equal			X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
		N	1	Prefabricated Footwall Unit	Compass or equal			X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
			1	Physiological Monitor	Philips		X		X		W						mtd on headwall w/ arm
			1	Sphygmomanometer			X		X		W						mtd on headwall
			1	Thermometer			X		X		W						mtd on headwall
			1	Pulse Oximeter			X		X		W						mtd on headwall
		N	1	Sharps			X		X		W						
		N	1	Glove Dispenser			X		X		W						
		N	1	System Clock			X		X		W						mtd on footwall. Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
		N	1	Soiled Linen Hamper			X		X		F						
		N	1	Television - 42"			X		X		W						
		N	1	Wall Bracket for TV			X		X		W						
		N	1	Markerboard			X		X		W						Marker Board is also noted as Patient Information on drawings. Corian shelf below board is Contractor Furnished and Installed
		N	1	Flashlight - Rechargeable			X		X		W						
		N	1	Overbed Table			X		X		F						
		N	1	Patient Recliner			X		X		F						
		N	1	Sleeper Settee or Recliner (family)			X		X		F						
		N	1	Guest Chair (folding)			X		X		W						mtd on wall bracket
		N	1	Wall Bracket for guest chair			X		X		W						
		N	1	Task Chair - High (no casters)			X		X		F						
	N	1	Charting Computer			X		X									
	N	1	Mobile computer cart			X		X		F						for charting computer	
119		N	1	Patient Lift	Arjo Maxi Sky 1000		X		X		C						Owner to confirm equipment specifications. Owner installation includes tracks and associated structural supports.

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	MANUFACTURER & MODEL#	SIZE (W x D x H)	SUPPLIED		INSTALLED		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
								OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
B8030	Charting - Decentralized																	
B8042		N	2	Computer Workstation				X		X		D						
B8048		N	2	Task Chair - High (w/ casters)				X		X		F						
B8036	Charting - Decentralized																	
		N	1	Computer Workstation				X		X		D						
		N	1	Task Chair - High (w/ casters)				X		X		F						
B8037	Family Room																	
		N		Lounge Chair				X		X		F						
		N		Settee				X		X		F						
B8033	Soiled Utility																	
		R	1	Trash Can - 44 gallon				X		X		F						
		N	1	Sharps (wall)				X		X		W						
		N	1	Gloves				X		X		W						
		R	2	Soiled Linen Hamper				X		X		F						
		R	2	Red bag waste can				X		X		F						
		R	2	Sharps containers				X		X		F						
B8041	Nourishment																	
	125	N	1	Refrigerator/Freezer			24w x 24d x 33h	X		X		F						
	126	R	1	Microwave			21w x 24d x 12h	X		X		CT						
	114	N	1	Ice Maker		Follett	21w x 24d x 47h	X		X		CT		115V				Air cooled
	116	N	1	Water Filter		Follett	16w x 4d x 20h	X		X		W						
	127	N	1	Coffee Maker		Bunn or similar		X		X		CT						

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	MANUFACTURER & MODEL#	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
								OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
B8043	Nurse Station																	
	132	R	1	Crash Cart w/ Defib (beige)			28w x 22d x 38h	X		X		F						currently in CCU corridor
	131	R	1	ECG			18w x 40h x 28d	X		X		F						currently in CCU corridor
	133	R	1	Anesthesia Cart			24w x 24d x 44h	X		X		F						currently in CCU corridor
		R	1	Patient Information Board			36w x 30h	X		X		W						
		R	1	Central Monitor Station				X		X		D						
		R	1	Central Monitor printer			6w x 9d x 5h	X		X		D						
		R	1	Patient Order Monitor			10w x 11h x 5d	X		X		D						
		R	1	Intellivue Printer			12w x 12d x 12h	X		X		D						
		R	1	HP Laser Jet Printer			16w x 17d x 16h	X		X		D						
		R	2	Lateral File			20d x 36w	X		X		F						
		N	1	Clock				X		X		W						Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
		R	2	Paper Recycling Bin				X		X		F						
		N	1	OR Code Blue				X		X		W						
		R	14	Computer Workstation				X		X		UCT						
		N	14	Task Chair				X		X		F						
		N	10	Pedestal Files				X		X		F						
		R	1	Patient Order Monitor			10w x 11h x 5d	X		X		D						
		R	2	Monitor - Unit Clerk				X		X		D						
		R	1	Scanner - small			24w x 12d x 12h	X		X		D						
		135	R	1	Copier			41w x 26d x 46h	X		X		F					
				Systems Furniture				X		X		F					see plan	
B8053	Alcove - Med Prep																	
	152	R	1	Medication Dispenser		Med Select	19w x 20d x 38h	X		X		F						
	152	R	1	Medication Dispenser w/ Monitor		Med Select	19W x 28D x 70H	X		X		F						Monitor on left
B8055	Med Prep																	
	121	R	1	Shelving Unit		Metro	48w x 24d x 72h	X		X		F						
	111	N	1	Refrigerator		Follett	24w x 26d x 35h	X		X		UCT						
		N	1	Hook Strip			36w	X		X		W						
		N	2	Sharps				X		X		W						
		N	1	Gloves				X		X		W						
		R	2	Recycling Bin				X		X		F						
		R	1	Computer Workstation				X		X		CT						

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES	
					OWNER		CONTR	OWNER	CONTR	WATTS		VOLTAG	CW	HW	DRAIN			
B8057	Clean Utility																	
	123	R	1	Shelving Unit	Metro	60w x 24d x 72h	X		X		F							
	121	R	4	Shelving Unit	Metro	48w x 24d x 72h	X		X		F							
	151	R	2	Small supply cart		38w x 22d x 36h	X		X		F							
		R	1	Hazardous Waste			X		X		F							
B8059	Equipment Room																	
	124	R	1	Blanket Warmer		30w x 27d x 36h	X		X		F							
	142	R	1	Cortrak Monitor		18w x 18d x 60h	X		X		F						currently in CCU corridor	
	143	R	1	Wireless Monitor		18w x 18d x 60h	X		X		F						currently in CCU corridor	
	144	R	2	Bladderscan		21w x 21d x 36h	X		X		F							
	145	R	1	Bronch Tower		24w x 26d x 72h	X		X		F						currently in CCU corridor	
	146	R	1	Ultrasound		21w x 24 d x 60h	X		X		F						currently in CCU corridor	
	149	R	1	Maxi Move Patient Lift	Arjo		X		X		F							
	123	N	1	Shelving Unit	Metro	60w x 18d x 72h	X		X		F							
	130	R	1	I-Med Consent COW		26w x 30d x 54h	X		X		F						currently in CCU corridor	
	150	R	1	Crash Cart (red)		34w x 26d x 48h	X		X		F							
		R	1	IV Pole w/ Pumps			X		X		F							
		N	1	Hooks for transfer boards			X		X		W							
	B8061	Clean Linen																
123		N	1	Shelving Unit	Metro	60w x 24d x 72h	X		X		F							
121		N	1	Shelving Unit	Metro	48w x 24d x 72h	X		X		F							
147		R	1	Comfort Cleanse Warmer (white)		28w x 14d x 18h	X		X		CT							
148		R	1	Comfort Cleanse Warmer (black)		28w x 15d x 20h	X		X		CT							
B8054	Respiratory Therapy Storage																	
	141	R	1	RT Supply Shelving Unit		36w x 24d x 72h	X		X		F							
	123	R	1	Shelving Unit	Metro	60w x 24d x 72h	X		X		F						currently in CCU	
		R	1	Oxygen Tank Cart - Full Tanks		18w x 27d x 40h	X		X		F						currently in CCU	
		R	1	Oxygen Tank Cart - Empty Tanks		12w x 18d x 36h	X		X		F						currently in SICU	
	137	R	1	Ventilator		24w x 31d x 53h	X		X		F						currently in SICU	
	137	R	1	Ventilator		24w x 31d x 53h	X		X		F						currently in SICU	
	138	R	1	PICC Cart		32w x 28d x 38h	X		X		F						currently in SICU	
	139	R	1	Neuro Cart		32w x 22d x 37h	X		X		F							
	140	R	1	Hemodynamic Cart		32w x 22d x 37h	X		X		F							
	136	R	2	Ventilator		23w x 26d x 68h	X		X		F							
		R	1	Oxygen Tank Cart - Empty Tanks		12w x 18d x 36h	X		X		F							
		R	1	Non-invasive Vent CPAP														

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING	D = DESKTOP	ST = STORAGE
CAB = CABINET	F = FLOOR	UCT = UNDER COUNTER
CT = COUNTERTOP	P = PORTABLE	W = WALL

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
					OWNER		CONTR	OWNER	CONTR	WATTS		VOLTAG	CW	HW	DRAIN		
B8056	ICU Equipment Storage																
	R	1	Portable Scale			24w x 60h x 30d	X		X		F						
	R	2	Stretcher				X		X		F						
	R	1	Stretcher		Stryker Zoom	87w x 32d	X		X		F						
	R	1	Stretchair			29w x 48d	X		X		F						
	R	1	Stretchair			29w x 48d	X		X		F						
	R	1	Dr Peaslee Monitor			28w x 28d x 60h	X		X		F						

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING	D = DESKTOP	ST = STORAGE
CAB = CABINET	F = FLOOR	UCT = UNDER COUNTER
CT = COUNTERTOP	P = PORTABLE	W = WALL

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	MANUFACTURER & MODEL #	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
								OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
Intensive Care Unit 2 (B Wing East)																		
B8002	ICU Protective Environment Room																	
B8004			1	Patient Bed				X		X		F						Owner to confirm equipment specifications
		N	1	Prefabricated Headwall Unit	Compass or equal				X		X	W						see intr elevs. Contr to provide utility rough-ins and final hook-up for install of equipment
			N	1	Prefabricated Footwall Unit	Compass or equal				X	X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
			1	Physiological Monitor	Philips			X		X		W						
			1	Sphygmomanometer				X		X		W						
			1	Thermometer				X		X		W						
			1	Pulse Oximeter				X		X		W						currently in SICU corridor
		N	1	Sharps				X		X		W						
		N	1	Glove Dispenser				X		X		W						
			N	1	System Clock				X		X		W					mounted on footwall. Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
			N	1	Soiled Linen Hamper				X		X		F					
			N	1	Television - 42"				X		X		W					
			N	1	Wall Bracket for TV				X		X		W					
			N	1	Markerboard				X		X		W					Marker Board is also noted as Patient Information on drawings. Corian shelf below board is Contractor Furnished and Installed
			N	1	Flashlight - Rechargeable				X		X		W					
			N	1	Overbed Table				X		X		F					
			N	1	Patient Recliner				X		X		F					
			N	1	Sleeper Settee or Recliner (family)				X		X		F					see plan
			N	1	Guest Chair (folding)				X		X		W					
			N	1	Wall Bracket for guest chair				X		X		W					
		N	1	Task Chair - High (no casters)				X		X		F						
		N	1	Charting Computer				X		X		Boom						

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B **Project No.** 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
					OWNER		CONTR	OWNER	CONTR	WATTS		VOLTAGE	CW	HW	DRAIN		
B8008	ICU Bariatric Protective Environment Patient Room																
			1	Patient Bed			X		X		F						Owner to confirm equipment specifications
		N	1	Prefabricated Headwall Unit	Compass or equal			X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
		N	1	Prefabricated Footwall Unit	Compass or equal			X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
			1	Physiological Monitor	Philips		X		X		W						mtd on headwall w/ arm
			1	Sphygmomanometer			X		X		W						mtd on headwall
			1	Thermometer			X		X		W						mtd on headwall
			1	Pulse Oximeter			X		X		W						mtd on headwall
		N	1	Sharps			X		X		W						
		N	1	Glove Dispenser			X		X		W						
		N	1	System Clock			X		X		W						mounted on footwall. Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
		N	1	Soiled Linen Hamper			X		X		F						
		N	1	Television - 42"			X		X		W						
		N	1	Wall Bracket for TV			X		X		W						
		N	1	Markerboard			X		X		W						Marker Board is also noted as Patient Information on drawings. Corian shelf below board is Contractor Furnished and Installed
		N	1	Flashlight - Rechargeable			X		X		W						
		N	1	Overbed Table			X		X		F						
		N	1	Patient Recliner			X		X		F						
		N	1	Sleeper Settee or Recliner (family)			X		X		F						
		N	1	Guest Chair (folding)			X		X		W						mtd on wall bracket
		N	1	Wall Bracket for guest chair			X		X		W						
		N	1	Task Chair - High (no casters)			X		X		F						
		N	1	Charting Computer			X		X								
		N	1	Mobile computer cart			X		X		F						for charting computer
119		N	1	Patient Lift	Arjo Maxi Sky 1000		X		X		C						Owner to confirm equipment specifications. Owner installation includes tracks and associated structural supports.

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B **Project No.** 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	MANUFACTURER & MODEL #	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
								OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
B8010	ICU Patient Room - Protective Environment																	
B8014			1	Patient Bed				X		X		F						Owner to confirm equipment specifications
B8016		N	1	Prefabricated Headwall Unit	Compass or equal				X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
B8020		N	1	Prefabricated Footwall Unit	Compass or equal				X		X	W						see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
			1	Physiological Monitor	Philips			X		X		W						
			1	Sphygmomanometer				X		X		W						
			1	Thermometer				X		X		W						
			1	Pulse Oximeter				X		X		W						currently in SICU corridor
		N	1	Sharps				X		X		W						
		N	1	Glove Dispenser				X		X		W						
		N	1	System Clock				X		X		W						mounted on footwall. Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
		N	1	Soiled Linen Hamper				X		X		F						
		N	1	Television - 42"				X		X		W						
		N	1	Wall Bracket for TV				X		X		W						
		N	1	Markerboard				X		X		W						Marker Board is also noted as Patient Information on drawings. Corian shelf below board is Contractor Furnished and Installed
		N	1	Flashlight - Rechargeable				X		X		W						
		N	1	Overbed Table				X		X		F						
		N	1	Patient Recliner				X		X		F						
		N	1	Sleeper Settee or Recliner (family)				X		X		F						see plan
	N	1	Guest Chair (folding)				X		X		W							
	N	1	Wall Bracket for guest chair				X		X		W							
	N	1	Task Chair - High (no casters)				X		X		F							
	N	1	Charting Computer				X		X									
	N	1	Mobile computer cart				X		X		F							
119		R	1	Patient Lift		Arjo Maxi Sky 600		X		X		C						Owner to confirm equipment specifications. Owner installation includes tracks and associated structural supports.

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B **Project No.** 211033.00

MOUNTING KEY:

C = CEILING	D = DESKTOP	ST = STORAGE
CAB = CABINET	F = FLOOR	UCT = UNDER COUNTER
CT = COUNTERTOP	P = PORTABLE	W = WALL

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	MANUFACTURER & MODEL #	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
								OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
B8022	ICU Patient Room																	
			1	Patient Bed				X		X								Owner to confirm equipment specifications
		N	1	Prefabricated Headwall Unit	Compass or equal				X		X							see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
		N	1	Prefabricated Footwall Unit	Compass or equal				X		X							see interior elevations. Contractor to provide utility rough-ins and final hook-up for installation of equipment
			1	Physiological Monitor	Philips			X		X		W						mtd on headwall w/ arm
			1	Sphygmomanometer				X		X		W						mtd on headwall
			1	Thermometer				X		X		W						mtd on headwall
			1	Pulse Oximeter				X		X		W						mtd on headwall
		N	1	Sharps				X		X		W						
		N	1	Glove Dispenser				X		X		W						
		N	1	System Clock				X		X		W						mounted on footwall. Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
		N	1	Soiled Linen Hamper				X		X								
		N	1	Television - 42"				X		X		W						
		N	1	Wall Bracket for TV				X		X		W						
		N	1	Markerboard				X		X		W						Marker Board is also noted as Patient Information on drawings. Corian shelf below board is Contractor Furnished and Installed
		N	1	Flashlight - Rechargeable				X		X								
		N	1	Overbed Table				X		X								
		N	1	Patient Recliner						X								
		N	1	Sleeper Settee or Recliner (family)						X								
		N	1	Guest Chair (folding)				X		X								mtd on wall bracket
		N	1	Wall Bracket for guest chair				X		X		W						
		N	1	Charting Computer				X		X								
		N	1	Mobile computer cart				X		X								for charting computer
119		N	1	Patient Lift		Arjo Maxi Sky 1000		X		X		C						Owner to confirm equipment specifications. Owner installation includes tracks and associated structural supports.

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING	D = DESKTOP	ST = STORAGE
CAB = CABINET	F = FLOOR	UCT = UNDER COUNTER
CT = COUNTERTOP	P = PORTABLE	W = WALL

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL) MANUFACTURER & MODEL #	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
							OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN	
B8006	Charting - Decentralized																
B8012		N	2	Computer Workstation			X		X		D						
B8018		N	2	Task Chair - High			X		X		F						see plan
B8024																	
B8001	Staff Lounge																
	125	N	2	Refrigerator		full size, 19-21 CF	X		X		F						
	126	N	2	Microwave			X		X		CT						
	127	N	1	Coffee Maker	Bunn or similar		X		X		CT			X		X	
	134	N	1	Toaster Oven			X		X		CT						
		N		Table			X		X		F						
		N		Stacking Chair			X		X		F						
		N	80	Mailslots				X		X		F					See interior elevations
		N	20	Box Lockers					X		X	F					See interior elevations
		N	1	Computer Workstation				X		X		D					
		N	1	Pedestal File				X		X		F					
B8005	Family Room																
				Lounge Chair			X		X		F						
				Settee			X		X		F						
B8009	Nourishment																
	125	N	1	Refrigerator			X		X		F						
	126	N	1	Microwave		21w x 24d x 12h	X		X		CT						
	114	N	1	Ice Maker	Follett	21w x 24d x 47h	X		X		CT		115				Air cooled
	116	N	1	Water Filter	Follett	16w x 4d x 20h	X		X		W						
	127	N	1	Coffee Maker	Bunn or similar		X		X		CT			X		X	

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING	D = DESKTOP	ST = STORAGE
CAB = CABINET	F = FLOOR	UCT = UNDER COUNTER
CT = COUNTERTOP	P = PORTABLE	W = WALL

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL)	MANUFACTURER & MODEL #	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES
					OWNER			CONTR	OWNER	CONTR	WATTS		VOLTAGE	CW	HW	DRAIN		
B8013	Nurse Station																	
	132	R	1	Crash Cart w/ Defib (beige)			28w x 22d x 38h	X		X		F						one power connection or 2?
	133	R	1	Anesthesia Cart			24w x 24d x 44h	X		X		F						
	131	N	1	ECG			18w x 40h x 28d	X		X		F						
		R	1	Supply Cart			24w x 22d x 37h	X		X		F						
		R	1	Printer				X		X		D						
		R	1	Central Monitor Station				X		X		D						
		R	1	Central Monitor printer			6w x 9d x 5h	X		X		D						
		N	1	Patient Information Board (Markerboard)				X		X		W						
		N	1	OR Code Blue				X		X		W						
		R	15	Computer Workstations				X		X		D						
		N	16	Task Chair				X		X		F						
		N	6	Pedestal File				X		X		F						
		N	1	Lateral File				X		X		F						
		R	1	Patient Order Monitor			10w x 11h x 5d	X		X		D						
		N	1	Clock				X		X		W						Contractor to provide utility rough-ins and final hook-up for Owner installation of equipment.
		R	1	Scanner - small			24w x 12d x 12h	X		X		D						
		R	2	Monitors - Unit Clerk				X		X		D						
		135	R	1	Copier			41w x 26d x 46h	X		X		F					
					Systems Furniture				X		X		F					
B8019	Alcove - Med Prep																	
	152	R	1	Medication Dispenser	Med Select		19w x 20d x 38h	X		X		F						
	152	R	1	Medication Dispenser w/ Monitor	Med Select		19w X 28d X 70h	X		X		F						Monitor on right
B8021	Med Prep																	
	121	R	1	Shelving Unit	Metro		48w x 24d x 72h	X		X		F						
		R	1	Label Holder			16w x 4d x 35h	X		X		W						
	111	N	1	Refrigerator	Follett		24w x 26d x 34h	X		X		CT						
		N	1	Hook Strip			36w	X		X		W						
		R	2	Recycling Bin				X		X		F						
		N	2	Sharps				X		X		W						
		N	1	Glove Dispenser				X		X		W						
		R	1	Computer Workstation				X		X		CT						

MEDICAL EQUIPMENT INVENTORY & SPECIFICATION

Project: William S. Middleton Memorial Veterans Hospital - Consolidate ICUs - 8A/8B Project No. 211033.00

MOUNTING KEY:

C = CEILING **D = DESKTOP** **ST = STORAGE**
CAB = CABINET **F = FLOOR** **UCT = UNDER COUNTER**
CT = COUNTERTOP **P = PORTABLE** **W = WALL**

*Note: When multiple room numbers are provided, the equipment listed applies to each room.

NEW ROOM NO(S)*	ITEM NO.	NEW/REUSE	QUANTITY	EQUIPMENT NAME	DESIGN BASIS: (OR EQUAL) MANUFACTURER & MODEL #	SIZE (W x D x H)	SUPPLIED BY		INSTALLED BY		MOUNTING	ELECTRIC REQ'MTS		PLUMBING REQ'MTS			NOTES		
							OWNER	CONTR	OWNER	CONTR		WATTS	VOLTAGE	CW	HW	DRAIN			
B8023	Clean Utility																		
	123	R	1	Shelving Unit	Metro	60w x 24d x 72h	X			X		F							
	121	R	4	Shelving Unit	Metro	48w x 24d x 72h	X			X		F							
	151	R	1	Small supply cart (gray)		38w x 22d x 36h	X			X		F							
		N	1	Markerboard/Tackboard			X			X		W							
B8025	Equipment Room																		
	129	R	1	Warming Cabinet		28w x 25d x 72h	X			X		F							
	130	R	1	I-Med Consent COW		26w x 30d x 54h	X			X		F							
	153	R	2	Isolation Supply Cart		28w x 20d x 64h	X			X		F							
	154	R	1	Ultrasound		24w x 24 d x 60h	X			X		F							
	155	R	1	Bair Hugger		14w x 16d x 24h	X			X		F							
	156	R	1	Cortrak Monitor		18w x 18d x 60h	X			X		F							
	157	R	1	Bladderscan		21w x 21d x 36h	X			X		F							
	158	R	1	Scale		26w x 28d x 50h	X			X		F							
	159	R	1	Vital Signs Monitor on cart		20w x 28d x 36h	X			X		F							
	160	R	1	Crash Cart (red)		34w x 26d x 48h	X			X		F							
	149	R	1	Maxi Move standing patient lift	Arjo		X			X		F							
		R	1	IV Pole w/ Pumps			X			X		F							
		R	1	IV Pole w/ Pumps			X			X		F							
B8027	Clean Linen																		
	120	N	1	Shelving Unit (solid shelves)	Metro	48w x 24d x 72h	X			X		F							
	122	N	1	Shelving Unit (solid shelves)	Metro	48w x 24d x 72h	X			X		F							
	128	R	1	Comfort Cleanse Warmer (white)		28w x 14d x 18h	X			X		CT							
B8029	Conference/Report																		
		N	1	LCD Monitor - 50"			X			X		W							
		N	1	Workstation, Computer			X			X		D							
		N		Stacking Chair			X			X		F							
		N		Conference Chair			X			X		F							
		N		Conference Table			X			X		F							
		N	1	Projector			X			X		C							
		N	1	Projection Screen			X			X		C							
		N	1	Smart Board			X			X		W							