



- ## GENERAL NOTES
- EXISTING INTERIOR WALLS AND DOORS SHOWN WITH DASHED LINES ARE TO BE DEMOLITIONED.
 - CONTRACTOR TO ADJUST LOCATION OF CODE BLUE LIGHT, FIRE SPRINKLER HEAD LOCATED OUTSIDE EXISTING BATHROOM AND RELOCATE FIRE STROBE TO LOCATION ABOVE NEW BATHROOM DOOR. NEW BATHROOM DOOR TO HAVE ADA AUTOMATIC OPENER.
 - CONTRACTOR TO RELOCATE TO NEW WALL THE DUKANE CIRCUIT FUSE BOX (2 EA.) FOR CODE BLUE/NURSE CALL .
 - CONTRACTOR TO RELOCATE TO NEW WALL THE 2 DATA DROPS AND 1 DUPLEX EMERGENCY RECEPTACLE.
 - NEW BATHROOM DOOR TO BE SOLID CORE AND MEAS. 3' X 7' X 1 3/4"THK.
 - CONTRACTOR TO INSTALL NEW WHITE GRID AND ACOUSTICAL CEILING TILE, NEW FLOOR TILE AND WAINSCOT WALL TILE (48" HIGH).
 - CONTRACTOR TO INSTALL VA PROVIDED TOILET PAPER DISPENSER, SHARPS BOX, HAND SOAP AND TOWEL DISPENSER IN NEW PACU BATHROOM.
 - CONTRACTOR TO INSTALL CW UTILITY LINE, PLUMBING LINE AND DUPLEX ELEC. RECEPTACLE AT LOCATION INDICATED TO SERVICE ICE MACHINE. ICE MACHINE INSTALLED BY OTHERS.
 - CONTRACTOR TO REWORK/MODIFY ALL PLUMBING AND ELECTRICAL AS NEEDED FOR NEW ADA BATHROOM. INSTALL NEW LIGHTING AND MIRROR ABOVE NEW SINK.
 - CONTRACTOR TO SUBMIT SHOP DRAWINGS ON TOILET, SINK, NEW MIRROR, LIGHTS, TILE,DOOR AND DOOR FRAME AND ADA AUTOMATIC DOOR OPENER.