




- LEGEND**
- SERVICE NUMBER
ROOM NUMBER
- FINISHED FLOOR ELEVATION
- EXISTING TO REMAIN
- WALL LEGEND SYMBOL
- HAND RAIL
CORNER GUARD
- EQUIPMENT LEGEND**
- WV ITEM
V.A. SUPPLIED
V.A. INSTALLED
- VC ITEM
V.A. SUPPLIED
CONTRACTOR INSTALLED
- CC ITEM
CONTRACTOR SUPPLIED
CONTRACTOR INSTALLED
- WALL LEGEND**
- EXISTING WALL TO REMAIN
- EXISTING WALL FOR DEMOLITION
- NEW WALL CONSTRUCTION
- SMOKE BARRIER PARTITION
- ONE HOUR FIRE RATED PARTITION
- COMBINED ONE HOUR FIRE RATED PARTITION
AND SMOKE BARRIER PARTITION
- TWO HOUR FIRE RATED PARTITION
- COMBINED TWO HOUR FIRE RATED PARTITION
AND SMOKE BARRIER PARTITION
- TWO HOUR FIRE AND SMOKE RATED SHAFT WALL
- DRAWING KEYNOTES:**
1. 4" RWL DOWN FROM ABOVE.
 2. 6" RWL DOWN FROM ABOVE.
 3. SLEEVE EXISTING BRICK/BLOCK WALL AS NECESSARY.
 4. MOUNT P-604 AT 37" A.F.F. TO FLOOD RIM.
 5. ROUTE FULL SIZE DRAIN TO FLOOR DRAIN.
 6. 4" TYPE 'B' FLOOR DRAIN.
 7. ROUTE 1" CONDENSATE PIPING DOWN TO FLOOR DRAIN.
 8. FAN COIL UNIT.
 9. TRAP PRIMER ASSEMBLY.
 10. 1/2" DROPS TO TAILPIECE AT FLOOR DRAINS.
 11. STENCIL THIS MAIN "NO CONNECTION THIS PIPE" EVERY THREE FEET FROM THE ENTRANCE TO THE BUILDING TO THE NEW RPBPS IN EXISTING MECHANICAL ROOM 1001.
 12. REPLACE EXISTING DOUBLE CHECK VALVE ASSEMBLY WITH NEW DUPLEX 6" REDUCED PRESSURE BACKFLOW PREVENTER ASSEMBLY AND STRAINER. CONTRACTOR SHALL MAINTAIN WATER SERVICE TO BUILDING DURING REPLACEMENT.
 13. 6" WATER SERVICE ENTRANCE WITH SHUT-OFF VALVE.
 14. CAP VENT PIPING FOR FUTURE USE.
 15. VALVE AND CAP DOMESTIC WATER PIPING FOR FUTURE USE.
- NOTES**
- SLEEVE ALL PENETRATIONS THRU FLOOR AND WALL
CORE DRILLING SLAB IS PROHIBITED
- RELOCATED NATURAL GAS METER AND PRV
ASSEMBLY. COORDINATE EXACT LOCATION
IN FIELD WITH RESIDENT ENGINEER.
- 2 1/2" NATURAL GAS DOWN AND CONNECT TO
EXISTING 2 1/2" NATURAL GAS BELOW GRADE.
- PROVIDE MAIN GAS SHUT-OFF VALVE IN THE
VERTICAL RISE.
- 2 1/2" NATURAL GAS DOWN
AND CONNECT TO EXISTING
2 1/2" NATURAL GAS IN
CRAWL SPACE.

**PLUMBING
GROUND FLOOR PLAN**
one-eighth inch = one foot

 GS & P	Design Services	 GRESHAM SMITH AND PARTNERS	 Drawing Title PLUMBING GROUND FLOOR PLAN APPROVED PROJECT DIRECTOR	Project Title PHASE 3 BUILDING REPLACEMENT	Date MAY 14, 1999			
	For The Built Environment				Building Number 204	Checked GLD	Drawn JEM	Project No. 621-064
	Location DVAMC MOUNTAIN HOME, TN							

AREAS OF NEW CONSTRUCTION ARE FULLY PROTECTED
BY AN AUTOMATIC FIRE EXTINGUISHMENT SYSTEM

Revisions: _____ Date: _____

VA FORM 08-623A, MAR 1994

Department of Veterans Affairs