

- NOTES:
- SEE SHT. 204-E5 FOR POWER CONNECTIONS.
 - CONNECT INNER LAMPS TO ONE SWITCH. CONNECT OUTER LAMPS TO ONE SWITCH.
 - MOUNT FIXTURES IN MEDICAL RECORDS LOBBY WITH 36" SWIVEL STEM HANGERS.
 - REFER TO SHEET 204-E15 FOR ADD/ALTERNATE IN THIS AREA.

- GENERAL NOTES:
- BRANCH CIRCUIT HOMERUNS TO PANELBOARDS MAY BE GROUPED INTO FOUR WIRE BRANCH CIRCUITS, WITH THREE PHASE CONDUCTORS AND A COMMON NEUTRAL PROVIDED THAT EACH OF THE THREE PHASE CONDUCTORS ORIGINATE FROM DIFFERENT PHASES IN THE SAME PANELBOARD. NO MORE THAN THREE CIRCUITS WITH SHARED NEUTRAL SHALL BE INSTALLED IN SINGLE HOMERUN CONDUIT. DO NOT INSTALL MORE THAN ONE FEEDER CIRCUIT IN A CONDUIT. BRANCH CIRCUITS SHALL NOT BE ROUTED INTO WIRERAYS CONTAINING MORE WIRING THAN LISTED ABOVE FOR A BRANCH CIRCUIT CONDUIT.
 - CONTRACTOR SHALL INSTALL A GREEN GROUND WIRE NO SMALLER THAN NO. 12 AWG LARGER WHERE REQUIRED BY CODE FOR ALL POWER AND LIGHTING CIRCUITS INCLUDING SWITCH LEGS.
 - CONTRACTOR SHALL PROVIDE DOUBLE FACE EXIT LIGHTS AT LOCATIONS REQUIRED.


GROUND FLOOR PLAN
one-eighth inch = one foot
0 5' 10' 15'



Design Services
For The Built
Environment

GRESHAM
SMITH AND
PARTNERS

AREAS OF NEW CONSTRUCTION ARE FULLY PROTECTED
BY AN AUTOMATIC FIRE EXTINGUISHMENT SYSTEM



GROUND FLOOR PLAN
LIGHTING

PHASE 3
BUILDING REPLACEMENT

Project Title
Date
MAY 14, 1999

Building Number
204
Checked
M.J.B.
Drawn
P.M.
Location
DVAMC MOUNTAIN HOME, TN

Project No.
621-064
Drawing No.
204-E4
Dwg. of

Department of
Veterans Affairs