

DEPENDABLE, LLC

Material Safety Data Sheet

MSDS DATE 1/1/2002

Rev. 3-29-2011

Printed: 1/2013

1. CHEMICAL PRODUCT AND COMPANY IDENTIFICATION

PRODUCT NAME: **CUTDOWN II**Applied over concrete slabs and certain
other floors for moisture vapor transmission
reduction and adhesive residue isolationMANUFACTURED BY: Dependable, LLC
PO Box 16307
Rocky River, OH 44116-0334
440-333-1123 or 800-227-343424 hour emergency:
CHEMTREC: 800-424-9300

DOT Proper Shipping Name: Not required Reportable Quantity: None

2. COMPOSITION / INFORMATION ON INGREDIENTS

CHEMICAL FAMILY – Water Emulsion Latex Coating

CHEMICAL NAME: MIXTURE

COMPONENT	CAS NUMBER	AMOUNT (% w/w)	NOTE
Proprietary Formula	Mixture		

NPCA/HMIS INDEX

HAZARDOUS 4 – SEVERE
SYSTEM 1 – SLIGHTMATERIALS 3 – SERIOUS
0 – MINIMAL

IDENTIFICATION 2 – MODERATE

NFPA RATING: HEALTH 0 FIRE 0 REACTIVITY 0 PERSONAL PROTECTION 0 FLAMMABILITY 0

NO HAZARDOUS INGREDIENTS

Additional information will be provided in a medical emergency to qualified medical personnel.

3. PHYSICAL DATA

DESCRIPTION:

PHYSICAL STATE: Liquid

APPEARANCE: Light Beige

ODOR: Sweet

pH: 4-8

SOLUBILITY IN WATER: Miscible

SPECIFIC GRAVITY: 1.0

VAPOR PRESSURE: none

BOILING POINT (°F): 212°F

FREEZING POINT (°F): 32°F

VAPOR DENSITY: Heavier than air

VOC: 0 G/L (calculated)

4. FIRE AND EXPLOSION HAZARD DATA

FLASH POINT: >200°F

AUTO IGNITION: Not available

FIRE-FIGHTING EQUIPMENT: Wear self-contained breathing gear when in confined area.

EXTINGUISHING MEDIA: CO2, dry chemical or water fog

5. REACTIVITY DATA

DOT CATEGORY: Non Flammable

LEL: N/A

CHEMICAL STABILITY: Stable

HAZARDOUS POLYMERIZATION: Will not occur

CONDITIONS TO AVOID: Prevent from freezing

INCOMPATIBILITY: None known.

HAZARDOUS DECOMPOSITION PRODUCTS: When dry may produce CO, H₂O, CO₂ and NXO from burning.
Aromatic Hydrocarbons

UNUSUAL FIRE and EXPLOSION HAZARDS: None

6. HEALTH HAZARD DATA

THRESHOLD LIMIT VALUE: See Section II: Hazardous ingredients.

EFFECTS OF OVEREXPOSURE: None

EMERGENCY FIRST AID PROCEDURES: **KEEP OUT OF EYES** Flush eyes immediately with plenty of water for at least 15 minutes. Wash off skin with soap and water and remove contaminated clothing. Vapors should not be hazardous. If any symptoms persist, consult a physician. Do not induce vomiting if swallowed. Consult a physician.

7. PERSONAL PROTECTIVE MEASURES AND OCCUPATIONAL CONTROLS

EYE PROTECTION: Wear goggles or facemask

HAND/BODY PROTECTION: None

RESPIRATORY PROTECTION: Not required

OTHER PROTECTIVE EQUIPMENT: None

VENTILATION: Local ventilation

8. HANDLING PRECAUTIONS AND CONTROLS (Keep out of reach of children)

STORAGE CONDITIONS: Store in a cool, ventilated area, above freezing.

OTHER PRECAUTIONS: Do not ingest. Always wear eye and skin protection.

9. ENVIRONMENTAL AND DISPOSAL INFORMATION

DISPOSAL CONSIDERATIONS: Dam up to contain. Scoop up.

DISPOSAL METHOD: The disposal of contaminated absorbent material should comply with applicable federal, state and local laws and regulations.

10. REGULATORY INFORMATION

DOT PROPER SHIPPING NAME: Water Emulsion Latex Adhesive

US DOT HAZARD CLASS: None

DOT SHIPPING LABEL: None

IDENTIFICATION NUMBER:

OSHA Hazard Communication Standard (29 CFR 1910.1200) Status: None

TSCA (Toxic Substance Control Act) Chemical Substance Inventory: All components of this product are listed or excluded from listing – YES

Emergency Planning and Community Right-To-Know (SARA Title III) – Section 311/312 Classifications (40 CFR 372): NA

Section 313 Information (40 CFR 372): This product does not contain a chemical as listed in Section 313 above de minimum concentrations. The following listed chemicals are present (with CAS number and WT.%):

RCRA INFORMATION

Classified as a hazardous waste: NO

IMPORTANT: The information and data herein are believed to be accurate and have been compiled from sources believed to be reliable. It is offered for your consideration, investigation and verification. Buyer assumes all risk of use, storage, and handling of the product in compliance with applicable federal, state and local laws and regulations. DEPENDABLE, LLC makes no warranty of any kind, express or implied, concerning the accuracy or completeness of the information and data herein. DEPENDABLE, LLC will not be liable for claims relating to any party's use or reliance on information and data contained herein regardless of whether it is claimed that the information and data are inaccurate, incomplete or otherwise misleading.
