1 SITE PLAN - DEMOLITION
1/16"=1'-0"

KEYED NOTES:

1. REMOVE PORTION OF CONCRETE CURB
2. BLACKOUT STRIPING W/ NEW SEAL COAT
3. CLEAR & GRUB SEE ALSO LANDSCAPE DRAWINGS
4. REMOVE SIGN SEE AG101 (1)
5. REMOVE BOLLARDS
6. REMOVE PORTION OF PAVING
7. REMOVE SIGN SEE AG101
8. REMOVE SIGN SEE AG101
9. REMOVE & REPLACE SIGN A1 SEE AG101
10. REMOVE SIGN SEE AG101
11. PROTECT ALL EXISTING TREES SEE SPECIFICATION SECTION 01 57 19
12. REMOVE & CAP STORM DRAIN

LEGEND:

- SIGN TO BE REMOVED OR RELOCATED
- STRIPING TO BE REMOVED
- AREA TO CLEAR & GRUB SEE LANSCAPE DWGS FOR ADDITIONAL AREAS
- ASPHALT TO BE REMOVED

100% CONSTRUCTION DOCUMENTS

Revisions	Date
-	-
-	-
-	-
-	-
-	-
-	-
ADDENDUM 1	4/11/14
VA REVIEW	03/19/14
100% CONSTRUCTION DOCUMENTS	02/28/14

CONSULTANTS:

Stamp and Signature

ARCHITECT/ENGINEERS:

KPA THE KPA GROUP
ENGINEERS ARCHITECTS
ONE KAISER PLAZA SUITE 445
OAKLAND CALIFORNIA 94612
TEL 510.271.6701 FAX 510.271.6707
©THE KPA GROUP 2013
KPA Project No. 576.00

Drawing Title: SITE PLAN - DEMOLITION

Approved: Project Director
-
-
VAPAHCS PLANNING AND ENGINEERING

Project Title: EMERGENCY STORAGE RELOCATION

Location: 3801 MIRANDA AVENUE, PALO ALTO, CA

Date: 02/28/14 ADDENDUM 1 | Checked: PWP | Drawn: KPA TEAM

Project Number: 640-14-105P

Building Number:

Drawing Number: AD101

Dwg. of

Office of Construction and Facilities Management

VA PAHCS Veterans Affairs Palo Alto Health Care System

VA FORM 08-6231

UPDATED: 4/9/2014 5:42 PM