



WALL LEGEND (PLAN)

	2x4 D.F. STUD PARTITION 7 1/2" HIGH (TOP OF PLATE)
	FULL HEIGHT 2x4 D.F. STUD WALL (SEE F.LANS FOR HEIGHTS)
	CAVITY STONE
	STONE WALL W/ 2x4 D.F. STUD FURRING ON INTER. SIDE
	STONE WALL W/ A INTER. CONCRETE FINISH
	GLASS FULL HEIGHT

BUILDING NO. 1 - FLOOR PLAN

GENERAL NOTES: 1. REFER TO CLOSETORY PLAN DWS. NUMBER 1-4 FOR WALLS TO RECEIVE RECESSED PLANTER @ THE TOP OF CAVITY STONE WALLS.

2. AREA ON PLAN SHOWN AS SQ. TILE DESIGNATES AN AREA THAT SHALL BE RECESSED 1 1/2" BELOW THE SURROUNDING CONCRETE SLABS THAT WILL RECEIVE CARPET OR AN ARCHITECTURAL FINISH.

3. DIMENSIONS ARE SHOWN TO FACE OF WOOD STUD, FACE OF STONE WALL (REFER TO DET. 1/53 FOR WORK POINT) AND TO CENTER LINES OF COLUMNS AND GLASS MULLIONS. REFER TO ENLARGED PLANS AND CLOSETORY PLAN FOR DIMENSIONS NOT SHOWN.

4. INTERIOR GLASS AND GLAZING SHALL BE CONSIDERED A COMPONENT OF THE INTERIOR PARTITIONS. REFER TO INTERIOR ELEVATIONS FOR CROSS REFERENCE DETAILS. ALL INTERIOR GLASS SHALL BE 1/4" POLISHED CLEAR PLATE GLASS.

5. FOR GLASS BAYS AND WINDOW TYPES REFER TO SHT. NO. 1-9.

6. DOORS MARKED THIS "D-4" REFER TO DETAIL OF DOOR FRAMES. SEE DOOR TABLE NO. 1 SHEET NUMBER 1-9.

7. EXTERIOR FURRED WALLS TO BE FILLED WITH BATT INSULATION AND ALL FRAMED INTERIOR PARTITIONS TO HAVE SOUND ATTENUATION BLANKETS. (NO SOUND BLANKETS REQUIRED @ DIVIDER WALL OF ROOMS NO. 111 AND NO. 112.)

NO.	DATE	DESCRIPTION
1	11/1/82	AS BUILT - RELOCATED DOOR D2?
REVISIONS:		
SHEET TITLE		
FLOOR PLAN		
BLDG. NO.	PROJECT TITLE	
1	VETERANS ADMINISTRATION NATIONAL CEMETERY RIVERSIDE, CALIFORNIA PHASE 1 DEVELOPMENT	
DRAWN CHS	CHECKED RAR	DATE 9 MAR 77
Royston Hanamoto Beck & Abey LANDSCAPE ARCHITECTS & PLANNERS land planning park planning 225 Miller Avenue, Mill Valley, California (415) 953-7900		DRAWING NUMBER 1-3
Jones-Tillson Associates-Engineers Leland King & Associates-Architects		DWG. 73 OF 138 PROJECT NUMBER 789-533-001B
APPROVED: PROJECT DIRECTOR Veterans Administration		
LOCATION Riverside County, California		