



DOOR LEGEND				
CALLOUT	NOMINAL SIZE	MATERIAL	HARDWARE	GLAZING
DBL 3/0x6/8	6'-0" x 6'-8"	18ga. STEEL DOOR	LEVER / PANIC	NONE
3/0x6/8	3'-0" x 6'-8"	18ga. STEEL DOOR	LEVER / PANIC	NONE
3/0	3'-0" x 6'-8"	SOLID CORE WOOD	LEVER / LEVER	NONE
3/0X	3'-0" x 6'-8"	SOLID CORE WOOD	LEVER / PRIVACY	NONE
3/0C	3'-0" x 6'-8"	SOLID CORE WOOD	LEVER / STORAGE	NONE

WINDOW LEGEND			
CALLOUT	NOMINAL SIZE	TYPE	FINISH
3040	3'-0" x 4'-0"	SINGLE HUNG	BRONZE ALUM FRAME

- * DENOTES SHEAR WALL LOCATION
- ① - DENOTES 3-EA 2x4's AND 1-EA 3" WIDE x 26ga. STRAP AT EACH SIDE OF MATE-LINE. FASTENED W/ 16 - 1 5/8" .086 NAILS EACH END OF EACH STRAP. OR 11 - 1 1/2" x .148 NAILS EACH END OF EACH STRAP.

FLOOR PLAN

MENTAL HEALTH PHYS. OFFICE BUILDING 3

VA DALLAS, TX

JOB #: M7534

SERIAL #: 3057 A-H

SHEET No.

A-2

DATE:	3-10-08
SCALE:	1/8" = 1'-0"
PLOT SCALE:	1:1
DRAWN BY:	JW
CHECKED BY:	BA

No.	DESCRIPTION	BY	DATE

**ICON**
CONSTRUCTION

© 2005, Icon Construction, Inc. All Rights Reserved

RELEASE FOR PRODUCTION