

**AMENDMENT NO. 2**

VA Health Care System  
Replace Nurse Call System  
Fargo, ND      Image 1205.08 / VAMC 437-13-110

- A. Refer to the specifications of the above project and make the following additions, corrections, deletions, corrections and/or interpretations.
1. The existing facility telephone system is an Avaya CS-1000 Series, Software Version 7.6.
  2. The new nurse call server shall be installed in an existing server rack in the basement server room as indicated on Detail 1/E24. The server room is powered by an existing UPS system; additional UPS equipment is not required in this room.
  3. The contractor shall furnish and install a dual channel PRI interface card equal to Nortel/Meridian NT5D12AD Series, and MSD daughter card equal to Nortel/Meridian NTBK51CA Series, to be compatible with the existing Avaya telephone system. The contractor shall furnish and install this equipment and provide all necessary connections and ancillary equipment for interfacing the existing facility telephone system with the new wireless IP-based telephone equipment as described in Section 27 52 23, Paragraph 2.17.
  4. Phasing of existing system demolition and installation of new equipment: The new nurse call system may be installed in a phased process in lieu of a complete parallel installation as described on demolition plans E2-E12, General Note #2. The contractor may remove the existing nurse call equipment and associated dome light for a given room and install and activate the new equipment on a room by room basis. Room equipment to be made functional shall include the code blue buttons, staff registrations, touch screens, patient bed stations, auxiliary input jacks, pull cords, call cords, and the associated dome lights for that room. The associated code blue prerecorded announcements shall be functional as each room is switched over to the new system. The new local master station shall be fully operational and tested, and staff shall be trained in its use prior to conversion to the new system. The existing duty stations and master stations shall remain installed and functional until a complete turnover to the new system has occurred in a given clinic or coverage area. Activation of wireless handsets is not required as each room is brought online, this can occur after the complete system is in place and a more thorough training of staff is possible. Contractors shall closely coordinate the availability of rooms with the Owner prior to converting a room over to the new system.
- B. Refer to the drawings of the above project and make the following additions, corrections, deletions, corrections and/or interpretations.
1. Sheet E15 First Floor Remodeling Plans - Electrical
    - a. Room 1D-55A: Add dome light above doorway for pull cord station.
  2. Sheet E16 Second Floor Remodeling Plans - Electrical
    - a. Room 2B-77: This room shall be classified as a Procedure Room. Work in this room shall not be deducted under Alternate #1.

**END OF AMENDMENT NO. 2**