



1 FLOOR PLAN — DEMOLITION
SCALE: 1/8" = 1'-0"

KEY NOTES

- 1 REMOVE EXISTING FLOORING COMPLETE.
- 2 REMOVE EXISTING WALL TILE AND GYP COMPLETE TO EXPOSED STUDS.
- 3 REMOVE EXISTING CEILING COMPLETE.
- 4 REMOVE EXISTING TOILET COMPLETE WITH SUPPORT. SEE NEW PLAN FOR MTG. HT.
- 5 REMOVE EXISTING WALL MOUNTED LAV COMPLETE.
- 6 REMOVE EXISTING TUB COMPLETE.
- 7 REMOVE EXISTING WALL COMPLETE. SEE NEW PLAN.
- 8 REMOVE EXISTING SHOWER FIXTURES COMPLETE.
- 9 PROVIDE 1 HR CONSTRUCTION BARRIER WITH ACCESS DOOR PER NFPA 241.
- 10 REMOVE EXISTING GYP CEILING. FRAMING TO REMAIN FOR NEW CEILING

GENERAL NOTES

- 1 PROVIDE NEGATIVE AIR DURING WORK.
- 2 ITEMS TO BE SALVAGED WILL BE IDENTIFIED BY OWNER PRIOR TO START OF WORK

WORK SHOWN IS IN 1C, 1D WORK IDENTICAL SEE REFERENCE DRAWINGS FOR PLAN LAYOUT.

CONSULTANTS:		ARCHITECT/ENGINEERS:		Drawing Title FLOOR PLAN - DEMOLITION		Project Title -- -- --		Project Number -- Building Number --		Office of Construction and Facilities Management
				Approved Project Director		Location --		Drawing Number AD-101		
						Date --		Checked --		
						Drawn --		Dec. --		