



1 FLOOR PLAN — NEW  
SCALE: 1/8" = 1'-0"

DOOR NO.	DOOR SIZE	FRAME TYPE	FINISH	HARDWARE SET	COMMENTS
143	EXIST.	EXIST	PAINT	EXIST.	REPAINT FRAME, RELAMINATE DOOR
143A	EXIST.	EXIST	PAINT	EXIST	REPAINT FRAME, RELAMINATE DOOR
143B	4070	H.M.	PAINT	HW-1	PAINT FRAME, LAMINATE DOOR

HW-1 — 3 HINGES, OVERHEAD CLOSER, 3 DOOR SILENCERS, PRIVACY LOCK SET WITH EMERGENCY RELEASE. MATCH EXIST FACILITY.

## KEY NOTES

- 1 INSTALL NEW SHOWER PAN.
- 2 INSTALL NEW TOILET. MOUNT AT ADA HEIGHT.
- 3 INSTALL NEW WALL HUNG LAV.
- 4 INSTALL NEW EPOXY FLOORING OVER SHOWER PAN WITH 6" COVE BASE.
- 5 INSTALL NEW WHIRLPOOL TUB
- 6 NEW FOLDING SHOWER BENCH ADA AND BARIATRIC COMPLIANT.
- 7 INSTALL NEW ADA SHOWER FIXTURES TO MATCH EXISTING IN THE FACILITY
- 8 INSTALL NEW WALL TILE WITH ACCENT BANDS TO MATCH OTHER AREAS IN THE FACILITY.
- 9 INSTALL NEW WALL TILE WITH ACCENT BANDS TO MATCH OTHER AREAS IN THE FACILITY. EPOXY PAINT ABOVE
- 10 INSTALL NEW CUBICAL CURTAIN TRACK IN CEILING
- 11 EQUIPMENT BY OWNER
- 12 INSTALL NEW ADA GRAB BARS IN ALL LOCATIONS TO INCLUDE VERTICAL BARS
- 13 INSTALL NEW WALL FULL HT WITH TILE.
- 14 GOVERNMENT FURNISHED CONTRACTOR INSTALL WASH STATION.

## GENERAL NOTES

- 1 RELAMINATE EXIST DOORS WITH WILSONARE "AMBER CHERRY" 7919-38 (.050 THICKNESS) ALL FACES/EDGES. NEW DOOR TO HAVE SAME FINISH.
- 2 TOILET ACCESSORIES OWNER PROVIDED, CONTRACTOR INSTALLED, TOILET PAPER DISP., SOAP DISP., PAPER TOWEL DISP. REMAINING ITEMS CONTRACTOR FURNISHED, CONTRACTOR INSTALLED.
- 3 WALL FRAMING SHALL BE 4", 20 GA METAL STUDS FULL HT. TO STRUCTURE ABOVE.

WORK SHOWN IS IN 1C, 1D WORK IDENTICAL SEE REFERENCE DRAWINGS FOR PLAN LAYOUT.

### CONSULTANTS:

### ARCHITECT/ENGINEERS:

Drawing Title

FLOOR PLAN - NEW

Approved Project Director

Project Title

---

Location

Date

Checked

Drawn

Project Number

---

Drawing Number

AS-101

Page of

Office of  
Construction  
and Facilities  
Management



Virginia