

Column Schedule			
COLUMN DESIGNATION		C1	C2
COLUMN	SIZE	22"Ø	HSS 4x4x3/8
	BASE PLATE	---	1/2"x8"x8"
	ANCHOR RODS	8-#8 BARS	(4) 3/4"Øx1'
	NOTES	#4 TIES @12"	







### First Floor Plan

1/8"=1'-0"

1. NEW COLUMNS ARE TO USE EXISTING COLUMN STUBS AND FOUNDATIONS.
2. DEMOLITION OF A SECTION OF EXISTING FLOOR WILL BE REQUIRED AT LOCATIONS OF NEW COLUMNS TO ALLOW CONSTRUCTION.
3. FINISH FLOOR (TOP OF SLAB) ELEVATION 621'-0".

CONSTRUCTION DOCUMENTS - 100% FINALS FULLY SPRINKLERED

<b>CONSULTING ENGINEERS:</b>  <b>LBYP, Inc.</b> Civil and Structural Engineers 716 South 30th Street Birmingham, AL 35233 Main (205) 251-4500 Fax (205) 324-4181		<b>C.R.S.</b> Engineering & Design Consultants Birmingham • Huntsville 3504 7th Avenue South Birmingham, Alabama 35222 205.323.2373 craig@crs.com		<b>ARCHITECT:</b>  <b>CMH Architects, Inc.</b> 1800 International Park Drive, Suite 300 Birmingham, AL 35243 (205)969-2696 • TEL (205)969-3930 • FAX www.cmharch.com Copyright © 2011 CMH Architects, Inc.		<b>PROJECT MANAGEMENT:</b>  <b>WALKER AND MOORE</b> 1108 Laurel Lane Montgomery, Alabama 36106 Telephone: 334.380.4999 Facsimile: 334.264.5555		<b>Drawing Title</b> <b>FIRST FLOOR PLAN</b>		<b>Project Title</b> <b>A/E AMBULATORY SURGERY IMPROVEMENTS</b>		<b>Project Number</b> <b>521-328</b>		<b>Building Number</b> <b>0000000000</b>		<b>Office of Construction and Facilities Management</b> 	
<b>Approved Project Director</b> <b>James Zellander</b>		<b>Location</b> <b>VAMC - Birmingham, Alabama</b>		<b>Date</b> <b>5/23/2014</b>		<b>Checked</b> <b>WIN</b>		<b>Drawn</b> <b>GVA</b>		<b>Drawing Number</b> <b>S202</b>		<b>Dwg</b> 4 <b>of</b> 124					