

Column Schedule			
COLUMN DESIGNATION		C1	C2
COLUMN	SIZE	22"Ø	HSS 4x4x3/8
	BASE PLATE	EXISTING	1/2"x8"x8"
	ANCHOR RODS	8-#8 BARS	(4) 3/4"Øx1"
	NOTES	#4 TIES @12"	



Third Floor Framing Plan

$$1/8'' = 1' - 0''$$


1. NEW COLUMNS TO USE EXISTING COLUMN STUBS AND FOUNDATIONS.
2. FINISH FLOOR (TOP OF SLAB) ELEVATION MATCH EXISTING $\pm 644'-2 \frac{1}{4}"$.
3. NEW FLOOR SYSTEM: 10" CAST IN PLACE CONCRETE SLAB.
4. NEW CONCRETE TO BE N.W. 5,000 PSI, SEE GENERAL NOTES AND SPECS.

[illegible]

CONSULTING ENGINEERS:



LBYD, Inc.
Civil and Structural Engineers
716 South 30th Street
Birmingham, AL 35233
Main (205) 251-4500
Fax (205) 324-4181



ARCHITECT:



CMH Architects, Inc.
1800 International Park Drive, Suite 300
Birmingham, AL 35243
(205)969-2696 - TEL
(205)969-3930 - FAX
www.cmharch.com
Copyright © 2011 CMH Architects, Inc.

PROJECT MANAGEMENT:



KER AND MOORE INTERIOR DESIGN

 PROJECT MANAGEMENT

Montgomery, Alabama 36106 Telephone: 334.380.4599 Facsimile: 334.264.5585

Drawing Title

THIRD FLOOR FRAMING PLAN

Approved: Project Director
James Zellander

Project Title

A/E AMBULATORY SURGERY IMPROVEMENTS

Location	VAMC - Birmingham, Alabama
----------	----------------------------

Project Number
521-328

Building Number
0000000000

Drawing Number
000 4

Dwg. 6 of 124

Office of
Construction
and Facilities
Management



CONSTRUCTION DOCUMENTS - 100% FINALS FULLY SPRINKLERED