

PLUMBING FIXTURE BASIS OF DESIGN			
FXIT. NO.	DESCRIPTION	MANUFACTURER & MODEL NUMBER	REMARKS
M	ICE MAKER BOX	<u>FIXTURE</u> : GUY GRAY B200, SUPPLY BOX W/DRAIN	SUPPLY/DRAIN BOX WALL MOUNTED
CS	CLINICAL SINK	<u>CHINA</u> : KOHLER K-12867, VITREOUS CHINA SINK W/SIPHON JET FLUSHING RM, 1-1/2" TOP SPUD. <u>FAUCET</u> : KOHLER K-13642, CHROME-PLATED FAUCET, 4" WRIST CONTROL HANDLES, PLAIN END SPOUT WITH PAUL HOOK-ALL BRACE, LOOSE KEY STOPS. <u>BEDPAN WASHER</u> : KOHLER K-13660 BEDPAN WASHER WITH WALL MOUNTED SELF-CLOSING DOUBLE FLEX CONTROL MIXING VALVE. <u>VALVE</u> : ZURN Z-6000A-2-80-IN FLUSH VALVE. <u>SUPPLIES</u> : ZURN Z-1216 CONCEALED WALL CARRIER. <u>COUPLER</u> : KOHLER K-8935 THREE 11" STAINLESS STEEL RM GUARDS.	WALL MOUNTED, WITH BEDPAN WASHER
LVM	LAVATORY MEDICAL, ADA COMPLIANT	<u>CHINA</u> : KOHLER K-1997-1, SINGLE-FAUCET HOLE, WITH OVERFLOW, ADA COMPLIANT. <u>SINK</u> : ZURN Z6820-XL-CPA, SENSOR OPERATED, BATTERY POWERED, 5-3/8" RIGID GOOSENECK FAUCET, CHROME PLATED, 1.5 GPM, ADA DESIGNED. <u>SUPPLIES</u> : ZURN Z8800, Z8746-PC, Z8700. <u>TRAP WRAP</u> : ZURN Z8946-3-NT, TRAP/SUPPLY PROTECTORS <u>CARRIER</u> : ZURN Z1231 CONCEALED ARM CARRIER	WALL MOUNTED, BATTERY OPERATED FAUCET, INSTALLED W/TMV-1
LV	LAVATORY PUBLIC, ADA COMPLIANT	<u>CHINA</u> : AMERICAN STANDARD D124.024, THREE-FAUCET HOLES, WITH OVERFLOW, WALL HUNG, ADA COMPLIANT. <u>FAUCET</u> : SLOAN OPTIMA EBF-1, POLISHED CHROME-PLATED CAST BRASS FAUCET, BATTERY POWERED, 4" CENTERSET ELECTRONIC HAND WASHING FAUCET FOR TEMPERED WATER, 0.5 GPM, ADA COMPLIANT. <u>SUPPLIES</u> : ZURN Z8800, Z8746-PC, Z8700. <u>TRAP WRAP</u> : ZURN Z8946-3-NT, TRAP/SUPPLY PROTECTORS	WALL MOUNTED, BATTERY OPERATED SENSOR FAUCET, INSTALLED W/TMV-1
SKM	SINK, MEDICAL	<u>BOWL</u> : ELKAY LR2219, 3 FAUCET HOLES ON 4" CENTERS, STAINLESS, 7-5/8" DEEP FAUCET, ZURN Z81284-XL-18", POLISHED CHROME-PLATED CAST BRASSES, 11" TALL W/INTERGRAL SHANKS, QUARTER TURN CERAMIC DISC CARTRIDGE, 1" TALL INTERNAL CAST SPOUT, 1.5 GPM LAMINAR FLOW AERATOR, 4" VANDAL-RESISTANT BRASS WRIST BLADE COLOR-CODED HANDLES, 1-1/4" GRID STRAINER <u>SUPPLIES</u> : MCGUIRE ST02LX 1/2" X 3/8" SUPPLY WITH LOOSE-KEY STOP <u>MCGUIRE</u> B902 1-1/4" X 1-1/2" P-TRAP WITH ESCUTCHION. <u>ACCESSORIES</u> : ELKAY UK-99 DRAIN	COUNTER MOUNTED, SINGLE COMPARTMENT SINK. W/TMV-1
SK-1	SINK	<u>BOWL</u> : ELKAY LR2219, 3 FAUCET HOLES ON 4" CENTERS, STAINLESS, 7-5/8" DEEP FAUCET, ZURN Z81284-XL-18", POLISHED CHROME-PLATED CAST BRASSES, 11" TALL W/INTERGRAL SHANKS, QUARTER TURN CERAMIC DISC CARTRIDGE, 1" TALL INTERNAL CAST SPOUT, 1.5 GPM AERATOR, 4" VANDAL-RESISTANT BRASS WRIST BLADE COLOR-CODED HANDLES, 1-1/4" GRID STRAINER <u>SUPPLIES</u> : MCGUIRE ST02LX 1/2" X 3/8" SUPPLY WITH LOOSE-KEY STOP <u>MCGUIRE</u> B902 1-1/4" X 1-1/2" P-TRAP WITH ESCUTCHION. <u>ACCESSORIES</u> : ELKAY UK-99 DRAIN	COUNTER MOUNTED, SINGLE COMPARTMENT SINK. W/TMV-1
SS	SCRUB SINK	<u>UNIT</u> : JST JK5-770-1 SINGLE STATION SCRUB SINK WITH KNEE ACTIVATED SOAP AND WATER CONTROLS, 16 GAUGE 304 STAINLESS STEEL, SOUND DEADENED UNDERSIDE. <u>ACCESSORIES</u> : JST JT-150 CAST BRASS P-TRAP WITH CLEANOUT. <u>JUST</u> JTM-47 MIXING VALVE. <u>JUST</u> J35-SSS DRAIN SYSTEM.	COUNTER MOUNTED, SINGLE COMPARTMENT SINK. W/TMV-1
WC-1	WATER CLOSET, ADA	<u>BOWL</u> : CRANE 31080, ELONGATED BOWL, FLOOR MOUNTED BACK OULET <u>FLUSH VALVE</u> : SLOAN OPTIMA Q2 8111, 1.6 GPF, BATTERY SENSOR, FLUSH VALVE <u>SEAT</u> : BEWIS 16055ST, ELONGATED OPEN FRONT W/STAINLESS STEEL CHECK HINGE <u>CARRIER</u> : STANDARD INSTALLATION: ZURN Z1213-W42, VERTICAL NON-SUPPORT SYSTEM W/2" TOP VENT <u>CARRIER BACK TO BACK INSTALLATION</u> : ZURN Z1204-ND, ADJUSTABLE VERTICAL SIPHON JET - NO-HUB, WITH 2" TOP VENT	FLOOR MOUNTED, BACK OUTLET, ADA HEIGHT BATTERY OPERATED SENSOR VALVE