


0 2 4 6 8 16
SCALE: 1/8" = 1'-0"

1. ALL EXISTING FIRE PROTECTION SYSTEM PIPING AND SPRINKLERS SHALL REMAIN IN PLACE AND IN-SERVICE DURING THE WORK OF OTHER TRADES - CEILINGS, LIGHT FIXTURES, HVAC EQUIPMENT, ETC.
2. WHERE EXISTING FIRE PROTECTION PIPING OBSTRUCTS THE DEMOLITION/REMOVAL OF THE WORK OF OTHER TRADES, CONTRACTOR SHALL CUT/REMOVE/RELOCATE PIPING AS NEEDED TO FACILITATE THE DEMOLITION.
3. FIRE PROTECTION PIPING SHALL BE RETURNED TO SERVICE AS SOON AS DEMOLITION WORK IS COMPLETED IN AREAS THAT CONTRACTOR IS RESPONSIBLE FOR. FIRE PROTECTION PIPING SHALL BE RETURNED TO SERVICE AT THE END OF THE WORK DAY AND SHALL NOT BE SHUT OFF AFTER HOURS.
4. CONTRACTOR SHALL USE EXTREME CARE TO AVOID ACCIDENTALLY DAMAGING OR DISCHARGING SPRINKLERS THAT COULD CAUSE A FALSE DISCHARGE CONDITION.

PLAN	Project Title A/E AMBULATORY SURGERY IMPROVEMENTS			Project Number 521-328		<div>Office of Construction and Facilities Management</div> <div>  <div>Department of Veterans Affairs</div> </div>
				Building Number 0000000000		
	Location YAMC - Birmingham, Alabama			Drawing Number		
	Date 5/23/2014	Checked RWS	Drawn DLB	<div>FP201</div> <div>Dwg. 95 of 124</div>		