



LIGHTING FIXTURE SCHEDULE					
FIXTURE TYPE	LAMPS	VOLTAGE	MOUNTING	BASIS OF DESIGN	DESCRIPTION
				MANUFACTURER CATALOG NUMBER	
A	(6) 40W/T12	277V	RECESSED	DAY-BRITE 25LPF64-0FA12RF- 277-RF- 3/2 EMB	4" FLUORESCENT RECESSED MOUNTED SURGICAL LIGHT FIXTURE, CRI BETWEEN 5000-6000K, TO MATCH CEILING MOUNTED SURGICAL LIGHT FIXTURES. LOW-FREQUENCY HYBRID ELECTROMAGNETIC RAPID-START BALLAST, <10% THD, WITH a,b,c SWITCHING, RFI RESIST, U.D LAMP LISTED.
AE	(6) 40W/T12	277V	RECESSED	DAY-BRITE 25LPF64-0FA12RF- 277-RF- 3/2 EMB	SIMILAR TO TYPE 'A' FIXTURE ABOVE, EXCEPT WITH EMERGENCY BATTERY BALLAST.
B	(2) 28W/T8	277V	RECESSED	DAY-BRITE 21F832-21-UNV- 1/2-EB10R	4" FLUORESCENT RECESSED MOUNTED LIGHT FIXTURE, RAPID-START ELECTRONIC BALLAST, <10% THD, U.D LAMP LISTED.
C	(2) 28W/T8	277V	SURFACE	DAY-BRITE AWW232-PMW-UNV- 1/2-EB10R	4" FLUORESCENT WALL BRACKET LIGHT FIXTURE, DIE-FORMED 20 GAUGE COLD-ROLLED STEEL HOUSING, ELECTRONIC BALLAST, <10% THD, PROGRAM START, U.D LAMP LISTED.

		CONSULTANTS:	ENGINEER-OF-RECORD RANDALL A. HENSLEY	CA P.E. NO. 18607	ARCHITECT/ENGINEERS: <div><div>AKEA</div><div>INC.</div><div>3603 NW 98th Street, Suite B Gainesville, FL 32606 Phone: (352) 474-6124 Fax: (352) 474-6324 COA: FL #26693 AKEA Project No. 072-14</div></div>	Drawing Title	Project Number	Office of Construction and Facilities Management	
						ELECTRICAL DETAILS	508-14-105		
						Approved: Project Director	Location		Drawing Number
							Atlanta, Georgia		
							Date	Checked	Drawn
							APRIL 30, 2014	RAH	KLL
									E300 32 of 36
Revisions:	Date				<div><div></div><div>Department of Veterans Affairs</div></div>				