

B-46 Electrical Feed:

The contractor will replace the current 3 phase 100A feed and electric panel to B-46 that is routed through B-100. The feed is supplied from B-112. The electric panel will be wall mounted inside B-46. A 100A main breaker disconnect as well as one (1) 50A, four (4) 30A, and three (3) 20A breakers will also need to be provided. The feed will need to be sized to accommodate the panel load. The feed will need to be routed underground, placed in conduit, and marked in accordance with the current specification. A feed length of 175 feet should be used for estimating purposes. Electric outage time will need to be kept to 4 hours or less.