TOILET ACCESSORY SCHEDULE

ACCESSORY	ROOM		ACCESSORY			MOUNTING HEIGHT		RESPONSIBILITY			
T.A. #	NUMBER	NAME	DESCRIPTION	MANUFACTURER	QUANTITY	HEIGHT	REMARKS	PURCHASED BY	PLACED BY	INSTALLED BY	COMMENTS
~~TA-9B-2~~			~~Robe Hook Double~~	~~TO BE SELECTED BY VA~~	~~7~~	~~6' - 0"~~	~~To Top of Unit (Typical Height)~~	~~Contractor~~	~~Contractor~~	~~Contractor~~	
~~TA-9B-2~~			~~Robe Hook Double~~	~~TO BE SELECTED BY VA~~	~~1~~	~~6' - 0"~~	~~To Top of Unit (Typical Height)~~	~~Contractor~~	~~Contractor~~	~~Contractor~~	
1-000											
HSPK											
TA-11-2	1-000	HSPK	Utility Shelf - 24"	Bobrick	2	6' - 0"	To Top of Unit	Contractor	Contractor	Contractor	
1-102											
OFFICE											
TA-9B-1	1-102	OFFICE	Robe Hook Double	TO BE SELECTED BY VA	1	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-103											
ADMIN. OFFICE											
TA-9B-1	1-103	ADMIN. OFFICE	Robe Hook Double	TO BE SELECTED BY VA	1	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-104											
OFFICE											
TA-9B-1	1-104	OFFICE	Robe Hook Double	TO BE SELECTED BY VA	1	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-106A											
MEN'S TOILET											
TA-1A-2	1-106A	MEN'S TOILET	Glass Mirror	TO BE SELECTED BY VA	2	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	
TA-2C	1-106A	MEN'S TOILET	Soap Dispenser	PROVON, OR APPROVED EQUAL	2	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-106A	MEN'S TOILET	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-5B-2	1-106A	MEN'S TOILET	Toilet Tissue Dispenser - Double Roll	GEORGIA PACIFIC, OR APPROVED EQUAL	3	1' - 6"	To Top of Unit	Contractor	Contractor	Contractor	
TA-6A-5	1-106A	MEN'S TOILET	Grab Bar 36"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6A-6	1-106A	MEN'S TOILET	Grab Bar 42"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6B-2	1-106A	MEN'S TOILET	Grab Bar 24" - Vertical	TO BE SELECTED BY VA	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	
1-106B											
WOMEN'S TOILET											
TA-1A-2	1-106B	WOMEN'S TOILET	Glass Mirror	TO BE SELECTED BY VA	3	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	
TA-2C	1-106B	WOMEN'S TOILET	Soap Dispenser	PROVON, OR APPROVED EQUAL	2	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-106B	WOMEN'S TOILET	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	2	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-5B-2	1-106B	WOMEN'S TOILET	Toilet Tissue Dispenser - Double Roll	GEORGIA PACIFIC, OR APPROVED EQUAL	4	1' - 6"	To Top of Unit	Contractor	Contractor	Contractor	
TA-6A-5	1-106B	WOMEN'S TOILET	Grab Bar 36"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6A-6	1-106B	WOMEN'S TOILET	Grab Bar 42"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6B-2	1-106B	WOMEN'S TOILET	Grab Bar 24" - Vertical	TO BE SELECTED BY VA	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	
TA-7A	1-106B	WOMEN'S TOILET	Sanitary Napkin Vendor - Recessed	TO BE SELECTED BY VA	1						SEE TOILET ACCESSORY LEGEND AE408 FOR MOUNTING HEIGHT
TA-14A	1-106B	WOMEN'S TOILET	Baby Changing Station - Vertical	TO BE SELECTED BY VA	1	5' - 2"	To Top of Unit	Contractor	Contractor	Contractor	
1-109											
OFFICE											
TA-9B-1	1-109	OFFICE	Robe Hook Double	TO BE SELECTED BY VA	1	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-111											
OFFICE											
TA-9B-1	1-111	OFFICE	Robe Hook Double	TO BE SELECTED BY VA	1	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-112											
OFFICE											
TA-9B-1	1-112	OFFICE	Robe Hook Double	TO BE SELECTED BY VA	1	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-113											
EXAM											
TA-2C	1-113	EXAM	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-113	EXAM	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-113	EXAM	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-115											
EXAM											
TA-2C	1-115	EXAM	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-115	EXAM	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-115	EXAM	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-116											
EXAM											
TA-2C	1-116	EXAM	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-116	EXAM	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-116	EXAM	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-117											
EXAM											
TA-2C	1-117	EXAM	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-117	EXAM	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-117	EXAM	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-118											
OFFICE											
TA-9B-1	1-118	OFFICE	Robe Hook Double	TO BE SELECTED BY VA	1	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-119											
ACTIVITY ROOM											
~~TA-1A-5~~	~~1-119~~	~~ACTIVITY ROOM~~	~~MIRROR, WALL MOUNTED~~	~~TO BE SELECTED BY VA~~	~~3~~	~~3' - 4"~~	~~To Bottom of Reflective Surface~~	~~CONTRACTOR~~		~~CONTRACTOR~~	
1-122A											
STAFF TLT.											
TA-1A-2	1-122A	STAFF TLT.	Glass Mirror	TO BE SELECTED BY VA	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	
TA-2C	1-122A	STAFF TLT.	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-122A	STAFF TLT.	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-5B-2	1-122A	STAFF TLT.	Toilet Tissue Dispenser - Double Roll	GEORGIA PACIFIC, OR APPROVED EQUAL	1	1' - 6"	To Top of Unit	Contractor	Contractor	Contractor	
TA-6A-5	1-122A	STAFF TLT.	Grab Bar 36"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6A-6	1-122A	STAFF TLT.	Grab Bar 42"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6B-2	1-122A	STAFF TLT.	Grab Bar 24" - Vertical	TO BE SELECTED BY VA	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	
1-123											
HSKP.											
TA-11-2	1-123	HSKP.	Utility Shelf - 24"	Bobrick	1	6' - 0"	To Top of Unit	Contractor	Contractor	Contractor	
1-202											
PHYSICAL THERAPY CLINIC											
TA-2C	1-202	PHYSICAL THERAPY CLINIC	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-202	PHYSICAL THERAPY CLINIC	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
1-203											
PRIVATE TREATMENT ROOM											
TA-2C	1-203	PRIVATE TREATMENT ROOM	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-203	PRIVATE TREATMENT ROOM	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-8	1-203	PRIVATE TREATMENT ROOM	Lavatory Protective Enclosures	Truebro IPS Corporation	1	0"	To Bottom of Unit	Contractor	Contractor	Contractor	SEE TOILET ACCESSORY LEGEND AE408 FOR MOUNTING HEIGHT
1-205											
SHARED ACTIVITY/ EQUIPMENT											
~~TA-1A-5~~	~~1-205~~	~~SHARED ACTIVITY/ EQUIPMENT~~	~~MIRROR, WALL MOUNTED~~	~~TO BE SELECTED BY VA~~	~~7~~	~~3' - 4"~~	~~To Bottom of Reflective Surface~~	~~CONTRACTOR~~		~~CONTRACTOR~~	
1-304											
PRIV. TREATMENT RM											
TA-2C	1-304	PRIV. TREATMENT RM	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-304	PRIV. TREATMENT RM	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-8	1-304	PRIV. TREATMENT RM	Lavatory Protective Enclosures	Truebro IPS Corporation	1	0"	To Bottom of Unit	Contractor	Contractor	Contractor	SEE TOILET ACCESSORY LEGEND AE408 FOR MOUNTING HEIGHT
TA-9B-1	1-304	PRIV. TREATMENT RM	Robe Hook Double	TO BE SELECTED BY VA	1	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-403											
PT. TLT.											
TA-1A-2	1-403	PT. TLT.	Glass Mirror	TO BE SELECTED BY VA	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	
TA-2C	1-403	PT. TLT.	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-403	PT. TLT.	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-5B-2	1-403	PT. TLT.	Toilet Tissue Dispenser - Double Roll	GEORGIA PACIFIC, OR APPROVED EQUAL	1	1' - 6"	To Top of Unit	Contractor	Contractor	Contractor	
TA-6A-5	1-403	PT. TLT.	Grab Bar 36"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6A-6	1-403	PT. TLT.	Grab Bar 42"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6B-2	1-403	PT. TLT.	Grab Bar 24" - Vertical	TO BE SELECTED BY VA	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	
1-404											
PT. TLT.											
TA-1A-2	1-404	PT. TLT.	Glass Mirror	TO BE SELECTED BY VA	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	
TA-2C	1-404	PT. TLT.	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-404	PT. TLT.	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-5B-2	1-404	PT. TLT.	Toilet Tissue Dispenser - Double Roll	GEORGIA PACIFIC, OR APPROVED EQUAL	1	1' - 6"	To Top of Unit	Contractor	Contractor	Contractor	
TA-6A-5	1-404	PT. TLT.	Grab Bar 36"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6A-6	1-404	PT. TLT.	Grab Bar 42"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6B-2	1-404	PT. TLT.	Grab Bar 24" - Vertical	TO BE SELECTED BY VA	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	
1-406											
TREATMENT											
TA-2C	1-406	TREATMENT	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-406	TREATMENT	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-406	TREATMENT	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-407											

TOILET ACCESSORY SCHEDULE

ACCESSORY	ROOM		ACCESSORY			MOUNTING HEIGHT		RESPONSIBILITY			
T.A. #	NUMBER	NAME	DESCRIPTION	MANUFACTURER	QUANTITY	HEIGHT	REMARKS	PURCHASED BY	PLACED BY	INSTALLED BY	COMMENTS
TREATMENT											
TA-2C	1-407	TREATMENT	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-407	TREATMENT	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-407	TREATMENT	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-408											
TREATMENT											
TA-2C	1-408	TREATMENT	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-408	TREATMENT	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-408	TREATMENT	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-409											
TREATMENT											
TA-2C	1-409	TREATMENT	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-409	TREATMENT	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-409	TREATMENT	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-411											
TREATMENT											
TA-2C	1-411	TREATMENT	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-411	TREATMENT	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-411	TREATMENT	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-416											
TECHNICIAN'S WORKROOM											
TA-2C	1-416	TECHNICIAN'S WORKROOM	Soap Dispenser	PROVON, OR APPROVED EQUAL	2	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-416	TECHNICIAN'S WORKROOM	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	2	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-9B-1	1-416	TECHNICIAN'S WORKROOM	Robe Hook Double	TO BE SELECTED BY VA	2	3' - 4"	To Top of Unit (ADA Height)	Contractor	Contractor	Contractor	
1-501											
K.T.C. WEIGHT CONDITIONING											
~~TA-1A-5~~	~~1-501~~	~~K.T.C. WEIGHT CONDITIONING~~	~~MIRROR, WALL MOUNTED~~	~~TO BE SELECTED BY VA~~	~~11~~	~~3' - 4"~~	~~To Bottom of Reflective Surface~~	~~CONTRACTOR~~		~~CONTRACTOR~~	
1-502											
TREATMENT											
TA-2C	1-502	TREATMENT	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-502	TREATMENT	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-8	1-502	TREATMENT	Lavatory Protective Enclosures	Truebro IPS Corporation	1	0"	To Bottom of Unit	Contractor	Contractor	Contractor	SEE TOILET ACCESSORY LEGEND AE408 FOR MOUNTING HEIGHT
1-601											
WOMEN'S SHOWER/ LOCKER											
~~TA-1A-1~~	~~1-601~~	~~WOMEN'S SHOWER/ LOCKER~~	~~MIRROR, WALL MOUNTED~~	~~TO BE SELECTED BY VA~~	~~1~~	~~3' - 4"~~	~~To Bottom of Reflective Surface~~	~~CONTRACTOR~~		~~CONTRACTOR~~	
TA-1A-2	1-601	WOMEN'S SHOWER/ LOCKER	Glass Mirror	TO BE SELECTED BY VA	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	
TA-2C	1-601	WOMEN'S SHOWER/ LOCKER	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-2D	1-601	WOMEN'S SHOWER/ LOCKER	Ceramic Soap Dish	TO BE SELECTED BY VA	1	3' - 6"	To Top of Dish	Contractor	Contractor	Contractor	
TA-3B	1-601	WOMEN'S SHOWER/ LOCKER	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-5B-2	1-601	WOMEN'S SHOWER/ LOCKER	Toilet Tissue Dispenser - Double Roll	GEORGIA PACIFIC, OR APPROVED EQUAL	1	1' - 6"	To Top of Unit	Contractor	Contractor	Contractor	
TA-6A-5	1-601	WOMEN'S SHOWER/ LOCKER	Grab Bar 36"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6A-6	1-601	WOMEN'S SHOWER/ LOCKER	Grab Bar 42"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6B-2	1-601	WOMEN'S SHOWER/ LOCKER	Grab Bar 24" - Vertical	TO BE SELECTED BY VA	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	
TA-8	1-601	WOMEN'S SHOWER/ LOCKER	Lavatory Protective Enclosures	Truebro IPS Corporation	1	0"	To Bottom of Unit	Contractor	Contractor	Contractor	SEE TOILET ACCESSORY LEGEND AE408 FOR MOUNTING HEIGHT
TA-12B-2	1-601	WOMEN'S SHOWER/ LOCKER	Shower Rod - Extra Heavy Duty	Bobrick	2	6' - 0"	To CL of Tubing	Contractor	Contractor	Contractor	
1-604B											
TLT.											
TA-1A-2	1-604B	TLT.	Glass Mirror	TO BE SELECTED BY VA	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	
TA-2C	1-604B	TLT.	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-604B	TLT.	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-5B-2	1-604B	TLT.	Toilet Tissue Dispenser - Double Roll	GEORGIA PACIFIC, OR APPROVED EQUAL	1	1' - 6"	To Top of Unit	Contractor	Contractor	Contractor	
TA-8	1-604B	TLT.	Lavatory Protective Enclosures	Truebro IPS Corporation	1	0"	To Bottom of Unit	Contractor	Contractor	Contractor	SEE TOILET ACCESSORY LEGEND AE408 FOR MOUNTING HEIGHT
1-605											
MEN'S SHOWER/ LOCKER											
TA-1A-2	1-605	MEN'S SHOWER/ LOCKER	Glass Mirror	TO BE SELECTED BY VA	2	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	
~~TA-1A-5~~	~~1-605~~	~~MEN'S SHOWER/ LOCKER~~	~~MIRROR, WALL MOUNTED~~	~~TO BE SELECTED BY VA~~	~~1~~	~~3' - 4"~~	~~To Bottom of Reflective Surface~~	~~CONTRACTOR~~		~~CONTRACTOR~~	
TA-2C	1-605	MEN'S SHOWER/ LOCKER	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-2D	1-605	MEN'S SHOWER/ LOCKER	Ceramic Soap Dish	TO BE SELECTED BY VA	5	3' - 6"	To Top of Dish	Contractor	Contractor	Contractor	
TA-3B	1-605	MEN'S SHOWER/ LOCKER	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
TA-5B-2	1-605	MEN'S SHOWER/ LOCKER	Toilet Tissue Dispenser - Double Roll	GEORGIA PACIFIC, OR APPROVED EQUAL	1	1' - 6"	To Top of Unit	Contractor	Contractor	Contractor	
TA-6A-3	1-605	MEN'S SHOWER/ LOCKER	Grab Bar 24"	Bobrick	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6A-5	1-605	MEN'S SHOWER/ LOCKER	Grab Bar 36"	TO BE SELECTED BY VA	2	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6A-6	1-605	MEN'S SHOWER/ LOCKER	Grab Bar 42"	TO BE SELECTED BY VA	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	
TA-6B-2	1-605	MEN'S SHOWER/ LOCKER	Grab Bar 24" - Vertical	TO BE SELECTED BY VA	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	
TA-7A-1	1-605	MEN'S SHOWER/ LOCKER	Folding Shower Seat with Slat	TO BE SELECTED BY VA	1	1' - 6"	Top of Unit	Contractor	Contractor	Contractor	
TA-12B-1	1-605	MEN'S SHOWER/ LOCKER	Shower Rod - Extra Heavy Duty	Bobrick	4	6' - 0"	To CL of Tubing	Contractor	Contractor	Contractor	
TA-12B-3	1-605	MEN'S SHOWER/ LOCKER	Shower Rod - Extra Heavy Duty	Bobrick	1	6' - 0"	To CL of Tubing	Contractor	Contractor	Contractor	
1-701											
M.H.O.T. CLINIC											
TA-2C	1-701	M.H.O.T. CLINIC	Soap Dispenser	PROVON, OR APPROVED EQUAL	1	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-701	M.H.O.T. CLINIC	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	1	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	
1-802A											
BATHROOM											
TA-6A-4A	1-802A	BATHROOM	Grab Bar 30" - Tub Lower Grab Bar	TO BE SELECTED BY VA	2	2' - 2"	To Top of Tubing. Bottom of Tubing to be 9" above Bathtub Rim	Contractor	Contractor	Contractor	
TA-6A-7A	1-802A	BATHROOM	Grab Bar 48" - Tub Lower Grab Bar	TO BE SELECTED BY VA	1	2' - 2"	To Top of Tubing. Bottom of Tubing to be 9" above Bathtub Rim	Contractor	Contractor	Contractor	
1-803											
ADL KITCHEN & LAUNDRY											
TA-2C	1-803	ADL KITCHEN & LAUNDRY	Soap Dispenser	PROVON, OR APPROVED EQUAL	2	4' - 2 7/8"	To Top of Unit	OWNER	Contractor	Contractor	
TA-3B	1-803	ADL KITCHEN & LAUNDRY	Paper Towel Dispenser	GEORGIA PACIFIC, OR APPROVED EQUAL	2	3' - 11"	To Top of Unit	Contractor	Contractor	Contractor	

NOTE: SEE SHEET AE-002 FOR ALTERNATES

FULLY SPRINKLERED

ISSUED FOR BID

Revisions	Date

CONSULTANTS:

Project Manager	Architect	Structural Engineer	MEP/FP Engineer	Civil Engineer	Fire Protection Consultant	Cost Estimator	Aquatic Consultant	Associate Architects
BRAY MOONEY CONSULTING	ARRAY HEALTHCARE FACILITIES SOLUTIONS	WZG, STRUCTURAL CONSULTING ENGINEERS	APOGEE CONSULTING GROUP	GUIDON DESIGN	HARRINGTON GROUP	BRAY MOONEY CONSULTING	ATLANTIC AQUATIC ENGINEERING	W. COOK ARCHITECTS
410 E. 21 STREET CHESTER, PA, 19013 Tel (610) 872-3716	2520 RENAISSANCE BLVD., SUITE 110 KING OF PRUSSIA, PA, 19406 Tel (610) 270-0599	P.O. BOX 24 40 LITTLE ROAD ZIEGLERVILLE, PA, 19492 Tel (610) 287-3194	7330 CHAPEL HILL ROAD, SUITE 202 RALEIGH, NC, 27606 Tel (919) 858-7420	2453 N DELAWARE STREET INDIANAPOLIS, IN 46205 Tel (317) 800-6388	7508 E. INDEPENDENCE BLVD., SUITE 116 CHARLOTTE, NC, 28277 Tel (704) 531-9077	410 E. 21 STREET CHESTER, PA, 19013 Tel (610) 872-3716	1823 DEEP RUN ROAD PIPERSVILLE, PA, 18947 Tel (215) 766-0409	1251 ROMANSVILLE ROAD COATESVILLE, PA, 19320 Tel (610) 383-4460

PROJECT MANAGER: Bray Mooney Consulting

Project Number	Scale
3627	

Drawing Title: SCHEDULES - TOILET ACCESSORY

Approved: Project Director

Project Title: RENOVATE BUILDING 69

Location: 1400 Black Horse Hill, Coatesville, PA

Date: 1/22/2014 | Checked: Checker | Drawn: Author

VA Project Number: 542-CSI-203

Building Number: 69

Drawing Number: AE702

Dwg. 39 of 86

Office of Facilities Management

Department of Veterans Affairs

VA FORM 08-6231, OCT 1978