

FINISH SCHEDULE

FINISH CONTRACTOR MUST REVIEW ALL SPECIFICATIONS AND DRAWINGS PRIOR TO ORDERING MATERIALS AND COMMENCING FABRICATION AND INSTALLATION. MANY ITEMS ARE LONG-LEAD AND SHOULD BE ORDERED PROMPTLY. LOCATION DESCRIPTIONS ARE FOR REFERENCE ONLY AND ARE NOT INDICATIVE OF EVERY OCCURRENCE OF A PARTICULAR FINISH. REFER TO FINISH PLAN FOR EXACT LOCATIONS.

CEILING

AS MANUFACTURED BY ARMSTRONG WORLD INDUSTRIES, INC.
SALES REPRESENTATIVE: NANCY MEDL
PHONE: 215-491-2179

WHEREVER POSSIBLE, GRIDS TO BE CENTERED IN THE ROOM ON THE CENTER LINE OF THE CEILING TILE. INSTALL NO TILE SMALLER THAN 6" WIDE. ALL CEILING GRIDS TO BE ARMSTRONG WORLD INDUSTRIES.
COLOR: WHITE, U.N.O.

C-1
STYLE: HEALTH ZONE ULTIMA #1937 OR APPROVED EQUAL
EDGE PROFILE: BEVELED REGULAR
DIMENSIONS: 2' x 2' x 3/4"
GRID: PRELUDE
COLOR: WHITE
FOR USE AS THE GENERAL CEILING, U.N.O.

C-2
STYLE: OPTIMA OPEN PLAN #354 OR APPROVED EQUAL
EDGE PROFILE: BEVELED REGULAR
DIMENSIONS: 2' x 2' x 1"
GRID: 1516" SQUARE REGULAR
COLOR: WHITE

C-3
GYPSUM WALLBOARD SOFFT
COLOR: TBD

NOTE: WHERE THE FASCIA OF SOFFITS ALIGNS WITH THE ADJACENT PARTITION, PROVIDE 1/4" FRY REGLET REVEAL TO TERMINATE A MATERIAL OR COLOR. ALL SOFFT FASCIAS ARE TO RECEIVE PAINT, NOT VINYL WALLCOVERING. PLEASE REFER TO THE REFLECTED CEILING PLAN FOR LOCATIONS OF CEILING TILES.

C-4
STYLE: HEALTH ZONE OPTIMA #3114 OR APPROVED EQUAL
EDGE PROFILE: SQUARE REGULAR
DIMENSIONS: 2' x 2' x 1"
GRID: PRELUDE (MOISTURE AND CHEMICAL RESISTANT)
COLOR: WHITE
FOR USE IN POOL AND SHOWER AREAS

PANT

ALL PAINT AS MANUFACTURED BY: SHERWIN WILLIAMS

NOTE: ALL WALLS TO BE EGGSHELL FINISH, U.N.O. TOILET ROOMS ARE TO BE SEMI-GLOSS WATER BASE EPOXY. ALL TRIM AND FRAMES TO BE SEMI-GLOSS FINISH. METAL PANELS TO BE PAINTED TO MATCH ADJACENT WALL. ALL GWS CEILINGS AND SOFFITS TO BE FLAT FINISH, U.N.O. SOFFITS ARE NEVER TO RECEIVE VINYL WALLCOVERING AND FACE AND UNDERSIDE ARE TO BE PAINTED TO MATCH EXPOSED CEILINGS TO RECEIVE TWO PART EPOXY COATING

PT-1
COLOR: CANVAS TAN SW7531
FOR USE AS GENERAL PAINT, U.N.O.

PT-2
COLOR: OUTERBANKS SW7534
FOR USE AS DOOR FRAME AND TRIM PAINT, U.N.O.

PT-3
COLOR: MANOR HOUSE SW7505
FOR USE AS ACCENT PAINT

PT-4
COLOR: ARTISAN TAN SW7540
FOR USE AS ACCENT PAINT

PT-5
COLOR: HOMESTEAD BROWN SW7515
FOR USE AS ACCENT PAINT

PT-6
COLOR: HOMBERG GRAY SW7622
FOR USE AS ACCENT PAINT

PT-7
COLOR: HARDWARE SW8172
FOR USE AS ACCENT PAINT

PT-8
COLOR: WHITE
FOR USE AS THE COLOR UNDER THE ENTRANCE CANOPY
FOR USE ON THE STEEL WITHIN THE POOL

CERAMIC WALL TILE

AS MANUFACTURED BY DALTILE
SALES REPRESENTATIVE: SUSAN METKA
PHONE: 484-276-9387

CWT-1
STYLE: SPARK COLORBODY PORCELAIN OR APPROVED EQUAL
COLOR: TBD
DIMENSIONS: 12" x 24" x 3/16"
GROUT COLOR: TBD
GROUT WIDTH: 1/8"

CWTB-1
STYLE: COVE BASE S-30076 OR APPROVED EQUAL
COLOR: TO MATCH CWT-1
DIMENSIONS: 8" X 12"
GROUT COLOR: TO MATCH CWT-1
GROUT WIDTH: TO MATCH CWT-1

CWT-2
STYLE: SPARK COLORBODY PORCELAIN OR APPROVED EQUAL
COLOR: TBD
DIMENSIONS: 12" x 24" x 3/16"
GROUT COLOR: TBD
GROUT WIDTH: 1/8"

RUBBER BASE

AS MANUFACTURED BY MANNINGTON
SALES REPRESENTATIVE: JESSICA D'ANGELO
PHONE: 610-675-6599

RB-1
STYLE: SYNC RUBBER WALL BASE (TYPE TP) OR APPROVED EQUAL
COLOR: 918 FLAX
DIMENSIONS: 4" H x 120" COL
6" H IN SOLED UTILITY ROOMS AND JANITOR'S CLOSETS

SEAL JOINTS BETWEEN TOP OF WALL BASE AND IRREGULAR WALL SURFACES

WALL PROTECTION

AS MANUFACTURED BY CS ACROVYN
SALES REPRESENTATIVE: BRAD GLDIN
PHONE: 610-825-0320

PWP-1
PLASTIC WALL PROTECTION OR APPROVED EQUAL
STYLE: 4000 /6000 RIGID SHEET
DIMENSIONS: 4' x 10' SHEET
SURFACE: SHADOWGRAN
COLOR: BEIGE # 103
JOINTS/TRANSITIONS: COLOR MATCHING CAULK (NO PLASTIC TRIM PIECES)

CG-1
STYLE: CO-8 CORNER GUARD OR APPROVED EQUAL
DIMENSIONS: 3/16" LESS X FULL HEIGHT
ANGLE: 90 DEGREES
304 STAINLESS ALLOY WITH #4 SATIN FINISH
MOUNTED WITH CONSTRUCTION ADHESIVE AND STAINLESS STEEL SCREWS

BG-1
STYLE: FR-225N BUMPER GUARD OR APPROVED EQUAL
DIMENSIONS: 2-1/4" H x 3/4" D
ACROVYN 400 COVER
TEXTURE: SHADOWGRAN
COLOR: BEIGE # 103
RETAINER: ALUMINUM
COLOR: MATCHING END CAPS

HR-1
STYLE: P-RWS PLATFORM HANDRAIL OR APPROVED EQUAL
DIMENSIONS: 6-3/8" H x 3"D
TOP RAIL WOOD SPECIES: MAPLE
TOP RAIL WOOD FINISH: 448 WALNUT
BOTTOM RAIL COLOR: #4 POLISH (3 SIDES)
BRACKET COLOR: TBD
MATCHING END CAPS RETURNING TO THE WALL

PLASTIC LAMINATE

AS MANUFACTURED BY FORMICA
SALES REPRESENTATIVE: SAMANTHA SMTH
PHONE: 1-800-367-6422

PL-1
STYLE: 9012 LX EBONY OR APPROVED EQUAL
FINISH: LUXE
FOR USE AS VERTICAL LAMINATE, U.N.O.

PL-2
STYLE: 1883-58 PECAN WOODLINE OR APPROVED EQUAL
FOR USE AS HORIZONTAL LAMINATE, U.N.O.

SOLID SURFACE POLYMER

AS MANUFACTURED BY MEGANITE
DISTRIBUTOR: FESSENDEN HALL, INC.
SALES REPRESENTATIVE: ROSE LEISTER
PHONE: 609-686-1883

SSP-1
COLOR: 419 SURFIN SAFARI OR APPROVED EQUAL
FOR USE AS GENERAL COUNTER TOP, U.N.O.

SSP-2
COLOR: 501 SAN RAFAEL STONE OR APPROVED EQUAL
FOR USE IN TOILET ROOMS AND LABORATORY

SSP-3
SOLID SURFACE POLYMER SINK
CORIAN 180 SIDE OVERFLOW
COLOR: TBD
FOR USE AS TYPICAL TOILET ROOM SINK, U.N.O.

CANPET

AS MANUFACTURED BY SHAW CONTRACT
SALES REPRESENTATIVE: YICKY MCCONAGHY
PHONE: 610-299-0862

CPT-1
STYLE: METRO S0885 OR APPROVED EQUAL
COLOR: TBD
TYPE: BROADLOOM
DIMENSIONS: BROADLOOM
FOR USE IN SOUND BOOTHS

LUXURY VINYL TILE

AS MANUFACTURED BY MANNINGTON
SALES REPRESENTATIVE: JESSICA D'ANGELO
PHONE: 610-675-6599

LVT-1
STYLE: NATURE S PATH SELECT PLANK OR APPROVED EQUAL
COLOR: TBD
DIMENSIONS: 7" W PLANK

VINYL COMPOSITION TILE

AS MANUFACTURED BY MANNINGTON
SALES REPRESENTATIVE: JESSICA D'ANGELO
PHONE: 610-675-6599

VCT-1
STYLE: PROGRESSIONS OR APPROVED EQUAL
COLOR: 55137 SANDRIFT
DIMENSIONS: 12" x 12" x .125"

VCT-2
STYLE: PROGRESSIONS OR APPROVED EQUAL
COLOR: 55129 PUTTY
DIMENSIONS: 12" x 12" x .125"

VCT-3
STYLE: PROGRESSIONS OR APPROVED EQUAL
COLOR: 55103 WHEAT
DIMENSIONS: 12" x 12" x .125"

VCT-4
STYLE: PROGRESSIONS OR APPROVED EQUAL
COLOR: 55019 BEO ROCK
DIMENSIONS: 12" x 12" x .125"

VCT-5
STYLE: PROGRESSIONS OR APPROVED EQUAL
COLOR: 55525 CALICO
DIMENSIONS: 12" x 12" x .125"

VCT-6
STYLE: PROGRESSIONS OR APPROVED EQUAL
COLOR: 55265 FROSTED JADE
DIMENSIONS: 12" x 12" x .125"

VCT-7
STYLE: PROGRESSIONS OR APPROVED EQUAL
COLOR: 55509 DARK BARK
DIMENSIONS: 12" x 12" x .125"

SOLID RUBBER TILE

AS MANUFACTURED BY MANNINGTON COMMERCIAL
SALES REPRESENTATIVE: JESSICA D'ANGELO
PHONE: 610-675-6599

SRT-1
STYLE: COLORSPEC - SCULPTURED
COLOR: SAND DOLLAR
DIMENSIONS: 18 1/8" X 18 1/8" X 1/8"

SRT-2
STYLE: COLORSPEC - SCULPTURED
COLOR: 880 STRAW
DIMENSIONS: 18 1/8" X 18 1/8" X 1/8"

SRT-3
STYLE: COLORSPEC - SCULPTURED
COLOR: 822 CANYON
DIMENSIONS: 18 1/8" X 18 1/8" X 1/8"

SRT-4
STYLE: COLORSPEC - SCULPTURED
COLOR: SHADOW GRAY
DIMENSIONS: 18 1/8" X 18 1/8" X 1/8"

RUBBER STAIR TREAD

AS MANUFACTURED BY MANNINGTON COMMERCIAL
SALES REPRESENTATIVE: JESSICA D'ANGELO
PHONE: 610-675-6599

RST-1
STYLE: COLORSPEC VISUAL IMPAIRED STAIR TREAD
2" ABRASIVE STRIP IN CONTRASTING COLOR
TREAD COLOR: TBD
ABRASIVE STRIP COLOR: TBD
DIMENSIONS: 61 X 18" THICKNESS
NOSE: SQUARE

SHEET VINYL

AS MANUFACTURED BY MANNINGTON
SALES REPRESENTATIVE: JESSICA D'ANGELO
PHONE: 610-675-6599

SV-1
STYLE: BIOSPEC MD OR APPROVED EQUAL
COLOR: SANDRIFT 16203
DIMENSIONS: 6' ROLL 5000S X 0.080" THICKNESS
HEAT WELD: COLOR MATCHING

SV-1
STYLE: BIOSPEC MD OR APPROVED EQUAL
COLOR: SANDRIFT 16203
DIMENSIONS: 6' ROLL 5000S X 0.080" THICKNESS
HEAT WELD: COLOR MATCHING

SV-1
STYLE: BIOSPEC MD OR APPROVED EQUAL
COLOR: SANDRIFT 16203
DIMENSIONS: 6' ROLL 5000S X 0.080" THICKNESS
HEAT WELD: COLOR MATCHING

CERAMIC TILE

AS MANUFACTURED BY GST
SALES REPRESENTATIVE: JAMIE BLOCK
PHONE: 215-316-1731

CT-1
STYLE: SPARK COLORBODY PORCELAIN OR APPROVED EQUAL
COLOR: TOASTED LUSTER SK52
DIMENSIONS: 12" x 12"
GROUT COLOR: TBD
GROUT WIDTH: TBD

RESINOUS FLOORING

AS MANUFACTURED BY STONHARD, INC
SALES REPRESENTATIVE: BOB STEIN
PHONE: 610-416-0171

RS-1
STYLE: STONHARD STONSHIELD URT
COLOR: ACORN
TEXTURE: MEDIUM
GAUGE: 1/8"
WEARING SURFACE: CLEAR UV RESISTANT, ALIPHATIC POLYSPARTIC URETHANE SEALER

RSB-1
STYLE: TO MATCH RS-1
COLOR: TO MATCH RS-1
DIMENSIONS: 6" H INTEGRAL BASE

RS-2
STYLE: STONHARD STONSHIELD URT
COLOR: DRIFTWOOD
PATTERN: MEDIUM
GAUGE: 1/8"
WEARING SURFACE: CLEAR UV RESISTANT, ALIPHATIC POLYSPARTIC URETHANE SEALER

RSB-2
STYLE: TO MATCH RS-2
COLOR: TO MATCH RS-2
DIMENSIONS: 6" H INTEGRAL BASE

RS-2
STYLE: STONHARD STONSHIELD URT
COLOR: DRIFTWOOD
PATTERN: MEDIUM
GAUGE: 1/8"
WEARING SURFACE: CLEAR UV RESISTANT, ALIPHATIC POLYSPARTIC URETHANE SEALER

RSB-2
STYLE: TO MATCH RS-2
COLOR: TO MATCH RS-2
DIMENSIONS: 6" H INTEGRAL BASE

ENTRANCE MAT

AS MANUFACTURED BY THE MOHAWK GROUP - LEES
SALES REPRESENTATIVE: MICHELLE RUBINIO
PHONE: 215-630-6993

EM-1
COLLECTION: TUFF STUFF OR APPROVED EQUAL
STYLE: STEP IN STYLE MODULAR G1066
COLOR: BLURNEY STONE 0518
DIMENSIONS: 24" x 24"
INSTALLATION: BRICK

FLOORING ACCESSORIES

ACCESSORY PIECES: SCHLUTER TRANSITION STRIPS
CARPET TO RESILIENT OR SHEET VINYL: SCHLUTER SCHEME-AE100
CARPET TO LVT: SCHLUTER SCHEME-AE100
CARPET TO CERAMIC TILE: SCHLUTER SCHEME-AE100
CARPET TO EXISTING: SCHLUTER-RAND-KAMP-AE100-BBS
CERAMIC TILE TO EPOXY: SCHLUTER SCHEME-AE100
CERAMIC TILE TO SHEET VINYL: SCHLUTER SCHEME-AE100

FABRIC WRAPPED PANELS

AS MANUFACTURED BY MHARAM
SALES REPRESENTATIVE: HEATHER MOORE
PHONE: 215-837-2441

FWP-1
STYLE: REPLY
COLOR: 001 CANVAS
CONTENTS: 100% POLYESTER
WIDTH: 48"
REPEAT: 1/4" V, 4 3/4" H
BACKING: ACRYLIC BACKING

CURBICLE CURTAIN

AS MANUFACTURED BY DESIGNTX
SALES REPRESENTATIVE: STAN SKULSKI
PHONE: 610-864-2344

TO BE INSTALLED 15" A.F.F. TO BOTTOM OF HEM WITH CODE COMPLIANT MESH AT TOP WHERE REQUIRED.

CC-1
STYLE: SUGAR LASH 7510-402
COLOR: TEMPEST
WIDTH: 72"

PATTERN REPEAT: 48 1/2" V, 24 1/4" H
CONTENTS: 100% TREVIRA CS

WINDOW TREATMENT

AS MANUFACTURED BY MECOHSHADES SYSTEMS
SALES REPRESENTATIVE: RICH ROSENBAUM
PHONE: 215-682-9075

WT-1
MANUAL SHADE: MECOH'S SUMLINE WITH FASCIA OR APPROVED EQUAL
MOUNT: WALL OR CEILING
SHADECLOTH: ECOVEL 1580 SERIES (8% OPEN)
COLOR: WHITE 1581
CONTENT: 100% THERMOPLASTIC OLEFIN
WIDTH: 100"

NFPA 701-2004: PASS
FOR USE ON ALL EXTERIOR WINDOWS EXCEPT FOR 1ST FLOOR ENTRANCE AND 2ND FLR WAITING, U.N.O.

WINDOW FILM

AS MANUFACTURED BY 3M
SALES REPRESENTATIVE: BOB SWARTLEY
PHONE: 610-408-8000

WF-1
STYLE: FASARA DECORATIVE WINDOW FILMS
PATTERN: RWKU SHOPTIX
DIMENSIONS: 30" W X 96-4L

SPECIALTY EQUIPMENT SCHEDULE

EQUIP. NUMBER	EQUIPMENT DESCRIPTION	RESPONSIBILITIES			REQUIRES BLOCKING	REMARKS
		PURCHASED BY	RELOCATED/ PLACED BY	INSTALLED BY		
001	COMPUTER WITH KEYBOARD AND MOUSE	OWNER		CONTRACTOR		INSTALLED WITH LINKS PANIC ALARM SYSTEM
002	EXAM TABLE		OWNER	OWNER		
003	EXAM TABLE		OWNER	OWNER		
005	WORKSTATION MOUNTING BRACKET W/ADJUSTIBLE ARM	OWNER		CONTRACTOR	X	
007	MOBILE CART		OWNER	OWNER		
008	PATIENT TABLE WITH CHATTANOOGA		OWNER	OWNER		
010	CRASH CART		OWNER	OWNER		
011	SINGLE BOX GLOVE DISPENSER	OWNER		CONTRACTOR		
014	HAMPER, SOILED LINEN		OWNER	OWNER		
018	LIGHT, EXAM, PORTABLE	OWNER		OWNER		
021	LOCKERS		CONTRACTOR	CONTRACTOR		
023	MICROWAVE	OWNER		OWNER		
025	PRINTER/FAX/COPYER, COUNTERTOP	OWNER		CONTRACTOR		
026		OWNER		CONTRACTOR		
032	REFRIGERATOR, UNDERCOUNTER	OWNER		CONTRACTOR		
033	REFRIGERATOR, UNDERCOUNTER	OWNER		CONTRACTOR		
033A	REFRIGERATOR WITH FREEZER	OWNER		CONTRACTOR		
034	DISPOSAL, SHARPS, WALL MOUNT	OWNER		CONTRACTOR		
034B	DISPOSAL, SHARPS, WALL MOUNT	OWNER		CONTRACTOR		
035	MOBILE CASEWORK		OWNER	OWNER		
044	VISUAL DISPLAY BOARD, 48"	CONTRACTOR		CONTRACTOR		
047A	TV, 51" LCD, WALL MOUNTED	CONTRACTOR		CONTRACTOR	X	
047B	TV, 41" LCD, WALL MOUNTED	CONTRACTOR		CONTRACTOR	X	
047C	TV, 51" LCD, WALL MOUNTED	CONTRACTOR		CONTRACTOR	X	
051	BLOOD PRESSURE MACHINE		OWNER	OWNER		
058	SCALE, CLINICAL, ADULT, DIGITAL, FLOOR		OWNER	OWNER		
070	DISH WASHER		OWNER	OWNER		
071	WASHING MACHINE		OWNER	OWNER		
072	DRIER		OWNER	OWNER		
073A	HOT/COLD PACK		OWNER	OWNER		HOT PACK
073B	HOT/COLD PACK		OWNER	OWNER		COLD PACK
074	MIRROR, WALL MOUNTED	CONTRACTOR		CONTRACTOR		
074A	MIRROR, MOBILE		OWNER	OWNER		
116	STOVE		OWNER	OWNER		
117	ELLIPTICAL CROSS TRAINER		CONTRACTOR	CONTRACTOR		
118	UPRIGHT BIKE		OWNER	OWNER		
119A	ROW MACHINE		CONTRACTOR	CONTRACTOR		
119B	LOW ROW MACHINE		CONTRACTOR	CONTRACTOR		
120	CABLE COLUMN		CONTRACTOR	CONTRACTOR		
121	ABDOMINAL MACHINE		CONTRACTOR	CONTRACTOR		
122	ARM CURL MACHINE		CONTRACTOR	CONTRACTOR		
123	BICEPS/TRICEPS MACHINE		CONTRACTOR	CONTRACTOR		
124	CHEST PRESS		CONTRACTOR	CONTRACTOR		
125	LATERAL PULL MACHINE		CONTRACTOR	CONTRACTOR		
126	GLUTE MACHINE		CONTRACTOR	CONTRACTOR		
127	LEG CURL MACHINE		CONTRACTOR	CONTRACTOR		
128	LEG PRESS MACHINE		CONTRACTOR	CONTRACTOR		
129	LEG EXTENSION MACHINE		CONTRACTOR	CONTRACTOR		
130	SHOULDER PRESS		CONTRACTOR	CONTRACTOR		
131	TORSO ROTATION MACHINE		CONTRACTOR	CONTRACTOR		
132A	DECLINE BENCH		CONTRACTOR	CONTRACTOR		
132B	FLAT BENCH		CONTRACTOR	CONTRACTOR		
132C	FLAT BENCH		CONTRACTOR	CONTRACTOR		
133	OVERHEAD PRESS		CONTRACTOR	CONTRACTOR		
134	LEG RISE MACHINE		CONTRACTOR	CONTRACTOR		
136	DUMBBELL RACK		CONTRACTOR	CONTRACTOR		
137	PUNCHING BAG		CONTRACTOR	CONTRACTOR		PROVIDE UNISTRUT SUPPORTS ABOVE CEILING
138	CHAIR, CLINICAL, RECLINER, TREATMENT	OWNER		CONTRACTOR		
150	DOLLY		OWNER	OWNER		
151	SKELETON		OWNER	OWNER		
152	WEIGHT STORAGE		OWNER	OWNER		
154A	MATT TABLE		OWNER	OWNER		
154B	TREATMENT TABLE		OWNER	OWNER		
154C	TREATMENT TABLE		OWNER	OWNER		
155	TREADMILL		OWNER	OWNER		
156A	TREADMILL		OWNER	OWNER		
156B	TREADMILL		OWNER	OWNER		
156C	TREADMILL		OWNER	OWNER		
156D	TREADMILL		CONTRACTOR	CONTRACTOR		
156E	TREADMILL		OWNER	OWNER		
159A	PARRALLEL BARS	OWNER		OWNER		
159B	PARRALLEL BARS, WALL MOUNTED	OWNER		OWNER	X	
160A	WALL PULLY		OWNER	OWNER	X	
160B	WALL PULLY		OWNER	OWNER	X	
160C	WALL PULLY		OWNER	OWNER	X	
160D	WALL PULLY		OWNER	OWNER	X	
162	CROZEX MACHINE		OWNER	OWNER		
163	ELLIPTICAL TOTAL BODY MACHINE		OWNER	OWNER		
164	TRAINING STAIRS		OWNER	OWNER		
165	ELLIPTICAL PRECOR		OWNER	OWNER		
166	CABLE MACHINE		OWNER	OWNER		
167	LEG PRESS		OWNER	OWNER		
169	RECLUMBENT BIKE		OWNER	OWNER		
170	UPRIGHT BIKE		OWNER	OWNER		
172	RESISTANCE SYSTEM		OWNER	OWNER		
173	UPPER BODY EXERCISOR		OWNER	OWNER		
174	PEG BOARD		CONTRACTOR	CONTRACTOR	X	
175	HYDRAFITNESS MACHINE		OWNER	OWNER		
176	SOUND BOOTH	OWNER		CONTRACTOR		BOO: MIDLANTIC TECHNOLOGIES GROUP - ACOUSTIC SYSTEMS CUSTOM DOUBLE WALL CONTROL / DOUBLE WALL EXAM AUDIOMETRIC TEST SUITE
177	CLOCK	OWNER		OWNER		