

AIR FILTER SCHEDULE																
MARK	LOCATION	AREA AND/OR BLDG SERVED	SYSTEM AND/OR SERVICE	MERV RATING	AIR FLOW		APD				HOUSING TYPE	CARTRIDGES				REMARKS
							INITIAL		CHANGEOVER			#	SIZE		ARRANGEMENT	
					CFM	[L/s]	IN	[Pa]	IN	[Pa]			IN	[mm]		
(AHU-12)	ATTIC	ISOLATION ROOMS 315, 323	A.I.I. SUPPLY	8	600	[280]	0.31	[78]	1	[250]	AHU	1	2	[50]	N/A	----
(AHU-14)	ATTIC	ISOLATION ROOMS 338, 346	A.I.I. SUPPLY	8	626	[300]	0.31	[78]	1	[250]	AHU	1	2	[50]	N/A	----
(EF-29 PRE)	ROOF	ISOLATION ROOM 315	A.I.I. FILTERED EXHAUST	8	350	[170]	0.31	[78]	1	[250]	BAG IN / BAG OUT	1	2	[50]	N/A	----
(EF-29 FIN)	ROOF	ISOLATION ROOM 315	A.I.I. FILTERED EXHAUST	19	350	[170]	1.35	[340]	2	[500]	BAG IN / BAG OUT	1	12	[300]	N/A	----
(EF-30 PRE)	ROOF	ISOLATION ROOM 346	A.I.I. FILTERED EXHAUST	8	376	[180]	0.31	[78]	1	[250]	BAG IN / BAG OUT	1	2	[50]	N/A	----
(EF-30 FIN)	ROOF	ISOLATION ROOM 346	A.I.I. FILTERED EXHAUST	19	376	[180]	1.35	[340]	2	[500]	BAG IN / BAG OUT	1	12	[300]	N/A	----